

INDEX OF SHEETS	
No.	DESCRIPTION
A Sheets	Title Sheets
A.1	Title Sheet
A.2	Location Map Sheet
B Sheets	Typical Cross Sections and Details
B.1 - 3	Typical Cross Sections and Details
C Sheets	Quantities and General Information
C.1	Estimated Project Quantities and Reference Notes
C.1	Standard Road Plans
C.1	Index of Tabulations
C.1	General Notes
C.1	Tabulations
D Sheets	Mainline Plan and Profile Sheets
* D.1	Plan & Profile Legend & Symbol Information Sheet
* D.2 - 3	US 20 Plan & Profile
G Sheets	Survey Sheets
G.1	Reference Ties and Bench Marks
* G.2	Reference Ties and Bench Marks
G.3	Reference Ties and Bench Marks
G.4	Horizontal Control Tab. & Super for all Alignments
J Sheets	Traffic Control and Staging Sheets
J.1	Traffic Control Plan
* J.2 - 6	Staging and Traffic Control Sheets
* J.7	Crossovers Layout
R Sheets	Erosion Control Sheets
RC.1 - 4	Est. Quantities, PPP, General Notes and Tabulations
* RR.1	Erosion Control Legend and Symbol Information Sheet
* RR.2 - 7	Drainage Basin and Erosion Control Device Maps
V Sheets	Bridge and Culvert Situation Plans
* V.1 - 2	Bridge and Culvert Situation Plans
W Sheets	Mainline Cross Sections
* W.1	Cross Sections Legend & Symbol Information Sheet
* W.2 - 14	Mainline Cross Sections
	* Color Plan Sheets



PLANS OF PROPOSED IMPROVEMENT ON THE
PRIMARY ROAD SYSTEM
DUBUQUE COUNTY
Improvement of Crossing
Westbound U.S. 20 bridge
over the North Fork Maquoketa River
0.6 mile west of IA 136

SCALES: As Noted

Refer to the Proposal Form for list of applicable specifications.

Value Engineering Saves. Refer to Article 1105.14 of the Specifications.



REVISIONS

PROJECT IDENTIFICATION NUMBER	TOTAL
	47
21-31-020-020	
PROJECT NUMBER	
BRF-020-9(269)--38-31	
R.O.W. PROJECT NUMBER	

Paddling Portage Detour will be required since river is a DNR paddling route. Need signage in J sheets. Requested info through Tom Lovan 9/25/2023.

Salvage existing steel beam guardrail and deliver to Dyersville DOT Maintenance shop. Separate Cost Division is needed per design manual due to Federal Funding.

DESIGN DATA RURAL			
20 21	AADT	10,900	V.P.D.
20 46	AADT	15,300	V.P.D.
20 46	DHV	1,580	V.P.H.
TRUCKS		17	%
Total			
Design ESALs		--	




INDEX OF SEALS		
SHEET NO.	NAME	TYPE
A.1	X	Primary Signature Block
V.1 / V.2	Mark D. Werner	Hydraulics
X	X	X



PRELIMINARY PLANS


Subject to change by final design.

D05 Plan, Date: 12/22/2023

US 20 IMPROVEMENT OF CROSSING
FHWA NO. 23780
MAINT. 3193.5L020
STA. 25+58.71








Full Depth PCC Combination Shoulder

Shoulder Jointing:
Longitudinal joint: BT-2, L-2 or KT-2
Transverse joints: C at 17' spacing

4_C_FullPCC_04-20-21				
Direction of Travel	BEGIN STATION	END STATION	(P) Feet	(G) Feet
EB	8+44.76	22+72.23	4	2
EB	29+69.08	31+53.91	4	2

US 20 EB SHOULDER STRENGTHENING

US 20 EB



PLAN VIEW


9" HMA Paved Shoulder at guardrail. 8" PCC may be substituted with the following jointing layout:

Match mainline pavement joint spacing. When mainline pavement is 8" or greater in thickness, place additional transverse 'C' joints in shoulder at mid-panel of the mainline pavement. Place longitudinal 'C' joint at P/2 from edge of mainline pavement when P is greater than 10' wide. Terminate longitudinal joint at transverse joint less than 10' in length.


Compaction of HMA is required to face of guardrail post. Hand compaction will be allowed under guardrail. Removal and reinstallation of guardrail will be allowed with no additional payment.

Refer to Tabulation 112-9 for shoulder quantities.


- ① PCC option only: When guardrail posts are installed prior to construction of PCC paved shoulder, fasten form board to the face of guardrail posts for the length shown.
- ② Continue paved shoulder 20 feet beyond the center of the first post.
- ③ Shoulder may be notched for first 2 posts or post sleeves may be installed through pavement. Do not drive posts through pavement.
- ④ 'KT' (per PV-101) joint for PCC shoulder. 'B' (per PV-101) joint for HMA shoulder.
- ⑤ Match shoulder slope.
- ⑥ The Contractor has the option to pave the paved shoulder at guardrail and the full width paved shoulder as one operation.
- ⑦ Refer to other details in the plan.




NEW CONSTRUCTION




Section B-B



EXISTING SHOULDER



Section B-B

PAVED SHOULDER AT GUARDRAIL
(ADJACENT TO FULL WIDTH PAVED SHOULDER)

ESTIMATED ROADWAY QUANTITIES (1 DIVISION PROJECT)						100-0A 10-28-97
Item No.	Item Code	Item	Unit	Total	As Built Qty.	

ESTIMATE REFERENCE INFORMATION			100-4A 10-29-02
Item No.	Item Code	Description	

STANDARD ROAD PLANS			105-4 10-18-11
The following Standard Road Plans apply to construction work on this project.			
Number	Date	Title	
BA-200	04-20-21	Steel Beam Guardrail Components	
BA-201	10-18-22	Steel Beam Guardrail Barrier Transition Section (MASH TL-3)	
BA-202	10-20-15	Steel Beam Guardrail Bolted End Anchor	
BA-205	10-17-23	Steel Beam Guardrail Tangent End Terminal (MASH TL-3)	
BA-250	04-20-21	Steel Beam Guardrail Installation at Concrete Barrier or Bridge End Post (MASH TL-3)	
BR-203	10-19-21	Double Reinforced 12" Approach	
DR-212	04-21-20	Beveled Pipe and Guard	
DR-303	10-17-17	Subdrains (Longitudinal)	
DR-306	10-17-23	Precast Concrete Headwall for Subdrain Outlets	
DR-402	04-19-22	Rock Flume for Bridge End Drain	
DR-504	04-21-20	Diagonal Placed Drain for Median Crossovers	
EC-201	04-20-21	Silt Fence	
EC-204	10-19-21	Perimeter, Slope and Ditch Check Sediment Control Devices	
EC-301	10-18-22	Rock Erosion Control (REC)	
EC-502	04-21-15	Seeding in Rural Areas	
EW-201	04-19-16	Bridge Berm Grading without Recoverable Slope (Barnroof Section)	
EW-301	04-20-21	Guardrail Grading	
EW-403	04-18-17	Temporary Erosion Control Measures	
PM-110	04-21-20	Line Types	
PM-111	04-21-20	Symbols and Legends	
PV-12	10-20-20	Milled Shoulder Rumble Strips	
PV-101	04-19-22	Joints	
PV-102	04-21-20	PCC Curb Details	
PV-501	04-21-20	Median Crossover (50' Median) 16' Wide 1 Lane	
SI-173	04-19-16	Object Markers	
SI-211	10-18-22	Object Marker and Delineator Placement with Guardrail	
SI-881	04-16-19	Special Signs for Workzones	
TC-1	10-15-19	Work Not Affecting Traffic (Two-Lane or Multi-Lane)	
TC-61	10-17-23	Two-Lane, Two-way Operation	
TC-252	04-21-20	Routes Closed to Traffic	
TC-402	04-18-23	Work Within 15 ft of Traveled Way	
TC-418	04-18-23	Lane Closure on Divided Highway	
TC-420	10-16-18	Lane Closure at Ramps	
TC-432	10-17-17	Shoulder Rumble Strip Operations	
TC-433	10-17-17	Pavement Marking Operations	

EXISTING PAVEMENT																						102 04-18-
No.	Location					Year	Type	Project Number	Surface		Base		Subbase		Removal		Coarse Aggregate			Reinforcement	Remarks	
	County	Route	Dir. of Travel	Begin Ref. Loc. Sign	End Ref. Loc. Sign				Type	Depth	Type	Depth	Type	Depth	Type	Depth	Source	Type	Durability Class	Type		
																						IN
	Dubuque	US-20	EB	293.16	294.55	2023	M	HSIPX-020-8(56)--3L-28													HMA PAVED SHOULDER	
						2017		MP-020-6(706)283--76-28	PCC	10											PCC Patching	
						1987		F-20-9(66)--20-31	PCC	10	ECB	4					SUNDHEIM	C.LST	I			
	Dubuque	US-20	WB	293.15	294.55	2023	M V S	HSIPX-020-8(56)--3L-28													HMA PAVED SHOULDER	
						2017		MP-020-6(706)283--76-28	PCC	10											PCC Patching	
						2013		NHSN-020-8(49)--3H-28	HMA	1.5	HMA	1			SCR	1					HMA overlay last 0.3mi	
						2000		MP-20-6(701)283--76-28	MSS													
						1988		NA	PCC	10	CTB	4										

MEDIAN CROSSOVERS														112-8 04-15-14
Refer to PV-500 Series.														
* Not a bid item														
Road Ident.	Location Station	Standard Road Plan	Detour Pavement	Special Backfill	Granular Shoulder	Embankment in Place	Class 10 Excavation	Class 13 Excavation	Removal of Pavement	Saw Cut*	18" Unclassified Roadway Pipe	36" CMP Slotted Drain/ 6" Grate	Beveled Pipe and Guard	Remarks
		No.	SY	TON	TON	CY	CY	CY	SY	LF	LF	LF	No.	
US 20	3+76.03	PV-501	1140.0	555.0	200.0	267.2	384.5		1298.2	1456.0	250.0		2	
US 20	36+22.56	PV-501	1140.0	555.0	200.0	267.2	384.5		1298.2	1456.0	250.0		2	
		Totals:	2280.0	1110.0	400.0	534.3	768.9		2596.4	2912.0	500.0		4	

SURVEY SYMBOLS

	AST, Above Ground Storage Tank		PR, Electric Riser Pole
	BB, Billboard		PRO, Profile Shot
	BBB, Bottom of Bridge Beam		PT, Curve Point
	BCL, Bridge Centerline		REF, Reference Tie Point
	BD, Bridge Deck		RET, Retaining Walls
	BIN, Grain Bin		RIP, Rip-Rap
	BL, Topo Breakline		ROC, Rock Outcropping
	BLD, Building or Foundation		ROW, Right of Way Mark
	BLS, Bridge Low Steel		RR, Centerline of Railroad Tracks
	BM, Bench Mark		RRB, Railroad Signal Box
	BNK, Stream Bank		RRF, Railroad Frog
	BRG, Bridge		RRR, Railroad Rail
	C, Centerline BL of Road -ML or SR		RRS, Railroad Signal
	CAV, Cave		RRW, Railroad Switch
	CEL, Cell Phone Tower		RT, Radio Tower
	CIS, Cistern		S, Soil Sampling Site -Wetlands
	CON, Concrete or A/C Slab		SBR, Size of Bridge
	CP, Control Point		SC, Spiral Point
	CRP, Corporation Line		SCR, Section Corner
	CS, Curve Point		SEP, Septic Tank
	CU, Back of Curb		SF, Silt Fence -Wetlands
	CUL, Culvert		SG, Staff Gauge -Wetlands
	D, Centerline Draw or Stream -Down		SH, Paved Shoulder
	DAB, Drainage Area Boundary		SHR, Shrub
	DIK, Centerline of Dike or Dam		SI, Sign
	DTM, Photogrammetry Elv Control Check		SL, Speed Limit Sign
	DU, Centerline Draw or Stream -Up		SLN, Section Line
	EB, Electrical Box		SLO, Silo
	EG, Edge of Gravel Road		SNK, Sink Hole
	ENP, Edge Paved Entrance and Park Lot		SNP, Unpaved Shoulder
	ENT, Centerline BL of Entrance		SP, Stream Profile
	ENU, Edge Unpaved Entrance and Parking		STP, Stump
	EP, Edge of Paved Roads -ML or SR		SWK, Sidewalk
	EW, Edge of Water		SWP, Swamp or Marsh
	FCL, Chain Link and Security Fence		TA, Tower Anchor
	FENO, FENO Monument		TBO, Telephone Booth
	FHD, Fire Hydrants		TCB, Traffic Signal Box
	FLG, Flag Poles		TDC, Tree Deciduous
	FP, Filler Pipe		TDL, Trafic Detection Loop
	FW, Wire Fence		TER, Terrace
	FWD, Wood Fence		TEV, Evergreen Tree
	GDC, Guard Rail Cable		TFR, Tree Fruit
	GDL, Guard Rail Steel		TGP, Telegraph Pole
	GP, Guard Post -Less Than 4 Posts		TIL, Tile Line
	GPR, Guard Post -4 or More Posts		TLNL, Tree Line Left
	GR, Ground Shot		TLNR, Tree Line Right
	GRV, Grave		TOP, Top of Bridge Pier
	GU, Gutter In Front of Curb		TPA, Telephone Pole Co. 1
	GV, Gas Valve		TPB, Telephone Pole Co. 2
	HDG, Hedge Row		TPC, Telephone Pole Co. 3
	HS, Hydric Soil -Wetlands		TR, Telephone Riser Pole
	HT, Electrical Highline Tower		TRL, Trail
	IN, Storm Sewer Intake		TS, Spiral Point
	INB, Storm Sewer Beehive Intake		TSB, Telephone Switch Box
	LC, Lot Corner		TSG, Traffic Signal
	LIN, Miscellaneous Line		TSL, Traffic Signal and Luminare
	LP, L.P. Tank		TV, Satellite TV Dish
	LUM, Luminaire		TVP, TV Pedestal
	MH, Utility Access -Manhole		TW, Top of Water
	MIS, Miscellaneous		UB, Utility Box
	MM, Mile Marker Post		UE, Utility Elevation
	OUT, Tile Outlet		UPH, Utility Pot Hole - Quality A
	PC, Curve Point		UST, Underground Tank
	PCP, Photo Control Point		UV, Underground Utility Vault
	PCT, Photo Control Target		VS, Channel Cross Section
	PI, Tangent Point		WC, Wild Card -Misc. Field Shot
	PIP, Pipe Culvert		WEL, Well
	PL, Location of Photo -Wetlands		WHD, Water Hydrant
	PLG, Location of General Photo		WHU, RV Water Hook Up
	POC, Curve Point		WM, Wind Mill
	POST, Spiral Point		WND, Wind Turbine
			WV, Water Valve

SURVEYED UTILITY OWNER SYMBOLS

Sub-Surface Utility Mapping Quality Level is in accordance with C/ASCE 38-02 Standard
Guidelines for the Collection and Depiction of Existing Subsurface Utility Data.

Remark Abbreviations
QLA Quality Level A Highest guideline quality level
QLD Quality Level D Lowest guideline quality level

	ELIC, ALLIANT ANERGY - Quality C Mary Montgomery 319-786-4768 marymontgomery@alliantenergy.com
	SAIC, CITY OF DYERSVILLE- Quality C John Wandsnider 563-875-7724 jwandsnider@cityofdyersville.com
	WLIC, CITY OF DYERSVILLE - Quality C John Wandsnider 563-875-7724 jwandsnider@cityofdyersville.com
	FO1C, IOWA COMMUNICATIONS NETWORK - Quality C Tim Flickinger 515-725-4699 timothy.flickinger@icn.state.ia.us
	FO2C, MAQUOKETA VALLEY ELECTRIC CO-OP - Quality C Nic Schulte P.O. Box 370 Anamosa, IA 52205 319-462-3541 nschulte@mvec.com

PLAN VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS

LINEWORK	Design	Color	No.	
Green	(2)		Existing Topographic Features and Labels	
Blue	(1)		Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation	
Magenta	(5)		Existing Utilities	
SHADING	Design	Color	No.	
Lavender	(9)		Temporary Pavement Shading	
Yellow	(4)		Proposed Pavement Shading	
Orange	(6)		Proposed Granular Shading	
Orange	(70)		Proposed Shoulder Granular Shading	
Yellow	(68)		Proposed Shoulder Paved Full Depth Shading	
Yellow	(132)		Proposed Shoulder Paved Partial Depth Shading	
Gray, Dark	(112)		Proposed Grade and Pave Shading "In conjunction with a paving project"	
Brown, Light	(236)		Grading Shading	
Orange, Light	(134)		Proposed Granular Entrance Shading	
Yellow	(220)		Proposed Paved Entrance Shading	
Tan	(8)		Proposed Sidewalk Shading	
Blue, Light	(230)		Proposed Sidewalk Landing Shading	
Pink	(11)		Proposed Sidewalk Ramp Shading	
Green, Light	(225)		Existing Pavement Shading	
Red	(3)		Proposed Structure Shading	
Red	(3)		Delineates Restricted Areas	

PROFILE VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS

LINEWORK	Design	Color	No.	
Green	(10)		Existing Ground Line Profile	
Blue	(1)		Proposed Profile and Annotation	
Magenta	(5)		Existing Utilities	
Blue, Light	(230)		Proposed Ditch Grades, Left	
Black	(0)		Proposed Ditch Grades, Median	
Rust	(14)		Proposed Ditch Grades, Right	

	Reference Point		Survey Line
	Station		
	Section Corner		
	Ground Line Intercept		
	Saw Cut		
	Guardrail		
	Trench Drain		
	HighTension Cable Guardrail		
	Sheet Pile		
	Pavement Removal		Clearing & Grubbing Area

RIGHT-OF-WAY LEGEND


- Proposed Right-of-Way
- Existing Right of Way
- Existing and Proposed Right-of-Way
- Easement and Existing Right-of-Way
- Easement (Temporary)
- Easement
- Access Control
- Property Line

PLAN AND PROFILE
LEGEND AND SYMBOL
INFORMATION SHEET


(COVERS SHEET SERIES D, E, F, & K)

Refer to W sheets
for superelevation
runout at west
end of west
approach pavement.

During Field Exam,
DOT mentioned that
going forward, bridge
reconstruction projects
should construct 300 ft
of full depth/full width
shoulders at all four
corners of bridge.



Refer to V sheets for
notes regarding Steel
Beam Guardrail
connections to East
end of EB US 20 bridge.



Survey Information

SURVEY INDEX

County: Dubuque
PIN: 21-31-020-020
Project Number: BRF-020-9(269)--38-31
Location: N. Fork Maquoketa River 0.6 Mi W of IA 136 (WB)
Type of Work: Bridge Replacement

(U.S. SURVEY FOOT)
VERTICAL DATUM: NAVD88
GEOID MODEL: GEOID12B

Alignment Information

NO alignment

Survey Personnel

Matthew Fouts – PLS
Daniel Marti – PLS
Drake Marti – Survey Technician
Joshua Randolph – Survey CADD Technician

Date(s) of Survey

Begin Date 01/31/2023
End Date 02/06/2023

General Information

This survey is for preliminary design for the section of approximately 0.2 miles of roadway, there is one bridge along the route. Project datum is provided by Design Survey Office. This project is a full DTM Survey.

Utility Information

For logging data and other utility details see Utility Survey and Ownership Report in the Utility folder of the PrelimSurvey project directory.

Project Control

(RTN)
Nearby Iowa Real Time Network reference stations were utilized to obtain horizontal and vertical control on primary project control points. For additional details of the control survey, contact the Preliminary Survey department.

(Static)
Static observations were not used for this survey.

PROJECT DATUM: NAD83(2011) for EPOCH 2010.00
COORDINATE SYSTEM: IOWA REGIONAL COORDINATE SYSTEM ZONE 11
(Dubuque / Davenport).

CONTROL POINT VICINITY MAP

This map is a guide to the vicinity of the primary project control points. Primary control is for use with RTK base stations and for RTN validation. Future surveys will use primary project control to establish temporary control as needed for construction or other surveying applications.



HORIZ. DATUM: NAD83(2011) for EPOCH 2010.00 (IaRTN 2019 Adjustment) - Iowa RCS Zone 11 (U.S. Survey Foot)

VERT. DATUM: NAVD88 - Geoid Model: 12B

Coordinate listing from next sheet will be used with IaRTN for monument recovery. No other reference ties are given.

HORIZONTAL AND VERTICAL PROJECT CONTROL COORDINATE LISTING
HORIZ. DATUM: NAD83(2011) for EPOCH 2010.00 (laRTN 2019 Adjustment)
la. Regional Coordinate System Zone 11 (U.S. Survey Foot)
VERT. DATUM: NAVD88
Geoid Model: 12B

POINT NAME	NORTHING	EASTING	ELEVATION	DESCRIPTION
CP2	8409852.23	21339787.30	954.00	SET 5/8" REBAR ON SOUTH SIDE OF WEST BOUND LANE ALONG HIGHWAY 20 WEST OF BRIDGE AND 250'+/- SOUTH OF CENTERLINE OF HIGHWAY 20
CP5	8409722.04	21340187.51	945.71	SET 5/8" REBAR ON EAST END OF THE BRIDGE ON TOP OF SLOPE
CP8	8409545.08	21340680.65	945.51	SET 5/8" REBAR ON WEST END OF THE BRIDGE ON TOP OF SLOPE
CP9	8409440.07	21341192.88	942.47	SET 5/8" REBAR 250'+/- EAST OF BRIDGE NORTH OF CENTERLINE OF HIGHWAY 20 OF WEST BOUND LANE
CP10	8409640.45	21340384.44	925.87	SET 5/8" REBAR ON SOUTH SIDE OF HIGHWAY 20 SECOND PIER FROM THE WEST ON TOP OF BANK WEST SIDE OF RIVER
CP11	8409721.85	21340368.23	926.15	SET 5/8" REBAR ON NORTH SIDE OF HIGHWAY 20 30'+/- NORTHWEST OF SECOND PIER TO THE WEST OF THE RIVER
CP12	8409844.05	21340282.00	924.78	SET FENO MONUMENT ON BOTTOM OF SLOPE NORTHWEST QUADRANT OF BRIDGE
CP13	8409906.92	21339795.01	953.71	SET FENO MONUMENT 1'+/- SOUTH OF REFLECTOR AND 5'+/- NORTH OF EDGE OF ROAD
CP14	8409484.42	21340902.67	943.62	SET FENO MONUMENT AT CORNER OF ASPHALT SHOULDER WEST END OF BRIDGE
BM200	8409609.80	21340115.53	942.76	WEST BOLT ON FIRE HYDRANT SOUTH OF HIGHWAY 20 WEST END OF BRIDGE AT RIGHT OF WAY
NGS15	8405441.28	21361006.04	1059.04	FOUND NGS MONUMENT B73 1934

ALIGNMENT COORDINATES																		101-16 10-20-09	
Name	Location	Point on Tangent		Begin Spiral		Begin Curve		Simple Curve PI or Master PI of SCS		End Curve		End Spiral							
		Station	Coordinates		Station	Coordinates		Station	Coordinates		Station	Coordinates		Station	Coordinates				
			Y (Northing)	X (Easting)		Y (Northing)	X (Easting)		Y (Northing)	X (Easting)		Y (Northing)	X (Easting)		Y (Northing)	X (Easting)			
1	US 20 (ML020)	+00.00	8409929.69	21337927.47															
2	US 20 (ML020)						12+10.76	8409919.86	21339138.19	16+64.31	8409916.18	21339591.72	21+10.19	8409770.86	21340021.36				
3	US 20 (ML020)						39+25.98	8409189.06	21341741.42	44+52.24	8409020.44	21342239.93	49+67.18	8409037.60	21342765.91				
4	US 20 (ML020)	115+61.56	8409252.69	21349356.77															
1	US 20 (WB20_PGL)	21+10.19	8409794.54	21340029.37															
2	US 20 (WB20_PGL)	39+25.98	8409212.74	21341749.43															

101-17 04-19-11																
SPIRAL OR CIRCULAR CURVE DATA																
Name	Location	ΔSCS	Horizontal Alignment Data												Remarks	
			Spiral Data								Curve Data					
			θS	Ls	Ts	Es	Xc	Yc	L.T.	S.T.	ΔC	T	L	R		E
C1	US 20 (ML020)										18.223°	453.545	899.430	2828.000	36.138	
C2	US 20 (ML020)										20.557°	526.257	1041.200	2902.000	47.331	

108-23A 08-01-08 TRAFFIC CONTROL PLAN 1. At least one lane of traffic in both directions shall be maintained on US 20 at all times. 2. Refer to Standard Road Plans shown on Tab 105-4 in C Sheets for other information. 3. Refer to Staging Notes (Tabulation 108-26A) and other J sheets for details of specific closures. 4. All interchange ramps shall be maintained at all times.

111-01
04-17-12


COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
None provided	

108-26A 08-01-08 STAGING NOTES Stage 1 Traffic Control: Close US 20 EB and WB inside lanes. Maintain outside lanes of traffic in both directions. Construction: Construct west and east median crossovers (PV-501); also construct shoulder and guardrail for eastbound bridge trailing side. Construct shoulder strengthening on EB inside shoulder between the median crossovers. Stage 2 Traffic Control: Close US 20 westbound. Maintain 2-lane 2-way traffic in the eastbound lanes between west and east crossovers. Construction: Improve US 20 westbound bridge, approaches, shoulder and guardrail.
--

108-25 10-21-14												
511 TRAVEL RESTRICTIONS												
Route	Direction	County	Location Description	Feature Crossed	Object Type	Maint. Bridge No., Structure ID, or FHWA No.	Type of Restriction	Existing Measurement	Construction Measurement	Construction Measurement as Signed	Projected As Built Measurement	Remarks
None												



See Sheets 2 and 4 for Details

See Sheets 3 and 4 for Details

OVERVIEW OF CROSSOVER

Place Two-Way Traffic symbol and DO NOT PASS signs alternately on both sides of the roadway at a maximum of one-half mile intervals for both directions of travel. Always have signs in sight of motorists.


Contract Items:

- Painted Symbols and Legends
Pavement Marking Items
Pavement Marking Removed
Safety Closures
- Temporary Floodlighting
Temporary Lane Separator System
Traffic Control


Tabulations:

108-13A, 108-22, 108-27, 108-29, 108-30, 108-33, 108-35

MODIFIED STANDARD ROAD PLAN	REVISION	
	17	10-17-23
	TC-61	
SHEET 1 of 5		
MODIFICATIONS: Added westbound interchange ramps on sheet 5 of 5. Deleted original sheets 5 and 6.		
TWO-LANE, TWO WAY OPERATION		



MODIFIED STANDARD ROAD PLAN	REVISION	
	17	10-17-23
	TC-61	
SHEET 2 of 5		
MODIFICATIONS: Added westbound interchange ramps on sheet 5 of 5. Deleted original sheets 5 and 6.		
TWO-LANE, TWO WAY OPERATION		



See sheet 4 for supplemental drawings.

① Refer to [SI-881](#) for sign details.

② Refer to [PM-111](#) for arrow details.

③ Space Speed Limit signs at one-mile intervals.

④ Install an additional supplemental plaque with the message NEXT X MILES on the Two-Way Traffic symbol sign assembly on the right side of the roadway to inform motorists of the remaining length of two-lane traffic. Round X to the nearest whole-mile increment.

⑥ For roadways with a posted speed limit of 60 mph or greater before road work:

Place SPEED LIMIT AHEAD sign and SPEED LIMIT 55 sign prior to the lane closure as shown. Place SPEED LIMIT 65 or 70 beyond the work area as shown.

Remove or cover all existing signs that conflict with 55 mph speed limit while 55 mph speed limit is in effect.

Place Speed Feedback Sign at the end of the merge taper.

⑦ Add below R11-2 already included in Safety Closure.


LEGEND



	Traffic Sign		Arrow Board
	Drum		Safety Closure (Refer to TC-252)
	42" Channelizer		Temporary Floodlighting
	Tubular Marker		Work Area
	Temporary Lane Separator System		Direction of Traffic
	Speed Feedback Sign		Detour Pavement

FILE NO. TBD	ENGLISH	DESIGN TEAM Stanley Consultants Inc.	DUBUQUE COUNTY	PROJECT NUMBER BRF-020-9(269)--38-31	SHEET NUMBER J.4
--------------	---------	--------------------------------------	----------------	--------------------------------------	------------------

10:50:55 AM 10/25/2023 9589 pw:\projectwise.dot.int.lan:PWMain\Documents\Projects\3102002021\Design\CADD_Files\Sheet_Files\SHT_31020269_J02.dgn

MODIFIED STANDARD ROAD PLAN	REVISION	
	17	10-17-23
TC-61		
SHEET 3 of 5		
MODIFICATIONS: Added westbound interchange ramps on sheet 5 of 5. Deleted original sheets 5 and 6.		
TWO-LANE, TWO WAY OPERATION		









CROSSOVERS LAYOUT

SILT BASINS
Possible Standard: EW-403





* The functional height used in the volume equation is 95% of effective height. Effective height is 3 feet as shown in EW-403.
* Volume equation: $(0.5 * \text{Length} * (\text{Width} * \text{Height} + \text{Width} * (\text{Height} - \text{Length} * \text{Avg} \% \text{Slope})))$

Basin No.	Location		Bid Items		Stormwater Storage Volume Summary					Remarks
	Station	Side	Installation	Removal	Basin Width FT	Basin Length FT	Height	Avg. % Slope	Volume*	
			EACH	EACH			FT		CF	
1	19+57.00	Med	1	1	10.0	50.0	2.85	1.5%	1237.5	
2	23+63.00	Med	1	1	10.0	50.0	2.85	2.2%	1150.0	
3	27+40.00	Med	1	1	10.0	50.0	2.85	0.7%	1337.5	
5	33+92.00	Med	1	1	10.0	50.0	2.85	0.2%	1400.0	
5	34+10.00	Med	1	1	10.0	50.0	2.85	0.2%	1400.0	
		Totals:	5	5						

SILT FENCES FOR DITCH CHECKS

Possible Standard: EC-201



* The functional height used in the volume equation is 85% of effective height. Effective height is 1.58 feet as shown on EC-201.
* Volume equation: $[0.5 * \text{Spacing} * (0.5 * H^2 * FS + DW * H + 0.5 * H^2 * BS)]$

Basin No.	Type	Location		Bid Items			Stormwater Storage Volume Summary						Remarks
		Station	Side	Installation	Maintenance	Removal	Foreslope	Backslope	Ditch Width	Avg.% Slope	Volume*		
				LF	LF	LF	FS:1	BS:1	FT	Ditch Grade	CF		
1	1	1+40.00	Med	20.0	2.0	20.0	10.0	10.0	10.0	1.1%	1573.3		
1	1	6+73.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	0.3%	4387.8		
1	1	7+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	0.7%	2159.1		
1	1	8+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.3%	1393.0		
1	1	9+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.3%	1393.0		
1	1	10+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	11+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	12+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	13+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	14+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	15+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	16+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	17+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
1	1	18+72.00	Med	24.0	2.4	24.0	8.0	8.0	10.0	1.5%	1393.0		
2	1	20+72.00	Med	24.0	2.4	24.0	8.0	8.0	1.0	1.7%	591.5		
2	1	21+72.00	Med	24.0	2.4	24.0	8.0	8.0	1.0	1.4%	788.6		
2	1	22+72.00	Med	24.0	2.4	24.0	8.0	8.0	1.0	1.4%	788.6		
3	1	27+57.00	Med	20.0	2.0	20.0	8.0	8.0	1.0	2.2%	473.2		
3	1	28+17.00	Med	20.0	2.0	20.0	8.0	8.0	1.0	2.2%	473.2		
5	1	28+77.00	Med	20.0	2.0	20.0	8.0	8.0	1.0	0.9%	788.6		
5	1	29+77.00	Med	20.0	2.0	20.0	8.0	8.0	3.3	1.0%	943.1		
5	1	30+77.00	Med	20.0	2.0	20.0	8.0	8.0	10.0	1.0%	1393.0		
5	1	31+77.00	Med	20.0	2.0	20.0	8.0	8.0	10.0	1.0%	1393.0		
5	1	38+88.00	Med	20.0	2.0	20.0	8.0	8.0	10.0	0.4%	2785.9		
		Totals:		544.0	54.4	544.0							

PERIMETER, SLOPE AND DITCH CHECK SEDIMENT CONTROL DEVICES									100-19 10-19-21
Location			Possible Standards: EC-204						
Begin Station	End Station	Side	Perimeter and Slope			Ditch Check		Remarks	
			Length of Installation			Length of Installation			
			9 inch Dia	12 inch Dia	20 inch Dia	12 inch Dia	20 inch Dia		
			LF	LF	LF	LF	LF		
+00.00	4+29.35	Med		550					
4+09.00	23+31.00	Med		1920					
19+71.00	23+30.00	Med		360					
19+66.00	23+30.00	Lt		370					
21+76.00	23+30.00	Lt		150					
22+00.00	23+30.00	Lt		160					
23+28.00	23+28.00	Lt		150					
23+59.00	23+59.00	Lt		150					
27+34.00	27+34.00	Lt		140					
27+64.00	27+64.00	Lt		140					
27+48.00	31+28.00	Lt		380					
27+41.00	30+91.00	Lt		350					
27+89.00	31+49.00	Med		360					
27+80.00	36+39.00	Med		860					
36+11.00	41+31.00	Med		520					
27+56.00	28+11.00	Rt		90					
27+77.00	30+07.00	Rt		230					
			Totals:	6880					

ROCK EROSION CONTROL														100-23 04-17-18
Refer to EC-301 and Detail 570-8														
Location				L	W	Rock Erosion Control (REC)					Material Bid Quantities			Remarks
Road Identification	Begin Station	End Station	Side			Type 1	Type 2	Type 3	Type 4	Type 5	Eng. Fabric	Class E Revetment	Erosion Stone	
						Rock Ditch Check	Rock Ditch	Rock Flume	Rock Splash Basin	Rock Slope Protection				
						Lt./Rt.	FT	FT	SY	TON				
US 20	1+62.54	1+62.54	Med	12	12				X		28.4	15.1		
US 20	2+51.60	2+51.60	Med	7	11				X		18.3	8.1		
US 20	5+00.00	5+00.00	Med	7	11				X		18.3	8.1		
US 20	20+01.83	20+01.83	Med	12	12				X		28.4	15.1		
US 20	24+03.28	24+03.28	Med	12	12				X		28.4	15.1		
US 20	34+00.00	34+00.00	Med	12	12				X		28.4	15.1		
US 20	35+00.00	35+00.00	Med	7	11				X		18.3	8.1		
US 20	37+47.00	37+47.00	Med	7	11				X		18.3	8.1		
					Totals:						186.8	92.8		

STORMWATER DRAINAGE BASIN AND STORAGE														100-34 10-17-17
Drainage Basin Location						Summary of Stormwater Storage							Remarks	
Basin No.	Station to Station		Side	Discharge Point		Total Disturbed Area	Disturbed Area with Storage Provided	Disturbed Area without Storage Provided	Best Management Practice	Total Storage Volume Provided	Total Storage Volume Required	Storage Volume Met?		
				Station	Side					CF	CF	Yes/No		
	Acres	Acres	Acres											
1	+00.00	20+12.88	Med	20+01.83	RT	1.3	1.3	0.0	Silt Fence for Ditch Check (EC-201)	23442.8	4680.0	Yes		
									Silt Basin (EW-403)	1237.5				
									Total	24680.3				
2	20+09.00	23+62.62	Both	23+61.00	Med	0.6	0.6	0.0	Silt Fence for Ditch Check (EC-201)	2168.7	2160.0	Yes		
									Silt Basin (EW-403)	1150.0				
									Total	3318.7				
3	27+40.00	31+08.20	Lt	27+42.50	Med	0.6	0.6	0.0	Silt Fence for Ditch Check (EC-201)	946.3	2160.0	Yes		
									Silt Basin (EW-403)	1337.5				
									Total	2283.8				
4	27+92.70	29+53.06	Rt	27+92.70	Rt	0.1	0.0	0.1	Vegetated Buffer	0.0	0.0	N/A		
5	28+35.50	40+91.13	Med	34+02.00	Rt	1.2	1.2	0.0	Silt Fence for Ditch Check (EC-201)	7303.5	4320.0	Yes		
									Silt Basin (EW-403)	2800.0				
									Total	10103.5				

110-12
10-20-20

POLLUTION PREVENTION PLAN

This project is regulated by the requirements of the Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) General Permit No. 2 OR an Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) individual storm water permit. The Contractor shall carry out the terms and conditions of this permit and the Pollution Prevention Plan (PPP).

This Base PPP includes information on Roles and Responsibilities, Project Site Description, Controls, Maintenance Procedures, Inspection Requirements, Non-Storm Water Controls, Potential Sources of Off Right-of-Way Pollution, and Definitions. This plan references other documents rather than repeating the information contained in the documents. A copy of this Base Pollution Prevention Plan, amended as needed during construction, will be readily available for review.

All contractors shall conduct their operations in a manner that controls pollutants, minimizes erosion, and prevents sediments from entering waters of the state and leaving the highway right-of-way. The Contractor shall be responsible for compliance and implementation of the PPP for their entire contract. This responsibility shall be further shared with subcontractors whose work is a source of potential pollution as defined in this PPP.

I. ROLES AND RESPONSIBILITES

A. Designer:

1. Prepares Base PPP included in the project plan.
2. Prepares Notice of Intent (NOI) submitted to Iowa DNR.
3. Is signature authority on the Base PPP. If consultant designed, signature from Contracting Authority is also required.

B. Contractor:

1. Signs a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP. All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
2. Designates a Water Pollution Control Manager (WPCM), who has the duties and responsibilities as defined in Section 2602 of the Standard Specifications.
3. Submits an Erosion Control Implementation Plan (ECIP) and ECIP updates according to Section 2602 of the Standard Specifications.
4. Installs and maintains appropriate controls. This work may be subcontracted as documented through Subcontractor Request Forms (Form 830231).
5. Supervises and implements good housekeeping practices according to Paragraph III, C, 2.
6. Conducts joint required inspections of the site with inspection staff. When Contractor is not mobilized on site, Contractor may delegate this responsibility to a trained or certified subcontractor. Contracting Authority also may waive joint inspection requirement during winter shutdown. In both circumstances, WPCM (or trained or certified delegate from the Contractor) is still responsible to review and sign inspection reports.
7. Complies with training and certification requirements of Section 2602 of the Standard Specifications.
8. Submits amended PPP site map according to Section 2602 of the Standard Specifications.

C. Subcontractors:

1. Sign a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP if: responsible for sediment or erosion controls; involved in land disturbing activities; or perorming work that is a source of potential pollution as defined in this PPP. Subcontracted work items are identified in Subcontractor Request Forms (Form 830231). All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
2. Implement good housekeeping practices according to Paragraph III, C, 2.

D. RCE/Project Engineer:

1. Is Project Storm Water Manager.
2. On projects where DOT is the Contracting Authority, is current with erosion control training or certification.
3. Takes actions necessary to ensure compliance with storm water requirements including, where appropriate, issuing stop work orders, and directing additional inspections at construction project sites that are experiencing problems with achieving permit compliance.
4. Orders the taking of measures to cease, correct, prevent, or minimize the consequences of non-compliance with the storm water requirements of the Applicable Permit.
5. Supervises all work necessary to meet storm water requirements at the Project, including work performed by contractors and subcontractors.
6. Requires employees, contractors, and subcontractors to take appropriate responsive action to comply with storm water requirements, including requiring any such person to cease or correct a violation of storm water requirements, and to order or recommend such other actions as necessary to meet storm water requirements.
7. Is familiar with the Project PPP and storm water site map.
8. On projects where DOT is Contracting Authority, is responsible for periodically monitoring inspection reports to determine whether deficiencies identified in inspection reports were adequately and timely addressed, and if not, has the authority and responsibility to direct immediate actions to correct the deficiencies.
9. Is the point of contact for the Project for regulatory officials, Inspector, contractors, and subcontractors regarding storm water requirements.
10. Is signature authority on Notice of Discontinuation.
11. Maintains an up-to-date record of contractors, subcontractors, and subcontracted work items through Subcontractor Request Forms (Form 830231).
12. Makes information to determine permit compliance available to the DNR upon their request.

E. Inspector:

1. Updates PPP through fieldbook entries and storm water site inspection reports if there is a change in design, construction, operation, or maintenance which has a significant effect on the discharge of pollutants from the project.
2. Makes information to determine permit compliance available to the DNR upon their request.
3. Conducts joint required inspections of the site with the contractor/subcontractor.
4. Completes an inspection report after each inspection.
5. Is signature authority on storm water inspection reports.

II. PROJECT SITE DESCRIPTION

A. This Pollution Prevention Plan (PPP) is for the construction of a River Crossing Improvement.

B. This PPP covers approximately 3.8 acres with an estimated 3.8 acres being disturbed.The portion of the PPP covered by this contract has 3.8 acres disturbed.

C. The PPP is located in an area of 1 soil association Dinsdale - Klinger. The estimated weighted average runoff coefficient number for this PPP after completion will be 0.40.

D. Storm Water Site Map is located in the R sheets. Proposed slopes are shown in cross sections, details, or standard road plans. Supplemental information is located in the Tabulations in the C or CE sheets.

E. The base storm water site map is amended by contract modifications and progress payments (fieldbook entries) of completed erosion control work. Also, due to project phasing, erosion and sediment controls shown on project plans may not be installed until needed, based on site conditions. For example, silt fence ditch checks will typically not be installed until the ditch has been installed. Installed locations may also be modified from tabulation locations by field staff. Installed locations will be

110-12
10-20-20

POLLUTION PREVENTION PLAN

documented by fieldbook entries and amended PPP site map.

F. Runoff from this work will flow into N. Fork Maquoketa River.

III. CONTROLS

A. The Contractor’s ECIP specified in Article 2602.03 of the Standard Specifications for accomplishment of storm water controls should clearly describe the intended sequence of major activities, and for each activity define the control measure and the timing during the construction process that the measure will be implemented.

B. Preserve vegetation in areas not needed for construction.

C. Sections 2601 and 2602 of the Standard Specifications define requirements to implement erosion and sediment control measures. Actual quantities used and installed locations may vary from the Base PPP and amendment of the plan will be documented via fieldbook entries, amended PPP site map, or by contract modification. Additional erosion and sediment control items may be required as determined by the inspector and/or contractor during storm water site inspections. If the work involved is not applicable to any contract items, the work will be paid for according to Article 1109.03 paragraph B of the Standard Specifications.

1. EROSION AND SEDIMENT CONTROLS

a. Stabilization Practices

- 1) Site plans will ensure that existing vegetation or natural buffers are preserved where attainable and disturbed portions of the site will be stabilized.
- 2) Initialize stabilization of disturbed areas immediately after clearing, grading, excavating, or other earth disturbing activities have:
 - a) Permanently ceased on any portion of the site, or
 - b) Temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days.
- 3) Staged permanent and/or temporary stabilizing seeding and mulching shall be completed as the disturbed areas are completed. Incomplete areas shall be stabilized according to paragraph III, C, 1, a, 2, b above.
- 4) Permanent and Temporary Stabilization practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation (105-4) in the C or R sheets.
- 5) Preservation of existing vegetation within right-of-way or easements will act as vegetative buffer strips.
- 6) Preservation of topsoil: Bid items to be used for this project are located in the Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets. Additional information may be found in the Tabulations in the C or T Tabulation sheets, or is referenced in Section 2105 of the Standard Specifications.

b. Structural Practices

- 1) Structural practices will be implemented to divert flows from exposed soils and detain or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Additionally, structural practices may include: silt basins that provide 3600 cubic feet of storage per acre drained or equivalent sediment controls, outlet structures that withdraw water from surface when discharging basins, and controls to direct storm water to vegetated areas.
- 2) Structural practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the devices to be used on this project can be found on the B or R sheets or are referenced in the Standard Road Plans Tabulation (105-4) located in the C or R sheets.

c. Storm Water Management

Measures shall be installed during the construction process to control pollutants in storm water discharges that will occur after construction operations have been completed. This may include velocity dissipation devices at discharge locations and along length of outfall channel as necessary to provide a non-erosion velocity flow from structure to water course. If included with this project, these items are located in the storm water site map and Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation. The installation of these devices may be subject to Section 404 of the Clean Water Act.

2. OTHER CONTROLS

Contractor disposal of unused construction materials and construction material wastes shall comply with applicable state and local waste disposal, sanitary sewer, or septic system regulations. In the event of a conflict with other governmental laws, rules and regulations, the more restrictive laws, rules or regulations shall apply.

a. Vehicle Entrances and Exits - Construct and maintain entrances and exits to prevent tracking of sediments onto roadways.

b. Material Delivery, Storage and Use - Implement practices to prevent discharge of construction materials during delivery, storage, and use.

c. Stockpile Management - Install controls to reduce or eliminate pollution of storm water from stockpiles of soil and paving.

d. Waste Disposal - Do not discharge any materials, including building materials, into waters of the state, except as authorized by a Section 404 permit.

e. Spill Prevention and Control - Implement chemical spill and leak prevention and response procedures to contain and clean up spills and prevent material discharges to the storm drain system and waters of the state.

f. Concrete Residuals and Washout Wastes - Waste shall not be discharged to a surface water and is not allowed to adversely affect a water of the state. Designate temporary concrete washout facilities for rinsing out concrete trucks. Provide directions to truck drivers where designated washout facilities are located. Designated washout areas should be located at least 50 feet away from storm drains, streams or other water bodies. Care should be taken to ensure these facilities do not overflow during storm events.

g. Concrete Grooving/Grinding Slurry - Do not discharge slurry to a waterbody or storm drain. Slurry may be applied on foreslopes or removed from the project.

h. Vehicle and Equipment Storage and Maintenance Areas - Perform on site fueling and maintenance in accordance with all environment laws such as proper storage of onsite fuels and proper disposal of used engine oil or other fluids on site. Employ washing practices that prevent contamination of surface and ground water from wash water. Wash waters must be treated in a sediment basin or alternative control that provides equivalent or better treatment prior to discharge.

i. Litter Management - Ensure employees properly dispose of litter. Minimize exposure of trash if exposure to precipitation or storm water would result in a discharge of pollutants.

j. Dewatering - Properly treat water to remove suspended sediment before it re-enters a waterbody or discharges off-site. Measures are also to be taken to prevent scour erosion at dewatering discharge point.

3. APPROVED STATE OR LOCAL PLANS

During the course of this construction, it is possible that situations will arise where unknown materials will be encountered. When such situations are encountered, they will be handled according to all federal, state, and local regulations in effect at the time.

IV. MAINTENANCE PROCEDURES

FILE NO.

ENGLISH

DESIGN TEAM

Stanley Consultants Inc.

DUBUQUE COUNTY

PROJECT NUMBER

BRF-020-9(269) -- 38-31

SHEET NUMBER

RC.3

10/20/2023

9:59:14 AM

9589

c:\pw_work\pwwmain\xingwei.weng\d1186596\SHF_31020269_RC01.xlsm

POLLUTION PREVENTION PLAN

The Contractor is required to maintain all temporary erosion and sediment control measures in proper working order, including cleaning, repairing, or replacing them throughout the contract period. This shall begin when the features have lost 50% of their capacity.

V. INSPECTION REQUIREMENTS

- A. Inspections shall be made jointly by the Contractor and the Contracting Authority's inspector at least once every seven calendar days. Storm water site inspections will include:
- 1. Date of the inspection.
 - 2. Summary of the scope of the inspection.
 - 3. Name and qualifications of the personnel making the inspection.
 - 5. Review of erosion and sediment control measures within disturbed areas for the effectiveness in preventing impacts to receiving waters.
 - 6. Major observations related to the implementation of the PPP.
 - 7. Identification of corrective actions required to maintain or modify erosion and sediment control measures.
- B. Include storm water site inspection reports in the Amended PPP. Incorporate any additional erosion and sediment control measures determined as a result of the inspection. Immediately begin corrective actions on all deficiencies found within 3 calendar days of the inspection and complete within 7 calendar days following the inspection. If it is determined that making the corrections less than 72 hours after the inspection is impracticable, it should be documented why it is impracticable and indicate an estimated date by which the corrections will be made.

VI. NON-STORM WATER DISCHARGES

This includes subsurface drains (i.e. longitudinal and standard subdrains) and slope drains. The velocity of the discharge from these features may be controlled by the use of headwalls or blocks, Class A stone, erosion stone or other appropriate materials. This also includes uncontaminated groundwater from dewatering operations, which will be controlled as discussed in Section III of the PPP.

VII. POTENTIAL SOURCES OF OFF RIGHT-OF-WAY (ROW) POLLUTION

Silts, sediment, and other forms of pollution may be transported onto highway right-of-way (ROW) as a result of a storm event. Potential sources of pollution located outside highway ROW are beyond the control of this PPP. Pollution within highway ROW will be conveyed and controlled per this PPP.

VIII. DEFINITIONS

- A. Base PPP - Initial Pollution Prevention Plan.
- B. Amended PPP - Base PPP amended during construction. May include Plan Revisions or Contract Modifications for new items, storm water site inspection reports, fieldbook entries made by the inspector, amended PPP site map by the Contractor, ECIP, NOI, co-permittee certifications, and Subcontractor Request Forms. Items amending the PPP are stored electronically and are readily available upon request.
- C. Fieldbook Entries - This contains the inspector's daily diary and bid item postings.
- D. Controls - Methods, practices, or measures to minimize or prevent erosion, control sedimentation, control storm water, or minimize contaminants from other types of waste or materials. Also called Best Management Practices (BMPs).
- E. Signature Authority - Representative authorized to sign various storm water documents.

CERTIFICATION STATEMENT

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature



Printed or Typed Name

Signature

LINE STYLE LEGEND OF LANDSCAPE SHEETS		
LINESTYLE	Design Element	
-----	Living Snow Fence Single Row	
-----	Living Snow Fence Double Row	
-----	Mechanical Edge	

CELL LEGEND OF LANDSCAPE SHEETS		
CELL	Design Element	Plant Diameter
+	Clearing	
•	Proposed Shrub	6 FT
•	Proposed Understory Tree	12 FT
•	Proposed Conifer Tree	18 FT
•	Proposed Overstory Tree	30 FT

PATTERN LEGEND OF LANDSCAPE SHEETS	
	Brush Clearing
	Spray Area
	Clearing & Grubbing

LINE STYLE LEGEND OF EROSION CONTROL SHEETS	
LINESTYLE	Design Element
	Silt Fence
	Perimeter and Slope Sediment Control Device (9")
	Perimeter and Slope Sediment Control Device (12")
	Perimeter and Slope Sediment Control Device (20")
	Open-Throat Curb Intake Sediment Filter
	Concentrated Flow
	Rock Check and Rock Check Dam
	Sheet Flow

CELL LEGEND OF EROSION CONTROL SHEETS	
CELL	Design Element
	Temporary Sediment Control basin
	Erosion Control for Circular Intake or Manhole Well
	Erosion Control for Rectangular Intake or Manhole Well
	Grate Intake Sediment Filter Bag
	Silt Basin
	Silt Fence Tail
	Stormwater Drainage Basin Discharge Point

PLAN VIEW COLOR LEGEND OF EROSION CONTROL SHEETS				
LINEWORK	Design	Color No.		
Green	(2)		Existing Topographic Features and Labels	
Blue	(1)		Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation	
Magenta	(5)		Existing Utilities	
Black	(0)		Permanent Erosion Control Features	
Blaze Orange	(222)		Temporary Erosion Control Features	
SHADING	Design	Color No.	Transparency	
Citron	(234)		Mulching, All Types	50%
Light Brown	(238)		Special Ditch Control, Wood Excelsior Mat	0%
Grass Green	(233)		8FT Mow Strip	50%
Red	(3)		Delineates Restricted Areas	0%


PATTERN LEGEND OF EROSION CONTROL SHEETS	
	Seeding and Fertilizing
	Seeding and Fertilizing (Rural)
	Seeding and Fertilizing (Urban)
	Native Grass Seeding
	Salt Tolerant Seeding
	Wetland Grass Seeding
	Wildflower Seeding
	Sodding
	Turf Reinforcement Mat Type 1
	Turf Reinforcement Mat Type 2
	Turf Reinforcement Mat Type 3
	Turf Reinforcement Mat Type 4
	Slope Protection, Wood Excelsior Mat
	Transition Mat
	Rock Features, Permanent
	Rock Features, Temporary

EROSION CONTROL
LEGEND AND SYMBOL
INFORMATION SHEET

(COVERS SHEET SERIES R)


FILE NO. TBD	ENGLISH	DESIGN TEAM Stanley Consultants Inc.	DUBUQUE COUNTY	PROJECT NUMBER BRF-020-9(269)--38-31	SHEET NUMBER RR.1
--------------	---------	--------------------------------------	----------------	--------------------------------------	-------------------






FILE NO. TBD	ENGLISH	DESIGN TEAM Stanley Consultants Inc.	DUBUQUE COUNTY	PROJECT NUMBER BRF-020-9(269)--38-31	SHEET NUMBER RR.3
--------------	---------	--------------------------------------	----------------	--------------------------------------	-------------------


9:52:26 AM 10/20/2023 9589 pw:\\projectwise.dot.int.lan:PWMain\Documents\Projects\3102002021\Design\CADD_Files\Sheet_Files\SH_31020269_RR02.dgn






FILE NO. TBD	ENGLISH	DESIGN TEAM Stanley Consultants Inc.	DUBUQUE COUNTY	PROJECT NUMBER BRF-020-9(269)--38-31	SHEET NUMBER RR.5
--------------	---------	--------------------------------------	----------------	--------------------------------------	-------------------

9:53:03 AM 10/20/2023 9589 pw:\\projectwise.dot.int.lan:PWMain\Documents\Projects\3102002021\Design\CADD_Files\Sheet_Files\SHT_31020269_RR05.dgn




FILE NO. TBD	ENGLISH	DESIGN TEAM Stanley Consultants Inc.	DUBUQUE COUNTY	PROJECT NUMBER BRF-020-9(269)--38-31	SHEET NUMBER RR.6
--------------	---------	--------------------------------------	----------------	--------------------------------------	-------------------

9:53:16 AM 10/20/2023 9589 pw:\projectwise.dot.int.lan:PWM\Main\Documents\Projects\3102002021\Design\CADD_Files\Sheet_Files\SH_31020269_RR05.dgn



FILE NO. TBD	ENGLISH	DESIGN TEAM Stanley Consultants Inc.	DUBUQUE COUNTY	PROJECT NUMBER BRF-020-9(269)--38-31	SHEET NUMBER RR.7	US 20
--------------	---------	--------------------------------------	----------------	--------------------------------------	-------------------	-------



Note:
Top of bridge deck at CL W.B. US 20 is 0.21' above the profile grade to account for deck cross slope and parabolic crown.

Longitudinal Section Along CL US 20

BENCH MARK NO. CP10: N:8409640.45 E:21340384.44; ELEV 925.87
SET 3/8" REBAR ON SOUTH SIDE OF HIGHWAY 20 SECOND PIER FROM THE WEST ON TOP OF BANK WEST SIDE OF RIVER

-0.44%
VPI Sta. = 22+10.52
VPI Elev. = 947.966
VPI Sta. = 28+78.20
VPI Elev. = 945.029

Proposed Profile
Grade U.S. 20

Hydraulic Data

RIDB: MaquoketaR_NF_71.5
Stream Gauge number: NWSDYRI4
Drainage Area = 122.0 Sq. Mi.
Stream Slope (HGL) = 7.69 Ft./Mi.

Q₅₀ = 13,181 cfs
Stage = 934.06 Ft.
Regulatory Low Beam=941.41

Q₁₀₀ = 15,895 cfs
Stage = 935.37 Ft.
Operational Low Beam=940.18
Backwater = 0.10 Ft.
Avg. Bridge Velocity = 3.16 fps

Q₂₀₀ = 20,470 cfs
Stage = 937.57 Ft.
Calculated Design Scour = 910.7 Ft.

Q₅₀₀ = 25,678 cfs
Stage = 939.52 Ft.
Avg. Bridge Velocity = 3.72 fps
Calculated Check Scour = 910.4 Ft.

50- 100-, 500-year stages and discharges from
Dubuque County F.I.S.,
Dated August 10, 2021.
F.I.S. Datum = NAVD88


Utilities Legend:

E1(C) - Electric Line - Alliant Energy
SAN.(C) - Sanitary Sewer - City of Dyersville
W(C) - Water Line - City of Dyersville
FO(C) - Fiber Optic - Iowa Communications Network
FO2(C) - Fiber Optic - Maquoketa Valley Electric Co-op

Traffic Estimate

2021 AADT 10,900 V.P.D.
(Includes EB and WB traffic)

TRUCKS 19 %



Situation Plan




Location

W.B. US 20 over N Fork Maquoketa River
T-88N R-2W
Section 6
Dodge Township
Dubuque County
FHWA No. 23780
Bridge Maint. No. 3193.5L020
Latitude 42.470288°
Longitude -91.123804°


Notes

All units are in feet unless noted otherwise.
TL-4 Bridge Railing proposed
Pier Type = Tee Piers
Beam Type = BTB Beams
Foundation type to be confirmed during final design.
Berm slopes to be confirmed during final design.



Typical Bridge Section
(Looking East)

HYDRAULIC DESIGN



I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Signature Mark D. Werner Date 9-28-2023
Printed or Typed Name MARK D. WERNER

My license renewal date is December 31, 2023

Pages or sheets covered by this seal: V.01

PRELIMINARY

Design For 0° Skew
496'-0" x 40'-0" Pretensioned
Prestressed Concrete Beam Bridge
121'-0" End Spans 137'-0", 117'-0" Interior Span

Situation Plan


STA. 25+58.71, 37' Lt. (CL US 20) Turn-in Date: July 2023

Dubuque County

IOWA DEPARTMENT OF TRANSPORTATION
Design No. TBD Design Sheet No. 1 of 2 FHWA No. 23780


Design Notes

All units are in feet unless noted otherwise.
TL-4 Bridge Railing proposed
Pier Type = Tee Piers
Beam Type = BTD Beams
Foundation type to be confirmed during final design.
Berm slopes to be confirmed during final design.



Berm Slope Location Table						
Points	West Abutment			East Abutment		
	Station	Offset	Elev.	Station	Offset	Elev.
A1	23+61.26	63.58' LT	925.00	27+55.56	63.58' LT	924.81
A2	23+59.67	14.42' LT	925.50	0+00.00	14.42' LT	924.61
B1	23+15.21	63.58' LT	940.32	28+02.21	63.58' LT	938.14
B2	23+15.21	14.42' LT	940.32	28+02.21	14.42' LT	938.14
W1	22+97.21	63.58' LT	947.20	28+20.21	63.58' LT	944.90
W2	22+97.21	14.42' LT	947.28	28+20.21	14.42' LT	944.98

Berm slope elevations reflect the grading surface.



Estimated Berm Armoring Quantities				
Location	Revetment CL. E (Ton)	Erosion Stone (Ton)	Engineering Fabric (SY)	CL. 10 Channel Excavation (CY)
Berm Lining - West	725		843	767
Berm Lining - East	809		941	856
Totals	1534		1784	1623

Excavation quantity calculated from grading surface. Excavation quantity if for embedded revetment core out only, and does not include excavation to the grading surface. Excavation quantity to the grading surface is determined by Road Design and included in the Road Plans.

General Notes

This design is for the replacement of the existing 498'-0" x 28'-0" Concrete Box Girder Bridge, Dubuque Design No. 157, FHWA 23780, Maint. No. 3193.5L020. An Iowa DNR Flood Plain Permit is required. Preliminary Design will submit the application and place the permit in the PW Regulatory_Permits subdirectory folder upon receipt. Requirements for a state water trail or paddling route are applicable. Signage, plan notes, and bid items shall be addressed by the Design Bureau and included in the road plans.

Utilities Note:

Utilities shown on this sheet are for information only. See Road Design sheets for utility information.

Utilities Legend:

E1(C) - Electric Line - Alliant Energy
SAN.(C) - Sanitary Sewer - City of Dyersville
W(C) - Water Line - City of Dyersville
FO(C) - Fiber Optic - Iowa Communications Network
FO2(C) - Fiber Optic - Maquoketa Valley Electric Co-op

PRELIMINARY

Design for 0° Skew

496'-0" x 40'-0" Pretensioned Prestressed Concrete Beam Bridge

121'-0" End Spans 137'-0", 117'-0" Interior Span

Site Plan

STA. 25+58.71, 37' Lt. (Q US 20) Turn-in Date: July 2023

Dubuque County

IOWA DEPARTMENT OF TRANSPORTATION

Design No. TBD Design Sheet No. 2 of 2 FHWA No. 23780

CROSS SECTION VIEW COLOR LEGEND			
Design Color No.	Feature	Design Color No.	Feature
Aggregate		Structural	
(64)	Choke Stone	(112)	Noise Wall
(42)	Engineering Fabric	(112)	Noise Wall Footing
(8)	Flooded Backfill	(112)	Retaining Wall Back
(92)	Macadam Stone	(112)	Retaining Wall Back Excavate
(20)	Modified	(112)	Retaining Wall Face
(12)	Plowing Shaping	(112)	Retaining Wall Front Excavate
(14)	Porous Backfill	(112)	Retaining Wall Front Footing
(8)	Revetment Class A	(112)	Retaining Wall MSE Gutter
(6)	Revetment Class B	(112)	Retaining Wall Reinforced Earth
(62)	Revetment Class C	Grading	
(188)	Revetment Class D	(8)	Behind Curb Cut
(28)	Revetment Class E	(6)	Granular
(12)	Shoulder Special Backfill	(13)	Granular Back Fill
(12)	Special Backfill	(48)	Rock Undercut
(20)	Subbase	(8)	Shoulder Earth Fill
(20)	Subbase Lower	(2)	Side Slopes
(20)	Subbase Upper	(226)	Side Slopes Dressing
(118)	Subgrade Treatment	Substrata	
Asphalt		(128)	Boulder Substrata
(207)	HMA Base Course	(48)	Broken Weathered Substrata
(207)	HMA Interim Course	(3)	Core Out Substrata
(207)	HMA Surface Course	(203)	Existing Pavement Substrata
Concrete		(6)	Loam Substrata
(0)	Barrier Concrete	(80)	Rock Substrata
(0)	Barrier Concrete Footing	(4)	Select Sand Substrata
(0)	Curb Gutter	(3)	Shale Substrata
(48)	Flowable Mortar	(10)	Topsoil Substrata
(0)	Median Concrete	Unsuitable / Waste	
(0)	PCC Pavement	(3)	Unsuitable Type A
(0)	Sidewalk	(13)	Unsuitable Type B
Shoulder		(11)	Unsuitable Type C
(209)	Shoulder HMA	(3)	Waste
(0)	Shoulder PCC		
(6)	Shoulder Granular		
Existing			
(0)	Existing Pavement		

NOTES:

Text




NOTES:

Text




CROSS SECTIONS
LEGEND AND INFORMATION SHEET

(COVERS SHEET SERIES W, X, Y, & Z)




WB US 20






WB US 20





WB US 20





WB US 20





WB US 20






WB US 20






WB US 20






WB US 20






WB US 20






WB US 20



WB US 20



WB US 20



WB US 20

