


DES MOINES COUNTY

Bridge Replacement - RCB  
BRF-061-2(96)--38-29

LETTING DATE  
1/21/2026



INDEX OF SHEETS	
No.	DESCRIPTION
<b>A Sheets</b>	<b>Title Sheets</b>
A.1	Title Sheet
A.2	Location Map Sheet
<b>B Sheets</b>	<b>Typical Cross Sections and Details</b>
B.1 - 2	Typical Cross Sections and Details
<b>C Sheets</b>	<b>Quantities and General Information</b>
C.1	Project Description
C.1	Estimated Project Quantities and Reference Notes
C.1	Standard Road Plans
<b>D Sheets</b>	<b>Mainline Plan and Profile Sheets</b>
* D.1	Plan & Profile Legend & Symbol Information Sheet
* D.2	US 61
<b>G Sheets</b>	<b>Survey Sheets</b>
G.1 - 3	Reference Ties and Bench Marks
G.4	Horizontal Control Tab. & Super for all Alignments
<b>J Sheets</b>	<b>Traffic Control and Staging Sheets</b>
J.1	Traffic Control Plan
* J.2	Staging and Traffic Control Sheet
<b>R Sheets</b>	<b>Erosion Control Sheets</b>
RC.1 - 3	Est. Quantities, PPP, General Notes and Tabulations
* RR.1	Erosion Control Legend and Symbol Information Sheet
* RR.2 - 3	Drainage Basin and Erosion Control Device Maps
<b>V Sheets</b>	<b>Bridge and Culvert Situation Plans</b>
* V.1 - 2	Bridge and Culvert Situation Plans
<b>W Sheets</b>	<b>Mainline Cross Sections</b>
* W.1	Cross Sections Legend & Symbol Information Sheet
* W.2 - 7	Mainline Cross Sections
	* Color Plan Sheets



PLANS OF PROPOSED IMPROVEMENT ON THE  
**PRIMARY ROAD SYSTEM**  
**DES MOINES COUNTY**  
**Bridge Replacement - RCB**  
 US 61 Bridge over the Branch Smith Creek  
 1.0 mi S. of Louisa Co

SCALES: As Noted

Refer to the Proposal Form for list of applicable specifications.

Value Engineering Saves. Refer to Article 1105.14 of the Specifications.



REVISIONS

TOTAL
28
PROJECT IDENTIFICATION NUMBER
15-29-061-010
PROJECT NUMBER
BRF-061-2(96)--38-29
R.O.W. PROJECT NUMBER

**DESIGN DATA RURAL**

20 21	AACT	5,100	V.P.D.
20 26	AACT	130	V.P.D.
20 -	DHV	--	V.P.H.
	TRUCKS	13	%
	Total		
	Design ESALs	--	

**INDEX OF SEALS**




SHEET NO.	NAME	TYPE
A.1	X	Primary Signature Block
V.1 / V.2	Mark D. Werner	Hydraulics

PRELIMINARY PLANS

Subject to change by final design.

**D05 Plan, Date: 12/22/2023**

US 61 BRIDGE REPLACEMENT  
RCB CULVERT  
FHWA NO. 23500  
MAINT. 2958.75061  
STA. 858+56.50




During Final Design, Discuss using Standard Road Plan PR-120.

**Full Depth PCC Shoulder**

Shoulder Jointing:  
 Longitudinal joint: BT-2, L-2 or KT-2  
 Transverse joints: C at 17' spacing

STATION TO STATION		(S)	(P) Feet
857+20.57	857+65.00	4:1	
857+65.00	857+80.00	4:1 - 2:1	
857+80.00	858+55.00	2:1	
858+55.00	858+70.00	2:1 - 4:1	
858+70.00	859+99.69	4:1	
857+20.57	857+40.57		11.2
857+40.57	857+88.11		11.2 - 9.3
857+88.11	859+32.24		9.3
859+32.24	859+79.69		9.3-11.2
859+79.69	859+99.69		11.2

① Refer to Detail 7157 for Guardrail Shoulder Paving



Mainline Jointing:  
 Transverse joints: CD at 17' spacing  
 Longitudinal joint: L-2

STATION TO STATION	
857+38.87	859+70.52


**Full Depth PCC Shoulder**

Shoulder Jointing:  
 Longitudinal joint: BT-2, L-2 or KT-2  
 Transverse joints: C at 17' spacing

STATION TO STATION		(S)	(P) Feet
857+38.87	857+87.47	②	
857+87.47	858+40.00	4:1	
858+40.00	858+55.00	4:1 - 2:1	
858+55.00	859+30.00	2:1	
859+30.00	859+45.00	2:1 - 4:1	
859+45.00	859+90.52	4:1	
857+38.87	857+87.47		8
857+87.47	858+55.34		16.3 - 9.3
858+55.34	859+23.52		9.3
859+23.52	859+70.52		9.3-11.2
859+70.52	859+90.52		11.2

① Refer to Detail 7157 for Guardrail Shoulder Paving  
 ② Match existing driveway grade.

**US HIGHWAY 61**






9.5" PCC Paved Shoulder at guardrail shall use the following joint layout:

Match mainline pavement joint spacing. When mainline pavement is 8" or greater in thickness, place additional transverse 'C' joints in shoulder at mid-panel of the mainline pavement. Place longitudinal 'C' joint at P/2 from edge of mainline pavement when P is greater than 10' wide. Terminate longitudinal joint at transverse joint less than 10' in length.

Refer to Tabulation 112-9 for shoulder quantities.

- ① PCC option only: When guardrail posts are installed prior to construction of PCC paved shoulder, fasten form board to the face of guardrail posts for the length shown.
- ② Continue paved shoulder 20 feet beyond the center of the first post.
- ③ Shoulder may be notched for first 2 posts or post sleeves may be installed through pavement. Do not drive posts through pavement.
- ④ 'KT' (per PV-101) joint for PCC shoulder.
- ⑤ Match shoulder slope.
- ⑥ The Contractor has the option to pave the paved shoulder at guardrail and the partial width paved shoulder as one operation.
- ⑦ Refer to other details in the plan.



PAVED SHOULDER AT GUARDRAIL  
(ADJACENT TO PARTIAL WIDTH PAVED SHOULDER)



### SURVEY SYMBOLS

- Interstate Highway Symbol
- U.S. Highway Symbol
- Iowa Highway Symbol
- County Road Highway Symbol
- Evergreen Tree
- Deciduous Tree
- Fruit Tree
- Shrub (Bushes)
- Timber
- Hedge
- Stump
- Swamp
- Rock Outcrop
- Broken Concrete
- Revetment (Rip Rap)
- Cemetery
- Grave
- Cave
- Sink Hole
- Board Fence
- Chain Link or Security Fence
- Wire Fence
- Terrace
- Earth Dam or Dike (Existing)
- Tile Outlet
- Edge of Water
- Existing Drainage
- Right of Way Rail or Lot Corner
- Concrete Monument
- Well
- Windmill
- Beehive Intake
- Existing Intake
- Existing Utility Access (Manhole)
- Fire Hydrant
- Water Hydrant (Rural)
- Septic Tank
- Cistern
- L.P. Gas Tank (No Footing)
- Underground Storage Tank
- Latrine
- Satellite TV Dish
- Water Hook Up
- Radio Tower
- Tower Anchor
- Guardrail (Beam or Cable)
- Guard Post (one or two)
- Guard Post (over two)
- Filler Pipe
- Gas Valve
- Water Valve
- Speed Limit Sign
- Mile Marker Post
- Sign
- Traffic Signal Control Box
- Rail Road Signal Control Box
- Telephone Switch Box
- Electric Box

### UTILITY LEGEND

- Eastern Iowa Electric  
Tom Quiram  
P.O. Box 3003  
Wilton, IA 52778-3003  
563-732-2211
- Mediapolis Telephone Company  
Marc Carlson  
652 Main St,  
Mediapolis, IA 52637  
319-394-3456
- Windstream  
Bryan Bogan  
4001 N Rodney Parham Rd.  
Little Rock, AR  
501-748-6919
- Lumen  
Steve Parker  
2103 E University Ave., 1st Floor  
Des Moines, IA 50317  
515-265-0968
- Mutual Telephone Company  
Randy Foor  
28 W Division St,  
Morning Sun, IA 52640  
319-868-7636
- Windstream  
Communications  
(Iowa Telecom)  
Bryan Bogan  
4001 N Rodney Parham Rd.  
Little Rock, AR  
501-748-6919
- Alliant Energy  
Mary Montgomery  
200 1st St. SE  
Cedar Rapids, IA 52401  
319-786-8196
- ANR Pipeline Company  
Robert Southers  
P.O. Box 9  
2795 Locust Avenue  
Birmingham, IA 52535  
319-498-4200 ext 2252
- ICN  
Mike Broderick  
400 E 14th Street  
Grimes State Office Bldg  
Des Moines, IA 50319  
515-725-4610
- Eastern Iowa Electric  
Tom Quiram  
P.O. Box 3003  
Wilton, IA 52778-3003  
563-732-2211
- Iowa Dept Of Transportation  
Lamont Sutter  
900 Park Street  
Donnellson, IA 52625  
319-835-5211
- Rathbun Regional Water  
Bill Benjamin  
16166 Hwy J-29  
Centerville, IA 52544  
319-258-2103
- Alliant Energy  
Mary Montgomery  
200 1st St. SE  
Cedar Rapids, IA 52401  
319-786-8196
- Mediacom  
Tim Eagen  
3210 Division St.  
Burlington, IA  
319-208-1829

### PLAN VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS

LINEWORK		Design Color No.	
Green	(2)		Existing Topographic Features and Labels
Blue	(1)		Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation
Magenta	(5)		Existing Utilities
SHADING		Design Color No.	
Lavender	(9)		Temporary Pavement Shading
Yellow	(4)		Proposed Pavement Shading
Orange	(6)		Proposed Granular Shading
Orange	(70)		Proposed Shoulder Granular Shading
Yellow	(68)		Proposed Shoulder Paved Full Depth Shading
Yellow	(132)		Proposed Shoulder Paved Partial Depth Shading
Gray, Dark	(112)		Proposed Grade and Pave Shading "In conjunction with a paving project"
Brown, Light	(236)		Grading Shading
Orange, Light	(134)		Proposed Granular Entrance Shading
Yellow	(220)		Proposed Paved Entrance Shading
Tan	(8)		Proposed Sidewalk Shading
Blue, Light	(230)		Proposed Sidewalk Landing Shading
Pink	(11)		Proposed Sidewalk Ramp Shading
Green, Light	(225)		Existing Pavement Shading
Red	(3)		Proposed Structure Shading
Red	(3)		Delineates Restricted Areas

### PROFILE VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS

LINEWORK		Design Color No.	
Green	(10)		Existing Ground Line Profile
Blue	(1)		Proposed Profile and Annotation
Magenta	(5)		Existing Utilities
Blue, Light	(230)		Proposed Ditch Grades, Left
Black	(0)		Proposed Ditch Grades, Median
Rust	(14)		Proposed Ditch Grades, Right



- Reference Point
- Station
- Survey Line
- Section Corner
- Ground Line Intercept
- Saw Cut
- Guardrail
- Trench Drain
- HighTension Cable Guardrail
- Sheet Pile
- Pavement Removal
- Clearing & Grubbing Area

### RIGHT-OF-WAY LEGEND

- Proposed Right-of-Way
- Existing Right of Way
- Existing and Proposed Right-of-Way
- Easement and Existing Right-of-Way
- Easement (Temporary)
- Easement
- Access Control
- Property Line

## PLAN AND PROFILE LEGEND AND SYMBOL INFORMATION SHEET

(COVERS SHEET SERIES D, E, F, & K)



## Survey Information

### Horizontal Control -

Control Monuments used for this project consisted of 11 Des Moines County GPS Monuments and 2 Louisa County GPS Monuments. These monuments are all 5/8" diameter aluminum rods with 2.5" diameter aluminum caps encased in 5" diameter PVC pipes with aluminum access covers. All monuments were previously set as part of countywide GPS control networks. Each monument was observed for a minimum of two 5 minute RTK sessions, at differing times of day using the Iowa RTN as a reference station. The monuments completely surround the project area, are approximately 1 to 2 miles east or west of the existing US 61 alignment and are spaced 3 to 4 miles apart north and south. These monuments are considered to be in safe locations that will survive construction.

Control Points used for this project consisted of 80 iron pins that were previously set along the existing Highway 61 alignment. These points were used for the initial survey work completed in 1999 and recovered for the new survey work. An additional 3 iron pins were set to supplement the points recovered. Points are no more than 1300 feet apart and intervisible. All points were observed for a minimum of two 5 minute RTK sessions, at differing times of day using the Iowa RTN as a reference station.

All Control Monuments and Control Points were referenced to at least three durable physical objects and complete sketches were made in the field notes.

GPS Horizontal Errors	Mean Error of Observations	0.034
	Standard Deviation of Error	0.021

### Coordinate System -

The coordinate system used is NAD83(CORS) (Epoch 2002.00) Iowa State Plane, South Zone, U. S. Survey Feet. The 13 Control Monuments were used to compute an average scale factor for the project area to convert from grid distances to ground distances. After applying the scale factor, a shift was applied to hold a central point in the job at true state plane coordinate values.

A sample of these initial coordinate values was compared to the coordinates from the previous work. This resulted in a scale difference of 0.62' over the entire length of the project or approximately 0.03' per mile. To ensure all previous work would merge seamlessly with the new work, the average scale factor initially computed was adjusted to correct the difference. The shift was also recomputed to better fit the previous work.

Final Scale and Shift Parameters-	Scale Factor	0.99992280532
	Northing Shift	-27.7970
	Easting Shift	-176.3040

### Vertical Control -

The vertical datum used is NAVD88. Benchmarks for this project consisted of 82 benchmarks that were previously established along the existing Highway 61 alignment. These were used for the initial survey work completed in 1999 and recovered for the new survey work. An additional 21 benchmarks were established to supplement the ones recovered. Benchmarks are spaced no more than 1300' apart.

The levels were started at an offsite benchmark, run to the job just North of the BOP and then run along the existing US 61 corridor. Side legs were added as necessary. The levels were run through all control points and all benchmarks. The levels were closed out on 2 separate offsite benchmarks. The levels were run in approximately 0.5 to 1 mile segments, each segment was closed back on its starting point at the end of each day.


The original benchmark used at the South end of the project in 1999 was not found. However, Des Moines County notes were found where this benchmark had been transferred to another location. We started our leveling at this point, MW#701. The closing benchmarks were NGS N126, point MW#725 and a USGS monument 20RWM, point MW#730. This USGS monument was also used in 1999 for the previous work.

The average closure error was 0.014' over 32 looped segments. All looped segments were left unadjusted. Holding the Des Moines County elevation value of the starting benchmark MW#701 resulted in a closure of +0.08' on both NGS N126, MW#725 and USGS monument 20RWM, MW#730. A comparison of the 1999 benchmark elevations and the new elevations showed an average difference of +0.085' using 51 common points that should have held stable since the previous work was done.

Assuming that the starting benchmark elevation was in error and based on the above information all computed elevations were adjusted by -0.08 to better match the 2 closing benchmarks and the benchmarks previously used on this project.







**ALIGNMENT COORDINATES**

Name	Location	Point on Tangent		Begin Spiral		Begin Curve		Simple Curve PI or Master PI of SCS			End Curve		End Spiral	
		Station	Coordinates	Station	Coordinates	Station	Coordinates	Station	Coordinates	Station	Coordinates	Station	Coordinates	
1	US 61 (ML061)	823+70.55	391525.69	2281866.00										
2	US 61 (ML061)					836+01.38	392754.82	2281801.45	844+58.49	393610.76	2281756.49	853+02.68	394415.00	2281460.14
4	US 61 (ML061)					870+26.39	396032.40	2280864.13	873+65.75	396350.83	2280746.80	876+93.72	396587.03	2280503.14
5	US 61 (ML061)	880+33.14	396823.28	2280259.44										

**SPIRAL OR CIRCULAR CURVE DATA**

Name	Location	ΔSCS	Horizontal Alignment Data												Remarks			
			Spiral Data						Curve Data									
			θS	Ls	Ts	Es	Xc	Yc	L.T.	S.T.	ΔC	T	L	R		E		
C1	US 61 (ML061)																	
C2	US 61 (ML061)																	


NO ACCESS RIGHTS ARE TO BE ACQUIRED ON THIS PROJECT.

**Yellow Springs Twp  
T-72N R-3W  
SEC. 2  
SW 1/4 SW 1/4**

TEMPORARY EASEMENT FOR  
CHANNEL REALIGNMENT

1

Quail Creek Farms INC.



857+35.00  
C 150.00' LT

856+99.00  
C 115.00' LT

857+30± EX R/W  
C 65' LT

858+64± EX R/W  
C 65' LT

Existing R.O.W.

856+00

857+00

858+00

859+00

860+00

861+00

US 61

+75' U.A.C. Ent.

Existing R.O.W.

857+45± EX R/W  
C 54.00' RT

858+49.88  
C 59.99' RT

859+73.45  
C 59.93' RT

857+67.00  
C 80.00' RT

858+97.00  
C 80.00' RT


859+54.00  
C 80.00' RT

TEMPORARY EASEMENT  
TO SHAPE

857+93± EX R/W  
C 58' RT

2

Dorlem S Harvey



Right of Way Design Information	
THIS SHEET INCLUDED FOR INFORMATION ONLY	
ROW Team: HINRICHSEN / LARSON	
ROW #: NHSN-061-2(97)--2R-29	
Plan Date: 03/15/2024	
Color Legend:	
	Property Lines
	Temporary Easement
	Permanent Acquisition

108-23A  
08-01-08

### TRAFFIC CONTROL PLAN


US 61  
- Close existing 2-lane US 61 and utilize detour route via new 4-lane US 61 for duration of the project. Refer to Sheet J.2 for detour route map.

111-01  
04-17-12

### COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
NHSX-061-2(110)--3H-39	PCC PAVEMENT - GRADE AND NEW



**PERIMETER, SLOPE AND DITCH CHECK SEDIMENT CONTROL DEVICES**

100-19  
10-19-21

Possible Standards: EC-204

Location			Perimeter and Slope			Ditch Check		Remarks
Begin Station	End Station	Side	Length of Installation			Length of Installation		
			9 inch Dia	12 inch Dia	20 inch Dia	12 inch Dia	20 inch Dia	
			LF	LF	LF	LF	LF	
856+76.00	857+12.00	Lt		150.0				
857+20.00	858+08.00	Lt		130.0				
857+30.00	858+55.00	Lt		160.0				
857+29.00	860+30.00	Lt		330.0				
857+18.00	857+69.00	Rt		70.0				
857+89.00	859+05.00	Rt		120.0				
858+55.00	858+90.00	Rt		50.0				
859+02.00	859+47.00	Rt		60.0				
859+48.00	860+25.00	Rt		90.0				
Totals:				1160.0				

**FLOATING SILT CURTAINS**

100-10  
10-21-14

Refer to EC-202

Station	Hanging	Containment	Clean-out (Containment)	Maintenance of Floating Silt Curtain	Remarks				
						LF	LF	LF	LF
						859+24.00	100.0	100.0	200.0

**STORMWATER DRAINAGE BASIN AND STORAGE**

100-34  
10-17-17

Refer to EC Standards and 570s Details.

Drainage Basin Location						Summary of Stormwater Storage							Remarks		
Basin No.	Station to Station		Side	Discharge Point		Total Disturbed Area	Disturbed Area with Storage Provided	Disturbed Area without Storage Provided	Best Management Practice	Total Storage Volume Provided	Total Storage Volume Required	Storage Volume Met?			
				Station	Side							CF		CF	Yes/No
				Acres	Acres							Acres		CF	CF
1	857+05.00	860+15.00	Both	859+24.00	Rt	0.8	0.0	0.8	Vegetated Buffer	0.0	0.0	N/A			



**POLLUTION PREVENTION PLAN**

This project is regulated by the requirements of the Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) General Permit No. 2 OR an Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) individual storm water permit. The Contractor shall carry out the terms and conditions of this permit and the Pollution Prevention Plan (PPP).

This Base PPP includes information on Roles and Responsibilities, Project Site Description, Controls, Maintenance Procedures, Inspection Requirements, Non-Storm Water Controls, Potential Sources of Off Right-of-Way Pollution, and Definitions. This plan references other documents rather than repeating the information contained in the documents. A copy of this Base Pollution Prevention Plan, amended as needed during construction, will be readily available for review.

All contractors shall conduct their operations in a manner that controls pollutants, minimizes erosion, and prevents sediments from entering waters of the state and leaving the highway right-of-way. The Contractor shall be responsible for compliance and implementation of the PPP for their entire contract. This responsibility shall be further shared with subcontractors whose work is a source of potential pollution as defined in this PPP.

**I. ROLES AND RESPONSIBILITIES**

- A. Designer:
  1. Prepares Base PPP included in the project plan.
  2. Prepares Notice of Intent (NOI) submitted to Iowa DNR.
  3. Is signature authority on the Base PPP. If consultant designed, signature from Contracting Authority is also required.
- B. Contractor:
  1. Signs a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP. All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
  2. Designates a Water Pollution Control Manager (WPCM), who has the duties and responsibilities as defined in Section 2602 of the Standard Specifications.
  3. Submits an Erosion Control Implementation Plan (ECIP) and ECIP updates according to Section 2602 of the Standard Specifications.
  4. Installs and maintains appropriate controls. This work may be subcontracted as documented through Subcontractor Request Forms (Form 830231).
  5. Supervises and implements good housekeeping practices according to Paragraph III, C, 2.
  6. Conducts joint required inspections of the site with inspection staff. When Contractor is not mobilized on site, Contractor may delegate this responsibility to a trained or certified subcontractor. Contracting Authority also may waive joint inspection requirement during winter shutdown. In both circumstances, WPCM (or trained or certified delegate from the Contractor) is still responsible to review and sign inspection reports.
  7. Complies with training and certification requirements of Section 2602 of the Standard Specifications.
  8. Submits amended PPP site map according to Section 2602 of the Standard Specifications.
- C. Subcontractors:
  1. Sign a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP if: responsible for sediment or erosion controls; involved in land disturbing activities; or performing work that is a source of potential pollution as defined in this PPP. Subcontracted work items are identified in Subcontractor Request Forms (Form 830231). All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
  2. Implement good housekeeping practices according to Paragraph III, C, 2.
- D. RCE/Project Engineer:
  1. Is Project Storm Water Manager.
  2. On projects where DOT is the Contracting Authority, is current with erosion control training or certification.
  3. Takes actions necessary to ensure compliance with storm water requirements including, where appropriate, issuing stop work orders, and directing additional inspections at construction project sites that are experiencing problems with achieving permit compliance.
  4. Orders the taking of measures to cease, correct, prevent, or minimize the consequences of non-compliance with the storm water requirements of the Applicable Permit.
  5. Supervises all work necessary to meet storm water requirements at the Project, including work performed by contractors and subcontractors.
  6. Requires employees, contractors, and subcontractors to take appropriate responsive action to comply with storm water requirements, including requiring any such person to cease or correct a violation of storm water requirements, and to order or recommend such other actions as necessary to meet storm water requirements.
  7. Is familiar with the Project PPP and storm water site map.
  8. On projects where DOT is Contracting Authority, is responsible for periodically monitoring inspection reports to determine whether deficiencies identified in inspection reports were adequately and timely addressed, and if not, has the authority and responsibility to direct immediate actions to correct the deficiencies.
  9. Is the point of contact for the Project for regulatory officials, Inspector, contractors, and subcontractors regarding storm water requirements.
  10. Is signature authority on Notice of Discontinuation.
  11. Maintains an up-to-date record of contractors, subcontractors, and subcontracted work items through Subcontractor Request Forms (Form 830231).
  12. Makes information to determine permit compliance available to the DNR upon their request.
- E. Inspector:
  1. Updates PPP through fieldbook entries and storm water site inspection reports if there is a change in design, construction, operation, or maintenance which has a significant effect on the discharge of pollutants from the project.
  2. Makes information to determine permit compliance available to the DNR upon their request.
  3. Conducts joint required inspections of the site with the contractor/subcontractor.
  4. Completes an inspection report after each inspection.
  5. Is signature authority on storm water inspection reports.

**II. PROJECT SITE DESCRIPTION**

- A. This Pollution Prevention Plan (PPP) is for the construction of a culvert.
- B. This PPP covers approximately 0.8 acres with an estimated 0.7 acres being disturbed. The portion of the PPP covered by this contract has 0.7 acres disturbed.
- C. The PPP is located in an area of 1 soil association (Otley - Ladoga). The estimated weighted average runoff coefficient number for this PPP after completion will be 0.41.
- D. Storm Water Site Map is located in the R sheets. Proposed slopes are shown in cross sections, details, or standard road plans. Supplemental information is located in the Tabulations in the C or CE sheets.
- E. The base storm water site map is amended by contract modifications and progress payments (fieldbook entries) of completed erosion control work. Also, due to project phasing, erosion and sediment controls shown on project plans may not be installed until needed, based on site conditions. For example, silt fence ditch checks will typically not be installed until the ditch has been installed. Installed locations may also be modified from tabulation locations by field staff. Installed locations will be

**POLLUTION PREVENTION PLAN**

documented by fieldbook entries and amended PPP site map.  
F. Runoff from this work will flow into Branch Smith Creek.

**III. CONTROLS**

- A. The Contractor's ECIP specified in Article 2602.03 of the Standard Specifications for accomplishment of storm water controls should clearly describe the intended sequence of major activities, and for each activity define the control measure and the timing during the construction process that the measure will be implemented.
- B. Preserve vegetation in areas not needed for construction.
- C. Sections 2601 and 2602 of the Standard Specifications define requirements to implement erosion and sediment control measures. Actual quantities used and installed locations may vary from the Base PPP and amendment of the plan will be documented via fieldbook entries, amended PPP site map, or by contract modification. Additional erosion and sediment control items may be required as determined by the inspector and/or contractor during storm water site inspections. If the work involved is not applicable to any contract items, the work will be paid for according to Article 1109.03 paragraph B of the Standard Specifications.
  - 1. EROSION AND SEDIMENT CONTROLS
    - a. Stabilization Practices
      - 1) Site plans will ensure that existing vegetation or natural buffers are preserved where attainable and disturbed portions of the site will be stabilized.
      - 2) Initialize stabilization of disturbed areas immediately after clearing, grading, excavating, or other earth disturbing activities have:
        - a) Permanently ceased on any portion of the site, or
        - b) Temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days.
      - 3) Staged permanent and/or temporary stabilizing seeding and mulching shall be completed as the disturbed areas are completed. Incomplete areas shall be stabilized according to paragraph III, C, 1, a, 2, b above.
      - 4) Permanent and Temporary Stabilization practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation (105-4) in the C or R sheets.
      - 5) Preservation of existing vegetation within right-of-way or easements will act as vegetative buffer strips.
      - 6) Preservation of topsoil: Bid items to be used for this project are located in the Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets. Additional information may be found in the Tabulations in the C or T Tabulation sheets, or is referenced in Section 2105 of the Standard Specifications.
    - b. Structural Practices
      - 1) Structural practices will be implemented to divert flows from exposed soils and detain or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Additionally, structural practices may include: silt basins that provide 3600 cubic feet of storage per acre drained or equivalent sediment controls, outlet structures that withdraw water from surface when discharging basins, and controls to direct storm water to vegetated areas.
      - 2) Structural practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the devices to be used on this project can be found on the B or R sheets or are referenced in the Standard Road Plans Tabulation (105-4) located in the C or R sheets.
    - c. Storm Water Management
 

Measures shall be installed during the construction process to control pollutants in storm water discharges that will occur after construction operations have been completed. This may include velocity dissipation devices at discharge locations and along length of outfall channel as necessary to provide a non-erosion velocity flow from structure to water course. If included with this project, these items are located in the storm water site map and Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation. The installation of these devices may be subject to Section 404 of the Clean Water Act.
  - 2. OTHER CONTROLS
 

Contractor disposal of unused construction materials and construction material wastes shall comply with applicable state and local waste disposal, sanitary sewer, or septic system regulations. In the event of a conflict with other governmental laws, rules and regulations, the more restrictive laws, rules or regulations shall apply.

    - a. Vehicle Entrances and Exits - Construct and maintain entrances and exits to prevent tracking of sediments onto roadways.
    - b. Material Delivery, Storage and Use - Implement practices to prevent discharge of construction materials during delivery, storage, and use.
    - c. Stockpile Management - Install controls to reduce or eliminate pollution of storm water from stockpiles of soil and paving.
    - d. Waste Disposal - Do not discharge any materials, including building materials, into waters of the state, except as authorized by a Section 404 permit.
    - e. Spill Prevention and Control - Implement chemical spill and leak prevention and response procedures to contain and clean up spills and prevent material discharges to the storm drain system and waters of the state.
    - f. Concrete Residuals and Washout Wastes - Waste shall not be discharged to a surface water and is not allowed to adversely affect a water of the state. Designate temporary concrete washout facilities for rinsing out concrete trucks. Provide directions to truck drivers where designated washout facilities are located. Designated washout areas should be located at least 50 feet away from storm drains, streams or other water bodies. Care should be taken to ensure these facilities do not overflow during storm events.
    - g. Concrete Grooving/Grinding Slurry - Do not discharge slurry to a waterbody or storm drain. Slurry may be applied on foreslopes or removed from the project.
    - h. Vehicle and Equipment Storage and Maintenance Areas - Perform on site fueling and maintenance in accordance with all environment laws such as proper storage of onsite fuels and proper disposal of used engine oil or other fluids on site. Employ washing practices that prevent contamination of surface and ground water from wash water. Wash waters must be treated in a sediment basin or alternative control that provides equivalent or better treatment prior to discharge.
    - i. Litter Management - Ensure employees properly dispose of litter. Minimize exposure of trash if exposure to precipitation or storm water would result in a discharge of pollutants.
    - j. Dewatering - Properly treat water to remove suspended sediment before it re-enters a waterbody or discharges off-site. Measures are also to be taken to prevent scour erosion at dewatering discharge point.
- 3. APPROVED STATE OR LOCAL PLANS
 

During the course of this construction, it is possible that situations will arise where unknown materials will be encountered. When such situations are encountered, they will be handled according to all federal, state, and local regulations in effect at the time.

**IV. MAINTENANCE PROCEDURES**

### POLLUTION PREVENTION PLAN

The Contractor is required to maintain all temporary erosion and sediment control measures in proper working order, including cleaning, repairing, or replacing them throughout the contract period. This shall begin when the features have lost 50% of their capacity.

#### V. INSPECTION REQUIREMENTS

- A. Inspections shall be made jointly by the Contractor and the Contracting Authority's inspector at least once every seven calendar days. Storm water site inspections will include:
  1. Date of the inspection.
  2. Summary of the scope of the inspection.
  3. Name and qualifications of the personnel making the inspection.
  5. Review of erosion and sediment control measures within disturbed areas for the effectiveness in preventing impacts to receiving waters.
  6. Major observations related to the implementation of the PPP.
  7. Identification of corrective actions required to maintain or modify erosion and sediment control measures.
- B. Include storm water site inspection reports in the Amended PPP. Incorporate any additional erosion and sediment control measures determined as a result of the inspection. Immediately begin corrective actions on all deficiencies found within 3 calendar days of the inspection and complete within 7 calendar days following the inspection. If it is determined that making the corrections less than 72 hours after the inspection is impracticable, it should be documented why it is impracticable and indicate an estimated date by which the corrections will be made.

#### VI. NON-STORM WATER DISCHARGES

This includes subsurface drains (i.e. longitudinal and standard subdrains) and slope drains. The velocity of the discharge from these features may be controlled by the use of headwalls or blocks, Class A stone, erosion stone or other appropriate materials. This also includes uncontaminated groundwater from dewatering operations, which will be controlled as discussed in Section III of the PPP.

#### VII. POTENTIAL SOURCES OF OFF RIGHT-OF-WAY (ROW) POLLUTION

Silts, sediment, and other forms of pollution may be transported onto highway right-of-way (ROW) as a result of a storm event. Potential sources of pollution located outside highway ROW are beyond the control of this PPP. Pollution within highway ROW will be conveyed and controlled per this PPP.

#### VIII. DEFINITIONS

- A. Base PPP - Initial Pollution Prevention Plan.
- B. Amended PPP - Base PPP amended during construction. May include Plan Revisions or Contract Modifications for new items, storm water site inspection reports, fieldbook entries made by the inspector, amended PPP site map by the Contractor, ECIP, NOI, co-permittee certifications, and Subcontractor Request Forms. Items amending the PPP are stored electronically and are readily available upon request.
- C. Fieldbook Entries - This contains the inspector's daily diary and bid item postings.
- D. Controls - Methods, practices, or measures to minimize or prevent erosion, control sedimentation, control storm water, or minimize contaminants from other types of waste or materials. Also called Best Management Practices (BMPs).
- E. Signature Authority - Representative authorized to sign various storm water documents.

#### CERTIFICATION STATEMENT

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Printed or Typed Name

\_\_\_\_\_  
Signature

\_\_\_\_\_

### LINE STYLE LEGEND OF LANDSCAPE SHEETS

LINETYPE	Design Element
-----	Living Snow Fence Single Row
-----	Living Snow Fence Double Row
_____	Mechanical Edge

### CELL LEGEND OF LANDSCAPE SHEETS

CELL	Design Element	Plant Diameter
⊕	Clearing	
⊙	Proposed Shrub	6 FT
⊙	Proposed Understory Tree	12 FT
⊙	Proposed Conifer Tree	18 FT
⊙	Proposed Overstory Tree	30 FT

### PATTERN LEGEND OF LANDSCAPE SHEETS

	Brush Clearing		Spray Area
	Clearing & Grubbing		

### LINE STYLE LEGEND OF EROSION CONTROL SHEETS

LINETYPE	Design Element
	Silt Fence
"/>	Perimeter and Slope Sediment Control Device (9")
"/>	Perimeter and Slope Sediment Control Device (12")
"/>	Perimeter and Slope Sediment Control Device (20")
	Open-Throat Curb Intake Sediment Filter
	Concentrated Flow
	Rock Check and Rock Check Dam
	Sheet Flow

### CELL LEGEND OF EROSION CONTROL SHEETS

CELL	Design Element
	Temporary Sediment Control basin
	Erosion Control for Circular Intake or Manhole Well
	Erosion Control for Rectangular Intake or Manhole Well
	Grate Intake Sediment Filter Bag
	Silt Basin
	Silt Fence Tail
	Stormwater Drainage Basin Discharge Point

### PLAN VIEW COLOR LEGEND OF EROSION CONTROL SHEETS

LINWORK	Design Color No.	Design Element
Green	(2)	Existing Topographic Features and Labels
Blue	(1)	Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation
Magenta	(5)	Existing Utilities
Black	(0)	Permanent Erosion Control Features
Blaze Orange	(222)	Temporary Erosion Control Features


SHADING	Design Color No.	Design Element	Transparency
Citron	(234)	Mulching, All Types	50%
Light Brown	(238)	Special Ditch Control, Wood Excelsior Mat	0%
Grass Green	(233)	8FT Mow Strip	50%
Red	(3)	Delineates Restricted Areas	0%


### PATTERN LEGEND OF EROSION CONTROL SHEETS


	Seeding and Fertilizing		Turf Reinforcement Mat Type 1
	Seeding and Fertilizing (Rural)		Turf Reinforcement Mat Type 2
	Seeding and Fertilizing (Urban)		Turf Reinforcement Mat Type 3
	Native Grass Seeding		Turf Reinforcement Mat Type 4
	Salt Tolerant Seeding		Slope Protection, Wood Excelsior Mat
	Wetland Grass Seeding		Transition Mat
	Wildflower Seeding		Rock Features, Permanent
	Sodding		Rock Features, Temporary

## EROSION CONTROL LEGEND AND SYMBOL INFORMATION SHEET


(COVERS SHEET SERIES R)








LONGITUDINAL SECTION ALONG  $\bar{C}$  CULVERT




CLASS E REVETMENT OUTLET SPLASH BASIN



PROPOSED PROFILE GRADE U.S. 61

**DESIGNER NOTES**

1. Outlet revetment included due to high velocity
2. Revetment placed inside headwall to increase roughness and help reduce velocity as flow transitions to creek channel.



SITUATION PLAN

**UTILITIES LEGEND:**

- Power Pole - Eastern Iowa Electric
- FO2 - Buried Fiber Optic Line - Mediapolis Telephone Co.
- W - Buried Water Line - Rathbun Regional Water

**TRAFFIC ESTIMATE**

2021 AADT	5,100	V.P.D.
2026 AADT	130	V.P.D.
TRUCKS	15	%

**Hydraulic Data**

RIDB: Not Applicable  
 Drainage Area = 1.9 Acres  
 Stream Slope = 30.8 Ft./Mi.

$Q_{50}$  = 1,257 cfs  
 HW Elev. = 690.66  
 Exit Velocity = 13.6 fps

$Q_{100}$  = 1,508 cfs  
 HW Elev. = 691.79  
 Exit Velocity = 14.4 fps

**LOCATION**

US 61 OVER BRANCH SMITH CREEK  
 T-72N R-3W  
 SECTION 2  
 YELLOW SPRING TOWNSHIP  
 DES MOINES COUNTY  
 FHWA NO. 23500  
 BRIDGE MAINT. NO. 2958.75061  
 LATITUDE 41.060404°  
 LONGITUDE -91.175773°

**NOTES:**

1. Existing 32'-0" x 44'-0" I-Beam Bridge Design No. 160 to be removed.
2. Flow line of culvert nominally buried 1 foot.
3. RCB culvert option shown.
4. U.S. 61 to be relocated on new alignment prior to this project. Roadway to become "Old U.S. 61" with significant reduction in traffic.
5. Drainage through existing channel must be maintained throughout construction.

**Estimated Revetment Quantities Included With Road Plans**

Location	Engineering Fabric (SY)	Excavation (CY)	Class "E" Revetment (Tons)
Outlet	111.5	55.0	104.6

Excavation quantity calculated from grading surface. Quantities shown for information only

**HYDRAULIC DESIGN**

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

*Mark D Werner* 9/12/2023  
 Signature Date  
 MARK D. WERNER  
 Printed or Typed Name  
 My license renewal date is December 31, 2023

Pages or sheets covered by this seal: V.01

PRELIMINARY

Design For 45° Skew (R.A.)  
**Twin 12'-0" x 8'-0" x 85'-0"**  
**Reinforced Concrete Box Culvert**

**Situation Plan**

Sta. 858+56.50 (US 61) June 2023


**Des Moines County**

IOWA DEPARTMENT OF TRANSPORTATION


Design No. TBD Design Sheet No. 1 of 2 FHWA/Asset 23500

PROGRESS PLANS, NOT FOR CONSTRUCTION


PROGRESS PLANS, NOT FOR CONSTRUCTION



LONGITUDINAL SECTION ALONG CL CULVERT




CLASS E REVETMENT  
OUTLET SPLASH BASIN



PROPOSED PROFILE  
GRADE U.S. 61

**DESIGNER NOTES**

1. Outlet revetment included due to high velocity
2. Revetment placed inside headwall to increase roughness and help reduce velocity as flow transitions to creek channel.



SITUATION PLAN

**UTILITIES LEGEND:**

- Power Pole - Eastern Iowa Electric
- FO2 - Buried Fiber Optic Line - Mediapolis Telephone Co.
- W - Buried Water Line - Rathbun Regional Water

**TRAFFIC ESTIMATE**

2021 AADT	5,100	V.P.D.
2026 AADT	130	V.P.D.
TRUCKS	15	%

**Hydraulic Data**

RIDB: Not Applicable  
Drainage Area = 1.9 Acres  
Stream Slope = 30.8 Ft./Mi.

Q<sub>50</sub> = 1,257 cfs  
HW Elev. = 690.78  
Exit Velocity = 13.0 fps

Q<sub>100</sub> = 1,508 cfs  
HW Elev. = 691.91  
Exit Velocity = 13.8 fps

**LOCATION**

US 61 OVER BRANCH SMITH CREEK  
T-72N R-3W  
SECTION 2  
YELLOW SPRING TOWNSHIP  
DES MOINES COUNTY  
FHWA NO. 23500  
BRIDGE MAINT. NO. 2958.75061  
LATITUDE 41.060404°  
LONGITUDE -91.175773°

**NOTES:**

1. Existing 32'-0"x44'-0" I-Beam Bridge Design No. 160 to be removed.
2. Flow line of culvert nominally buried 1 foot.
3. Precast culvert option shown.
4. U.S. 61 to be relocated on new alignment prior to this project. Roadway to become "Old U.S. 61" with significant reduction in traffic.
5. Drainage through existing channel must be maintained throughout construction.

**Estimated Revetment Quantities  
Included With Road Plans**

Location	Engineering Fabric (SY)	Excavation (CY)	Class "E" Revetment (Tons)
Outlet	143.7	55.0	116.8

Excavation quantity calculated from grading surface.  
Quantities shown for information only

**HYDRAULIC DESIGN**

PRELIMINARY

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

*Mark D Werner* 9/12/2023  
Signature Date

MARK D. WERNER  
Printed or Typed Name

My license renewal date is December 31, 2023

Pages or sheets covered by this seal: V.02

Design For 45° Skew (R.A.)  
**Twin 12'-0" x 8'-0" x 102'-0"**  
**Precast Concrete Box Culvert**

Situation Plan  
JUNE 2023

STA. 858+56.50 (US 61)  
Des Moines County  
IOWA DEPARTMENT OF TRANSPORTATION

Design No. TBD Design Sheet No. 2 of 2 FHWA/Asset 23500

## CROSS SECTION VIEW COLOR LEGEND

Design Color No.	Feature	Design Color No.	Feature
<b>Aggregate</b>			
(64)	Choke Stone	(112)	Noise Wall
(42)	Engineering Fabric	(112)	Noise Wall Footing
(8)	Flooded Backfill	(112)	Retaining Wall Back
(92)	Macadam Stone	(112)	Retaining Wall Back Excavate
(20)	Modified	(112)	Retaining Wall Face
(12)	Plowing Shaping	(112)	Retaining Wall Front Excavate
(14)	Porous Backfill	(112)	Retaining Wall Front Footing
(8)	Revetment Class A	(112)	Retaining Wall MSE Gutter
(6)	Revetment Class B	(112)	Retaining Wall Reinforced Earth
(62)	Revetment Class C		
(188)	Revetment Class D	<b>Grading</b>	
(28)	Revetment Class E	(8)	Behind Curb Cut
(12)	Shoulder Special Backfill	(6)	Granular
(12)	Special Backfill	(13)	Granular Back Fill
(20)	Subbase	(48)	Rock Undercut
(20)	Subbase Lower	(8)	Shoulder Earth Fill
(20)	Subbase Upper	(2)	Side Slopes
(118)	Subgrade Treatment	(226)	Side Slopes Dressing
<b>Asphalt</b>			
(207)	HMA Base Course	<b>Substrata</b>	
(207)	HMA Interim Course	(128)	Boulder Substrata
(207)	HMA Surface Course	(48)	Broken Weathered Substrata
<b>Concrete</b>			
(0)	Barrier Concrete	(3)	Core Out Substrata
(0)	Barrier Concrete Footing	(203)	Existing Pavement Substrata
(0)	Curb Gutter	(6)	Loam Substrata
(48)	Flowable Mortar	(80)	Rock Substrata
(0)	Median Concrete	(4)	Select Sand Substrata
(0)	PCC Pavement	(3)	Shale Substrata
(0)	Sidewalk	(10)	Topsoil Substrata
<b>Shoulder</b>			
(209)	Shoulder HMA	<b>Unsuitable / Waste</b>	
(0)	Shoulder PCC	(3)	Unsuitable Type A
(6)	Shoulder Granular	(13)	Unsuitable Type B
		(11)	Unsuitable Type C
		(3)	Waste
<b>Existing</b>			
(0)	Existing Pavement		

NOTES:



NOTES:

## CROSS SECTIONS LEGEND AND INFORMATION SHEET



(COVERS SHEET SERIES W, X, Y, & Z)





# US 61






# US 61





# US 61




# US 61



# US 61





STA. 859+70.52