
	INDEX OF SHEETS
NO.	DESCRIPTION
A. Sheets	Title Sheets
* A.3	Title Sheet
B. Sheets	Typical Cross Sections and Details
B.1 - 2	Typical Cross Sections and Details
C. Sheets	Quantities and General Information
C.1 - 2	Estimated Project Quantities
C.1 - 2	Estimate Reference Information
C.3	Project Description
C.3	Standard Road Plans
C.3	Index of Tabulations
C.3 - 6	Tabulations
CS. Sheets	Soils Tabulations
CS.1 - 3	Soils Tabulations
D. Sheets	Mainline Plan and Profile Sheets
* D.1	Plan & Profile Legend & Symbol Information Sheet
* D.2	IA 136
G. Sheets	Survey Sheets
G.1 - 3	Reference Ties and Bench Marks
G.4	Horizontal Control Tabulation
H. Sheets	Right-of-Way Sheets
* H.1	IA 136
J. Sheets	Traffic Control and Staging Sheets
J.1	Traffic Control Plan
* J.2 - 3	Detour Route and Signing Plan
Q. Sheets	Soils Sheets
* Q.1	Soils Legend & Symbol Information Sheet
* Q.2	Soils Sheets IA 136
RR. Sheets	Erosion Control Sheets
RC.1 - 6	Est. Quantities, PPP, General Notes and Tabulations
* RR.1	Erosion Control Legend and Symbol Information
* RR.2	Drainage Basin and Erosion Control Device Map
W. Sheets	Mainline Cross Sections
* W.1	Cross Sections Legend & Symbol Information Sheet
* W.2 -5	Mainline Cross Sections
	* Color Plan Sheets





	INDEX OF SEALS									
SHEET NO.	NAME	TYPE								
A.1	Michael J. Janechek	Primary Signature Block								
CS.1	Gary F. Miller	Geotechnical Design								

Roadway Design



I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

06-18-2024
Date


Signature Michael J. Janechek
Printed or Typed Name

My license renewal date is December 31, 2024

Pages or sheets covered by this seal:

A.3, B.1-2, C.1-6, D.1-2, G.1-4, J.1-3, RC.1-6, RR.1-2, W.1-

FILE NO. 32350 ENGLISH DESIGN TEAM IOWA DOT/Shive-Hattery CLINTON COUNTY PROJECT NUMBER BRF-136-1(101)--38-23 SHEET NUMBER A.3



FILE NO. **32350**

11:47:54 AM 4/22/2024

ENGLISH

Combination Shoulder Combination Shoulder Shoulder Jointing: Longitudinal joint: B Match Line Match Line Shoulder Jointing: Longitudinal joint: B 2_C_ 04-21-20 2_C_ 04-21-20 P G G PROFILE GRADE P STATION TO STATION STATION TO STATION Feet Feet Feet Feet 797+59.70 799+42.46 4 4 797+59.70 799+42.46 4 4 Modified Granular Subbase Shoulder Granular – Shoulder Modified Subbase Earth Shoulder Construction Earth Shoulder Construction 10" P.C. CONCRETE PAVEMENT) (6" HMA SHOULDER)— 6" HMA SHOULDER (6" MODIFIED SUBBASE) -Subdrain Mainline Jointing: Transverse joints: CD at 17' spacing Longitudinal joint: L-2 2P_ 04-21-20 STATION TO STATION 797+59.70 799+42.46 FILE NO. **32350** DESIGN TEAM IOWA DOT/Shive-Hattery CLINTON COUNTY PROJECT NUMBER BRF-136-1(101)--38-23 SHEET NUMBER B.2 ENGLISH 11:47:55 AM 4/22/2024 $pw:\lprojectwise.dot.int.lan: PWMain\locuments\lprojects\lambda 2313605020\locuments$

ES

ESTIMATED PROJECT QUANTITIES AND REFERENCE NOTES Roadway Items: Roadway Items
--

Item no.	Item Code	Item	Unit	Quantities Estimated Roadway Items	Estimate Reference Notes
1	2101-0850001	CLEARING AND GRUBBING	ACRE	1.2	All material generated as a result of Clearing and Grubbing shall become the property of the contractor and must be disposed off site. Quantity Included for area within ROW. All wood material must be disposed of according to Iowa Department of Agriculture and Land Stewardship Emerald Ash Borer Quarantine Order. For more information see www.iowatreepests.com.
2	2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED	CY	4,431	Includes 4,968 CY of fill material. Adding 30% shrink = 6,458 CY Subtracting 698 CY of cut material = 5,760 CY Factoring out shrink to establish bid item = 4,431 CY Overhaul will not be paid.
3	2102-2710070	EXCAVATION, CLASS 10, ROADWAY AND BORROW	CY	698	Includes cut material for removals to reach proposed subgrade. (698 CY of Cut). Shrink is not included.
4	2105-8425015	TOPSOIL, STRIP, SALVAGE AND SPREAD	CY	1,327	Refer to Tab. 103-6 on CS Sheets. Strip 12 inches of topsoil within the limits of grading. After excavating to the sub grade elevations, spread the stockpiled topsoil to an 8 inch depth across the grading area. Seed the disturbed topsoil stockpile area as per section 2601.05 of the standard specifications. Seeding of the stockpile areas shall be considered incidental to this bid item.
5	2107-0425020	COMPACTING BACKFILL ADJACENT TO BRIDGES, CULVERTS OR STRUCTURES	CY	109	Refer to Tab.104-4 on C Sheets.
6	2107-0875100	COMPACTION WITH MOISTURE CONTROL	CY	5,760	Refer to Tab. 103-6 on C Sheets. Cubic yards shown on the contract documents as determined by the template fill volume. Shrinkage will not be included in the moisture control quantity.
7	2115-0100000	MODIFIED SUBBASE	CY	325	Refer to Typicals on B Sheets and Tabulation 100-24 in the C Sheets.
8	2121-7425020	GRANULAR SHOULDERS, TYPE B	TON	51	Refer to Typical Section and Tabulation 112-9.
9	2122-5500080	PAVED SHOULDER, HOT MIX ASPHALT MIXTURE, 8 IN.	SY	163	
10	2123-7450000	SHOULDER CONSTRUCTION, EARTH	STA	3.72	Requires a minimum of 4 inches of topsoil. Place according to Article 2105.03,B of the Standard Specifications.
11	2301-1033100	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.	SY	487	Refer to Typical Section and Tabulation 100-24.
12	2402-0425040	FLOODED BACKFILL	CY	151	Refer to Tabulation 104-4.

Project Number:BRF-136-1(101)--38-23 SHEET C.1 Design Team : Shive-Hattery County Name :Clinton 05/31/2024 11:41 AM

ltom				Quantities	
Item no.	Item Code	Item	Unit	Estimated	Estimate Reference Notes
110.				Roadway Items	
13	2418-0000010	TEMPORARY STREAM DIVERSION	EACH	1	
14	2502-8212024	SUBDRAIN, LONGITUDINAL, (BACKSLOPE) 4 IN. DIA.	LF	485.6	Refer to CS Sheets.
15	2502-8221306	SUBDRAIN OUTLET, DR-306	EACH	4	Refer to CS Sheets.
16	2505-4008120	REMOVAL OF STEEL BEAM GUARDRAIL	LF	221	Refer to Tabulation 110-7A on C sheets. Includes removal and disposal of beams and posts.
17	2510-6745850	REMOVAL OF PAVEMENT	SY	320	Refer to Tabs.110-1 and 102-5 on C Sheets
18	2527-9263209	PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	STA	5.16	Refer to Tabulation 108-22 on C sheets.
19	2528-2518000	SAFETY CLOSURE	EACH	4	Refer to Tabulation 108-13A on C sheets. Item includes 2 hazard closures and 2 roadway closures.
20	2528-8445110	TRAFFIC CONTROL	LS	1	Refer to Traffic Control Plan and detour on J sheets. Contractor to furnish and install, maintain and remove all road closure signage and detour signage.
21	2548-0000100	MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	STA	3.66	Refer to Tab 112-10 on C-sheets.
22	2548-0000110	ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	GAL	4	
23	2548-0000320	MILLED CENTERLINE RUMBLE STRIPS, PCC SURFACE	STA	1.83	

Design Team : Shive-Hattery County Name :Clinton Project Number:BRF-136-1(101)--38-23 05/31/2024 11:41 AM SHEET C.2

100-1D 10-18-05

PROJECT DESCRIPTION

This project involves the replacement of the IA 136 bridge at the W Tributary of Elwood Creek located 1.9 miles north of US 61 with a twin 12' x 12' RCB culvert using an off-site detour.

INDEX OF TABULATIONS Tabulation Title Sheet No. C Sheets 100-0A 100-1D 100-4A ESTIMATED ROADWAY QUANTITIES (1 DIVISION PROJECT) PROJECT DESCRIPTION C.3 C.1-2 ESTIMATE REFERENCE INFORMATION C.6 C.4 100-24 P.C.C. PAVEMENT 102-5 EXISTING PAVEMENT C.5 C.3 C.5 C.6 C.4 C.4 104-4 105-4 108-13A 108-22 ROADWAY ITEMS FOR DRAINAGE STRUCTURES INSTALLED BY CULVERT CONTRACTOR STANDARD ROAD PLANS SAFETY CLOSURES PAVEMENT MARKING LINE TYPES 110-1 REMOVAL OF PAVEMENT REMOVAL OF STEEL BEAM GUARDRAIL 110-7A 110-13 DELIVERY AND STOCKPILING INDEX OF TABULATIONS SHOULDERS 111-25 C.3 C.5 MILLED RUMBLE STRIPS UTILITIES (POINT 25 PROJECT) 112-10 262-6

			105-4 10-18-11
		STANDARD ROAD PLANS	
		The following Standard Road Plans apply to construction work on this project.	
Number	Date	Title	
DR-101	04-18-17	Pipe Culvert (Bedding and Backfill)	
DR-111	04-17-18	Box Culvert (Backfill)	
DR-121	04-18-23	Connected Pipe Joints	
DR-202	10-17-23	Low Clearance Concrete Pipe Aprons	
DR-303	10-17-17	Subdrains (Longitudinal)	
DR-306	10-16-18	Precast Concrete Headwall for Subdrain Outlets	
EW-101	10-17-17	Embankment and Rebuilding Embankments	
EW-401	10-20-15	Temporary Stream Crossing, Causeway, or Equipment Pad	
PM-110	04-21-20	Line Types	
PV-101	04-19-22	Joints	
PV-12	10-20-20	Milled Shoulder Rumble Strips	
PV-13	10-17-17	Milled Centerline Rumble Strips	
TC-1	10-15-19	Work Not Affecting Traffic (Two-Lane or Multi-Lane)	
TC-202	04-18-23	Work Within 15 ft of Traveled Way	
TC-212	04-18-23	Spot Location Lane Closure with Flaggers	
TC-252	04-21-20	Routes Closed to Traffic	

102-5 04-18-17

EXISTING PAVEMENT

													131110									
				Locatio	on					Sur	face	В	ase	Subb	oase	Rem	oval	Coarse Agg	gregate		Reinforcement	
N		County	Route		Begin Ref. Loc. Sign	End Ref. Loc. Sign	Year	Type	Project Number	Туре	Depth IN	Туре	Depth IN	Туре	Depth IN	Туре	Depth IN	Source	Туре	Durability Class	Туре	Remarks
	1	23	IA 136	1	29.95	38.92	1995 1983		STPN-136-1(42)2J-23	AAC BSC	1.5	BAC	2					BEHR QRY.	C. LST.			
							1983 1971 1954		MP-136-6(30)76-2 FN-136-2(3)21-23 F-872 (3)	BAC AAC	1.5	TBB RSB	1.5					BLOORE/ELWOOD WEAVER	C. LST.			
							255.		. 6,2 (5)	7010	_								CV 23.1			
									LEGEND TYPE A ASPHALT CEMENT CON													
								BAC	TYPE B ASPHALT CEMENT CON													
								BSC	BITUMINOUS SEAL COAT													

262-5 10-18-05

UTILITIES

(POINT 25 PROJECT)

This is a POINT 25 project and is subject to the provisions of IAC 761-115.25.

110-1 04-16-13

REMOVAL OF PAVEMENT

* Not a Bid Ite	em		KE		bulation 102-	
Begin Station	End Station	Side	Pavement Type	Area	Saw Cut*	Remarks
797+59.70	798+20.00	BOTH	HMA	160.8	24.0	
798+83.00	799+42.46	BOTH	HMA	158.6	24.0	
			TOTAL:	319.4	48.0	

					110-7A 04-17-12
ı	REMO	VAL OF S	TEEL BEA	M GI	JARDRAIL
		to which the ins length of End T Location			
No.	Direction (_) of Traffic		o Station	Side	Removal of Guardrail
					LF
1	вотн	797+59.00	798+15.00	RT	56.0
2	вотн	797+60.00	798+15.00	LT	55.0
3	вотн	798+88.00	799+43.00	LT	55.0
4	BOTH	798+88.00	799+43.00	RT	55.0
			TOTAL:		221.0

					110-13 04-20-10
		DEL	IVERY AND STO	CKPILING	
Item Description	Ouantity	Units	Delivery Location	Contact Name & Number	Remarks
Existing steel beam guardrail	221	FT	Maintenance Garage	Kerry Burzlaff 563-590-2948	
Uncut and unbolted			2983 IA-62		
			Maquoketa, IA 52060		

SHOULDERS

Lane(s) to which the shoulder is adjacent.
Bid Item
Applies only for Paved Shoulders constructed on project with existing granular shoulders.
Does not include shrink.

Calculations assume a HMA unit weight (lbs/cf) of 145, a Special Backfill unit weight (lbs/cf) of 140, and a Granular Shoulder unit weight (lbs/cf) of 140.

* Calculated at 18" width for Shoulder.

		Location	cigc (103/ c. /	0. 1				(105/01) 01 140	,	<u> </u>	200. 0.120 1	erg.: (100)	c., c. 2.c.		Quantities									
Road	ion (†) ffic	Station to	Station	Side	P Width	G Width	L Length	Class 13 (3) Excavation	Hot Mix	Asphalt	Binder	Paved Shoulder	Temporary Pavement		Special	Backfill		Modified Subbase	Granular S	Shoulder	Earth Sho	ulder Cons Alternates		Remarks
Identification	Pra	Station to	Station	Side	WIUCII	width	Length								ternate		ternate				STA ²	HMA	PCC	
	Dir. Of .				FT	FT	FT	CY (2)	TON	TON/STA	TONS	SY (2)	SY ⁽²⁾	TON 2	TON/STA	TON 2	TON/STA	CY ⁽²⁾	TON ⁽²⁾	TON/STA	STA STA	CY (4)	CY (4)	
IA 136	вотн	797+59.70	799+42.46		4.0	4.0	182.8	54.2 54.2				81.2 81.2						27.1 27.1	25.6	14.0	1.83	60.9		
	вотн	797+59.70	799+42.46	RT	4.0	4.0	182.8	54.2				81.2						27.1	25.6	14.0	1.83	60.9		
			TOTALS:					108.3				162.5						54.2	51.2		3.66	121.8		

ROADWAY ITEMS FOR DRAINAGE STRUCTURES INSTALLED BY CULVERT CONTRACTOR

104-4 10-17-17

112-10 04-16-19

* Not a Bid (1)Backfill acc	to DI	R-111

(-) BUCKITIT UC						By F	Road Co	ntractor					Flooded					
Location	Design Number	Size	Kind	Rt.	Dike	Ton		Backfill	w/Moisture	Compaction w/Moisture	Floodable* Backfill	Porous* Backfill	Backfill 1	Excavation	Reve	tment	Engineering Fabric	Remarks
				Lt.	Location Station	Top. Elev.	Туре	Adjacent CY	Control CY	and Density CY	(A) CY	(B) CY	(A+B) CY	Type Quantity CY	Туре	Quantity TONS	SY	
798+55.00	525	ΓWIN 12'x12'x105'	RCB					108.8			140.0	11.0	151.0					
TOTALS:								108.8					151.0					

		108-13A 08-01-08
SAFE	TY CLOS	URES
to Section 25	18 of the Star	ndard Specifications
		Remarks
1		
1		
	1	
	1	
2	2	
	to Section 25 Closur	1 1 1 1

See PV-12 and PV-13.

			Loca	tion				Fog Seal*	Effe	ctive Shoulder N	Vidth	
	Road Identification	Station t	o Station	Shoulder Pavement Type	Rumble Strip Type (Centerline,	Len PCC	gth HMA	(Milled Rumble Strip) Shoulder	PCC Paved	HMA Paved	Granular∖ Earth	Remarks
				ravellenc Type	Rt or Lt Shoulder)	STA	STA	GAL	FT	FT	FT	
	TA 426	707.50 70	700 : 42 46	1100	Diebt Charles		4 02	3.0		1.0	4.0	
-	IA 136	797+59.70	799+42.46	HMA	Right Shoulder		1.83	2.0		4.0	4.0	
-		797+59.70	799+42.46	HMA	Left Shoulder	1.00	1.83	2.0		4.0	4.0	
		797+59.70	799+42.46	PCC	Centerline	1.83						
_												
			TOTALS:			1.83	3.66	4.0				

PAVEMENT MARKING LINE TYPES

See PM-110

***MNY4 - Factor of 1.00 as value includes number of 4-inch passes to cover median nose area. *BCY4 - Place on the same side of the roadway to match existing markings near the project.

**NPY4 - For estimating purposes only. No Passing Zone Lines will be located in the field.

DCY6: Double Centerline (Yellow) @ 2.00 ELW6: Edge Line Left (White) @ 1.00


ELW6: Edge Line Right (White) @ 1.00

FILE NO. 32350 ENGLISH DESIGN TEAM IOWA DOT\SHIVE-HATTERY

				Location								Le	ength by Li	ine Type	(Unfactore	ed)						
Road ID	Station to	Station	Dir. of	Marking Type	Sid	de	BCY4*	DCY4	NPY4**	BLW4	ELW4	ELY4	SLW2									Remarks
			Travel	3 7.	L C	R	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	
136	797+59.70	799+42.46	ВОТН	Waterborne/Solvent Paint	X	_					1.83											
. 150	797+59.70	799+42.46		Waterborne/Solvent Paint	X			1.83			1.05											
	797+59.70	799+42.46		Waterborne/Solvent Paint		Х					1.83											
										_	3.66		_	_	<u> </u>	-	_	_	<u> </u>	_		
							_	_	_	_	-	_	-	_	-	-	_		_	_	-	
							-	-	-	-	-	-	-	-	-	-	-	_	-	- 1	-	
				Factored Total: Waterborne/Solvent Paint			-	1.50	-	-	3.66	-	-	-	-	-	-	-	-	-	-	
							L															
				Bid Quantity: Painted Pavement Markings, Water	rborne or	POTA	nt-Basea	I		5.16					-				-			

100-24 04-21-15

PCC PAVEMENT



1 Does not include raised island area or curb. Refer to tabulation 112-4 for quantities.

SHEET NUMBER

C.6

- (2) Refer to PV-410, PV-411, PV-412, and PV-414.
- (3) Quantity includes Pavement Header.

BRF-136-1(101)--38-23

	Location				Mainline	2				Are	a (3)				Total Ar	rea By		Ι				
Road Identification	Direction of Travel	Station	to Station	Width	Length	Area	A	В	С	D	E	F	G	(H)	Pavem Thickr	ent ness		Modified Subbase	Granular Subbase		Remarks	
				FT	FT	SY	SY	SY	SY	SY	SY	SY	SY	SY	10 IN	TEMP	TONS	CY	SY			
IA 136	BOTH	797+59.70	799+42.46	24.0	182.8	487.4									487.4			270.8				
												'	TOTALS:		487.4			270.8				

CLINTON COUNTY PROJECT NUMBER

EMBANKMENT WITH MOISTURE CONTROL

Moisture Control is required for all Class 10 fill placed in all locations and depths. Topsoil will not require Moisture Control.



I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Gary F. Miller, P.E.

Date

License Number P25343

My license renewal date is December 31, 2024.

Pages or sheets covered by this seal: CS.1-CS.3 & Q.1-Q.2.

FILE NO.

ENGLISH DESIGN TEAM Iowa DOT/Shive-Hattery/

CLINTON COUNTY PROJECT NUMBER BRF-136-1(101)--38-23

SHEET NUMBER CS.1

SI	HRINKAGE DA	10 8/2
Material	%	Remarks
Class 10	30.0	
Topsoil	40.0	
Estimated Boulder Quantity	0.0	10 CY Class 12 Excavation

104_	09A
12/8	3/22

* Not a bid item.

Line No.	Road or Lane Identification	Station From	Station To	Side	Depth (IN) (D)	Subdrain Size (IN)		Outlet Station	Outlet Type	Porous Backfill* (CY)	Remarks
1.0	IA 136	797+59.70	799+42.46	Left	42.0	4.0	212.8	797+59.70	DR-306	19.7	Use Type 7A Installation
2.0				Left			30.0	799+42.46	DR-306		
3.0	IA 136	797+59.70	799+42.46	Right	42.0	4.0	212.8	797+59.70	DR-306	19.7	Use Type 7A Installation
4.0				Right			30.0	799+42.46	DR-306		
	·		•		•	•	•			· ·	_

LONGITUDINAL SUBDRAIN SHOULDER

FILE NO. ENGLISH DESIGN TEAM IOWA DOT/Shive-Hattery/ CLINTON COUNTY PROJECT NUMBER BRF-136-1(101)--38-23 SHEET NUMBER CS.3

SURVEY SYMBOLS Septic Tank Interstate Highway Symbol U.S. Highway Symbol Cistern (LP) Iowa Highway Symbol L.P. Gas Tank (No Footing) County Road Highway Symbol Underground Storage Tank Evergreen Tree Latrine Deciduous Tree Satellite TV Dish Fruit Tree Water Hook Up Shrub (Bushes) □ RT Radio Tower Timber Tower Anchor Hedge Guardrail (Beam or Cable) 2 Stump Guard Post (one or two) Guard Post (over two) Ш≣ Rock Outcrop Filler Pipe 0000 **Broken Concrete** Gas Valve Revetment (Rip Rap) Water Valve † Cemetery Speed Limit Sign ¦G] Grave Mile Marker Post (CV) Cave ☐ SIGN Sign (SH) Sink Hole □ TCB Traffic Signal Control Box Board Fence □ RRB Rail Road Signal Control Box # Chain Link or Security Fence □ TSB Telephone Switch Box Wire Fence Electric Box Terrace Earth Dam or Dike (Existing) Tile Outlet Edge of Water **Existing Drainage** Right of Way Rail or Lot Corner Concrete Monument Well Windmill Beehive Intake Existing Intake Existing Utility Access (Manhole) Fire Hydrant WH Water Hydrant (Rural)

UTILITY LEGEND

Sub-Surface Utility Mapping Quality Level is in accordance with CI/ASCE 38-02 Standard Guidelines for the Collection and Depiction of Existing Subsurface Utility Data.


Remark Abbreviations


QLA Quality Level A Highest guideline quality level QLD Quality Level D Lowest guideline quality level



Alliant - Quality D

PLAN VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS LINEWORK Design Color No. (2) Existing Topographic Features and Labels Green Blue Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation Magenta Existing Utilities SHADING Design Color No. Temporary Pavement Shading Lavender (9) Yellow Proposed Pavement Shading (4) (6) Proposed Granular Shading Orange Proposed Shoulder Granular Shading Orange (70)Yellow (68)Proposed Shoulder Paved Full Depth Shading Yellow (132)Proposed Shoulder Paved Partial Depth Shading Gray, Dark (112) Proposed Grade and Pave Shading "In conjunction with a paving project" Brown, Light (236)**Grading Shading** (134) Proposed Granular Entrance Shading Orange, Light Yellow (220) Proposed Paved Entrance Shading Proposed Sidewalk Shading Tan Blue, Light Proposed Sidewalk Landing Shading (230) Pink Proposed Sidewalk Ramp Shading (11) Green, Light (225) Existing Pavement Shading Red Proposed Structure Shading Delineates Restricted Areas Red





Proposed Right-of-Way

Existing Right of Way

Existing and Proposed Right-of-Way

Easement and Existing Right-of-Way

Easement (Temporary)

Easement

Access Control


Property Line

RIGHT-OF-WAY LEGEND

PLAN AND PROFILE LEGEND AND SYMBOL INFORMATION SHEET

(COVERS SHEET SERIES D, E, F, & K)

FILE NO. 32350 | ENGLISH | DESIGN TEAM IOWA DOT/Shive-Hattery



Survey Information

Clinton County BRF-136-1(101)—38-23 IA 136 Bridge over Branch Prairie Creek 1.9mi N of US 61 PIN 20-23-136-050 Sap-766.4

Party Personnel

Eddie Charles - Survey Party Chief

Date(s) of Survey

Begin Date 08/23/2021 End Date 10/22/2021

General Information

Measurement units for this survey are US survey feet. This survey is for proposed Bridge reconstruction and reconstruction of IA 136 over Branch Prairie Creek 1.9mi N. of US 61. Project datum and control information is provided by Shive-Hattery, Inc. This project is a Preliminary DTM Field Survey. This survey request was for the IA 136 corridor, Bridge over Branch Prairie Creek and Branch Prairie Creek.

Vertical Control

IARTN

Vertical datum for this survey is NAVD88 (Computed using Geoid12B). Additional benchmarks were placed throughout the project using a Total Station setup relative to Point 1 and Point 2. Vertical control was verified between control points with check shots by Total Station through multiple setup from various occupation points with a vertical error of less than 0.05 feet.

This survey found (2) local control benchmark monuments (benchmark disc and benchmark 'cut X' on bridge abutment in NW corner bridge of State Highway 136). No vertical information was available at the time field work was completed.

Horizontal Control

(Project Coordinates from Redundant IaRTN Observations)

The project coordinate system is modified Iowa Regional Coordinate System Zone 11 (U.S. Survey Feet This survey control is relative to the IaRTN reference stations.

observations with appropriate occupation times. Additional control points were placed throughout the project using a Total Station setup relative to Point 1 and Point 2.

Utility Information

Sub-Surface Utility Mapping Quality Level is in accordance with CI/ASCE 38-02 Standard Guidelines for the Collection and Depiction of Existing Subsurface Utility Data.

Remark abbreviations

QLA – Quality Level A Highest guideline quality level QLD – Quality Level D Lowest guideline quality level

A One-call utility locate request (Ticket# 552104698) was made July 2, 2021. The following Companies were listed:

(ASE) ALLIANT ENERGY

Contact Name: Alliant Energy Field Engineer

Contact Phone: 8002554268

Contact Email: locate IPL@alliantenergy.com


(LN1) LOST NATION-ELWOOD TELEPHONE

Contact Name : Jody Holtz Contact Phone: 5636782470

Contact Email: jody@lencomm.com

CONTROL POINT VICINITY MAP

This map is a guide to the vicinity of the primary project control points
Primary control is for use with RTK base stations and for RTN validation.
Future surveys will use primary project control to establish temporary control as needed for construction or other surveying applications.



HORIZ. DATUM: NAD83(2011) EPOCH 2010.00

VERT. DATUM: NAVD88

Ia. Regional Coordinate System Zone 11

Coordinate listing from next sheet will be used with IaRTN for monument recovery. No other reference ties are given.

PROJECT NUMBER BRF-136-1(101)--38-23

SHEET NUMBER

G.2

HORIZONTAL AND VERTICAL PROJECT CONTROL COORDINATE LISTING

HORIZ. DATUM: NAD83(2011) EPOCH 2010.00

VERT. DATUM: NAVD88

Ia. Regional Coordinate System Zone 11 Project Control Marks are Bench Marks


POINT NAME	Υ	X	Z	FEATURE DEFINITION - DESCRIPTION
1	8239086.430	21456230.280	734.590	СР
2	8239046.100	21455016.650	741.340	СР
3	8239051.940	21455811.180	731.520	СР
4	8239079.890	21455894.060	732.330	СР
5	8239065.447	21456244.840	735.700	PK NAIL PT
101	8239086.432	21456230.280	734.588	СР
102	8239046.097	21455016.630	741.400	СР
493	8239081.755	21455830.94	734.101	CUT X
6190	8239082.7820'	21455829.4300'	734.763'	BRASS

NOTE:

The first two digits in the control point name refer to the county number. The next 3 digits refer to the highway number. The next 3 digits refer to the highway milepost. The last digit refers to the distance from the referenced milepost to the nearest tenth of a mile.

FILE NO. 32350	ENGLISH	DESIGN TEAM IOWA DOT/Shive-Hattery	CLINTON:OUNTY	PROJECT NUMBER BRF-136-1(101)38-23	SHEET NUMBER G.3	
-----------------------	---------	------------------------------------	---------------	------------------------------------	------------------	--

								Align	ment Coord	inates									101-16 04-19-11
Element	Lasstian	Po	int on Tang	ent		Begin Spira	l		Begin Curve	e	Simple Cu	rve PI or M SCS	aster PI of		End Curve			End Spiral	
Number	Location	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)	Station	Y (Northing)	X (Easting)
1	ML136	79532.128 R1	8239065.955	21455541.670															
2	ML136	79759.698 R1	8239066.249	21455769.240															
3	ML136	79985.569 R1	8239065.898	21455995.110															
3	ML136	80240.349 R1	8239066.357	21456249.890															



108-26A 08-01-08

TRAFFIC CONTROL PLAN

108-234 08-01-08

With IA 136 traffic using detour, remove and replace bridge over the stream with a culvert.

Reopen IA 136 to normal traffic pattern.

1) While bridge and approaches are being removed and replaced with RCB culvert, IA 136 traffic shall be maintained via an off-site detour. Detours are furnished, maintained and removed by the Contractor. Refer to TC-252 for road closure and advanced signage details.

2) Contractor will furnish, install, maintain, and remove detour signs. All existing signs that conflict with detour shall be covered. These functions shall be included in the Traffic Control Bid Item.

> 108-25 10-21-14

511 TRAVEL RESTRICTIONS

Route	Direction	County	Location Description	Feature Crossed	Object Type	Maint. Bridge No., Structure ID, or FHWA No.	Type of Restriction	_	Construction Measurement	Construction Measurement as Signed	Projected As Built Measurement	Remarks
			No Travel Restrictions Expected									

111-01 04-17-12


STAGING NOTES


COORDINATED OPERATIONS


Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.


Project	Type of Work
BRF-136-1(97)38-23	Bridge Replacement
BRF-136-1(99)38-23	RCB Culvert Replacement
BRF-136-1(103)38-23	RCB Culvert Replacement
BRF-136-1(105)38-23	RCB Culvert Replacement

J.1









Erosion	Control	Items ·	Fresion	Control	ltems
	COHUO	itellis .		COHUO	IIGIIIS

				Quantities	
Item	Item Code	Item	Unit	Estimated	Estimate Reference Notes
no.	nom couc	ite		Erosion Control Items	
1	2601-2634100	MULCHING	ACRE	1.2	Perform mulching according to Article 2601.03, E, 2, of the Standard Specifications. Anchor mulch into the soil using mulch anchoring equipment with a minimum of two passes. Item is included for areas requiring reshaping and seedbed preparation. Use mulch that is Certified Noxious Weed Seed Free Mulch as certified by the lowa Crop Improvement Association or adjacent states Crop Improvement Associations.
2	2601-2636015	NATIVE GRASS SEEDING	ACRE	1	Seed all areas outside eight feet adjacent to outside shoulder along mainline, side roads, and infield areas at interchanges with "Native Grass Seeding". Supply all seed for "Native Grass Seeding". Apply all forb seed through the native grass drill wildflower or small seed box. Do not mix and apply Forb seed with the native grass seed. Apply cover crop through the cool season or through cover crop seed box. Do not mix and apply cover crop seed with the native grass seed. Remove seed remaining in the drill at the end of each day. At the completion of all seeding, remove remaining seed from the drill by vacuum or other means. Hand broadcast remaining seed on the project. The Owner's Representative will review the limits with the Contractor prior to seeding. Mulch Rate: 1 1/2 tons of dry cereal straw or native grass straw per acre.
3		SEEDING AND FERTILIZING (RURAL)	ACRE	0.1	Seed and fertilize all areas 8 foot adjacent to the shoulder mainline, medians, and side according to Article 2601.03, C, 3, of the Standard Specifications. Use ground driven equipment. Supply all seed for "Rural Grass Seeding" Do not mix and apply cover crop seed with the rural grass seed. Remove seed remaining in the drill at the end of the day. At the completion of all seeding, remove remaining seed from the drill by vacuum or other means. Hand broadcast remaining seed on the project. The Owner's Representative will review the limits with the Contractor prior to seeding.
4	2001-2042100	STABILIZING CROP - SEEDING AND FERTILIZING	ACRE	1.1	Item is included for disturbed areas. Seed and fertilize all disturbed areas according to Article 2601.03, C, 1, of the Standard Specifications. If permanent seeding cannot be placed due to the restrictive planting dates, stabilizing crop will need to be placed on all disturbed areas as temporary erosion control. Preparation and seeding shall be performed in accordance with Section 2601. Stabilizing crop will not be used when the application dates in Section 2601 allows permanent seeding. If stabilizing crop must be used, place immediately following completions of finished grading. Reseeding of these areas will be required at contractors expense if damage occurs due to contractors negligence during the contract period. It is not necessary to place stabilizing crop in locations that have be covered by Wood Excelsior Mat.

Design Team : Shive-Hattery County Name :Clinton Project Number:BRF-136-1(101)--38-23 05/17/2024 10:29 AM SHEET RC.1

				Quantities	
Item	Item Code	ltem	Unit	Estimated	Estimate Reference Notes
no.				Erosion Control Items	
5	2602-0000020	SILT FENCE	LF	620	Refer to Tab. 100-17. The tabulation includes estimated locations for placement of "Silt Fence" to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 25% additional quantity for field adjustments and replacements.
6	2602-0000030	SILT FENCE FOR DITCH CHECKS	LF	44	Refer to Tab 100-18. The tabulation includes estimated locations for placement of "Silt Fence for Ditch Checks" to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes tab quantities for the paving project for new locations and 10% of the original tab quantity for the grading project (insert original tab quantity from the grading project) for field adjustments and replacements. See Standard Note 232-10 and Standard Road Plan EC-201. See Sheet RR.2 for locations. The engineer may adjust silt fence locations to fit field conditions.
7	2602-0000071	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	LF	664	This item is included for silt fence and silt fence for ditch check removal required for staging reasons, removal to allow for replacement (replacement to be paid separately), or for areas that have achieved 70% permanent growth. This item is included for silt fence and silt fence for ditch check removal. Remove silt fence and posts after mulching or vegetation is established and approved by the engineer.
8	2602-0000101	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	LF	93	This item is included for maintaining the new silt fence and silt fence ditch checks installed for the paving project and existing silt fence and silt fence ditch checks installed as part of the grading project.
9		STABILIZED CONSTRUCTION ENTRANCE, EC-303	LF	200	
10	2602-0000312	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	LF	1,400	Refer to Tab. 100-19. The tabulation includes estimated locations for placement of "Perimeter and Slope Sediment Control Device, 12 in. dia." to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 25% additional quantity for field adjustments and replacements.
11		PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	LF	200	Refer to Tab. 100-19. The tabulation includes estimated locations for placement of "Perimeter and Slope Sediment Control Device, 20 in. dia." to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 25% additional quantity for field adjustments and replacements. Use Perimeter and Slope Sediment Control Devices fabricated using wood excelsior.
12		REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	LF	1,600	
13	2602-0010010	MOBILIZATIONS, EROSION CONTROL	EACH	1	
14	2602-0010020	MOBILIZATIONS, EMERGENCY EROSION CONTROL	EACH	1	

Design Team : Shive-Hattery County Name :Clinton Project Number:BRF-136-1(101)--38-23 05/17/2024 10:29 AM SHEET RC.2

			105-4 10-18-11
		STANDARD ROAD PLANS	
		The following Standard Road Plans apply to construction work on this project.	
Number	Date	Title	
EC-201	04-20-21	Silt Fence	
EC-204	04-19-16	Perimeter and Slope Sediment Control Devices	
EC-502	04-21-15	Seeding in Rural Areas	

	111-25 10-18-11 INDEX OF TABULATIONS						
Tabulation	Tabulation Title	Sheet No.					
RC Sheets							
100-1A	ESTIMATED PROJECT QUANTITIES (1 DIVISION PROJECT)	RC.1-2					
100-4A	ESTIMATE REFERENCE INFORMATION	RC.1-2					
100-17	TABULATION OF SILT FENCES	RC.4					
100-18	SILT FENCE FOR DITCH CHECKS	RC.4					
100-19	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE	RC.4					
105-4	STANDARD ROAD PLANS	RC.3					
110-12	POLLUTION PREVENTION PLAN	RC.5-RC.6					
111-25	INDEX OF TABULATIONS	RC.3					

281-1 10-18-16

SECTION 404 PERMIT AND CONDITIONS

Construct this project according to the requirements of U.S. Army Corps of Engineers Nationwide, Permit 14, Permit No. 2023-0228 A copy of this permit is available from the Iowa DOT website (http://www.envpermits.iowadot.gov/). The U.S. Army Corps of Engineers reserves the right to visit the site without prior notice.


281-3 10-17-17

STORM WATER BEST MANAGEMENT PRACTICES

When the following best management practices are used, they are intended to account for disturbed areas where storage volume cannot be provided: Wood Excelsior Mat for Ditch Protection, Silt Fence, Silt Fence for Ditch Protection, Perimeter and Slope Sediment Control Devices

CLINTON COUNTY PROJECT NUMBER BRF-136-1(101)--38-23 SHEET NUMBER RC.3

				100-17 04-20-16
TAI	BULATION	_		FENCES
		fer to	EC-201	
L	ocation		Length	
Begin Station	End Station	Side	LF	Remarks
797+02.00	797+87.00	LT	105.0	
798+50.00	799+63.00	LT	133.0	
799+17.00	800+08.00	LT	111.0	
797+12.00	797+39.00	RT	47.0	
797+71.00	798+64.00	RT	113.0	
798+98.00	799+54.00	RT	76.0	
799+69.00	799+84.00	RT	35.0	
S	F Tab Totals:		620	
S	F Bid Totals:		775	125% of Tab Total
SF Mainte	nance Totals:		78	10% of Bid Total
SF Re	moval Totals:		775.0	100% of Bid Total



100-19 04-19-16 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE Possible Standards: EC-204 Location Length of Installation 9 inch Dia | 12 inch Dia | 20 inch Dia Remarks Begin Station End Station Side 800+15.00 798+77.00 799+84.00 796+94.00 321 798+05.00 797+12.00 72 272 798+32.00 799+00.00 797+71.00 799+70.00 797+42.00 799+52.00 798+21.00 Culvert Edge Culvert Edge 798+52.00 798+46.00 Entrance 798+13.00 Entrance 798+59.00 798+88.00 Culvert Edge Culvert Edge 798+65.00 Entrance 798+95.00 Entrance 798+00.00 Ditch Check Ditch Check Ditch Check 798+49.00 20 20 799+22.00 799+51.00 Ditch Check PSSCD Tab Totals: 1115 12 inch PSSCD Bid Totals: 20 inch PSSCD Bid Totals: PSSCD Removal Totals: 125% of Tab Total 125% of Tab Total 100% of Bid Total 1400 200 1600

POLLUTION PREVENTION PLAN

This project is regulated by the requirements of the Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) General Permit No. 2 OR an Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) individual storm water permit. The Contractor shall carry out the terms and conditions of this permit and the Pollution

This Base PPP includes information on Roles and Responsibilities, Project Site Description, Controls, Maintenance Procedures, Inspection Requirements, Non-Storm Water Controls, Potential Sources of Off Right-of-Way Pollution, and Definitions. This plan references other documents rather than repeating the information contained in the documents. A copy of this Base Pollution Prevention Plan, amended as needed during construction, will be readily available for review.

All contractors shall conduct their operations in a manner that controls pollutants, minimizes erosion, and prevents sediments from entering waters of the state and leaving the highway right-of-way. The Contractor shall be responsible for compliance and implementation of the PPP for their entire contract. This responsibility shall be further shared with subcontractors whose work is a source of potential pollution as defined in this PPP.

I. ROLES AND RESPONSIBILITES

- A. Designer:
 - 1. Prepares Base PPP included in the project plan.
- 2. Prepares Notice of Intent (NOI) submitted to Iowa DNR.
- 3. Is signature authority on the Base PPP. If consultant designed, signature from Contracting Authority is also required.
- - 1. Signs a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP. All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
 - 2. Designates a Water Pollution Control Manager (WPCM), who has the duties and responsibilities as defined in Section 2602 of the Standard Specifications.
 - 3. Submits an Erosion Control Implementation Plan (ECIP) and ECIP updates according to Section 2602 of the Standard Specifications. 4. Installs and maintains appropriate controls. This work may be subcontracted as documented through Subcontractor Request Forms
 - (Form 830231).
 - 5. Supervises and implements good housekeeping practices according to Paragraph III, C, 2.
 6. Conducts joint required inspections of the site with inspection staff. When Contractor is not mobilized on site, Contractor may delegate this responsibility to a trained or certified subcontractor. Contracting Authority also may waive joint inspection requirement during winter shutdown. In both circumstances, WPCM (or trained or certified delegate from the Contractor) is still responsible to review and sign inspection reports.
 - 7. Complies with training and certification requirements of Section 2602 of the Standard Specifications.
 - 8. Submits amended PPP site map according to Section 2602 of the Standard Specifications.
- C. Subcontractors:
- 1. Sign a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP if: responsible for sediment or erosion controls; involved in land disturbing activities; or perorming work that is a source of potential pollution as defined in this PPP. Subcontracted work items are identified in Subcontractor Request Forms (Form 830231). All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
- 2. Implement good housekeeping practices according to Paragraph III, C, 2.
- D. RCE/Project Engineer:
- 1. Is Project Storm Water Manager.
- 2. On projects where DOT is the Contracting Authority, is current with erosion control training or certification.
- 3. Takes actions necessary to ensure compliance with storm water requirements including, where appropriate, issuing stop work orders, and directing additional inspections at construction project sites that are experiencing problems with achieving permit compliance.
- 4. Orders the taking of measures to cease, correct, prevent, or minimize the consequences of non-compliance with the storm water requirements of the Applicable Permit.
- 5. Supervises all work necessary to meet storm water requirements at the Project, including work performed by contractors and subcontractors.
- 6. Requires employees, contractors, and subcontractors to take appropriate responsive action to comply with storm water requirements, including requiring any such person to cease or correct a violation of storm water requirements, and to order or recommend such other actions as necessary to meet storm water requirements.
- 7. Is familiar with the Project PPP and storm water site map.
- 8. On projects where DOT is Contracting Authority, is responsible for periodically monitoring inspection reports to determine whether deficiencies identified in inspection reports were adequately and timely addressed, and if not, has the authority and responsibility to direct immediate actions to correct the deficiencies.
- 9. Is the point of contact for the Project for regulatory officials, Inspector, contractors, and subcontractors regarding storm water requirements.
- 10. Is signature authority on Notice of Discontinuation.
- 11. Maintains an up-to-date record of contractors, subcontractors, and subcontracted work items through Subcontractor Request Forms (Form 830231).
- 12. Makes information to determine permit compliance available to the DNR upon their request.
- E. Inspector:
 - 1. Updates PPP through fieldbook entries and storm water site inspection reports if there is a change in design, construction,
 - operation, or maintenance which has a significant effect on the discharge of pollutants from the project.
 - 2. Makes information to determine permit compliance available to the DNR upon their request. 3. Conducts joint required inspections of the site with the contractor/subcontractor.
- 4. Completes an inspection report after each inspection.
- 5. Is signature authority on storm water inspection reports.

II. PROJECT SITE DESCRIPTION

- A. This Pollution Prevention Plan (PPP) is for the construction of a Box Culvert as a bridge replacement.
- B. This PPP covers approximately 1.2 acres with an estimated 1.00 acres being disturbed. The
- portion of the PPP covered by this contract has 1.00 acres disturbed. C. The PPP is located in an area of Tama-Muscatine-Downs soil association
- The estimated weighted average runoff coefficient number for this PPP after completion will be 0.37.
- D. Storm Water Site Map is located in the R sheets. Proposed slopes are shown in cross sections, details, or standard road plans. Supplemental information is located in the Tabulations in the C or CE sheets.
- E. The base storm water site map is amended by contract modifications and progress payments (fieldbook entries) of completed erosion control work. Also, due to project phasing, erosion and sediment controls shown on project plans may not be installed until eeded, based on site conditions. For example, silt fence ditch checks will typically not be installed until the ditch has bee

POLLUTION PREVENTION PLAN

installed. Installed locations may also be modified from tabulation locations by field staff. Installed locations will be documented by fieldbook entries and amended PPP site map.

- F. Runoff from this work will flow into West Tributary of Elwood Creek.
- III. CONTROLS
- A. The Contractor's ECIP specified in Article 2602.03 of the Standard Specifications for accomplishment of storm water controls should clearly describe the intended sequence of major activities, and for each activity define the control measure and the timing during the construction process that the measure will be implemented.
- B. Preserve vegetation in areas not needed for construction.
- C. Sections 2601 and 2602 of the Standard Specifications define requirements to implement erosion and sediment control measures. Actual quantities used and installed locations may vary from the Base PPP and amendment of the plan will be documented via fieldbook entries, amended PPP site map, or by contract modification. Additional erosion and sediment control items may be required as determined by the inspector and/or contractor during storm water site inspections. If the work involved is not applicable to any contract items, the work will be paid for according to Article 1109.03 paragraph B of the Standard Specifications.
 - 1. EROSION AND SEDIMENT CONTROLS
 - a. Stabilization Practices
 - 1) Site plans will ensure that existing vegetation or natural buffers are preserved where attainable and disturbed portions of the site will be stabilized.
 - 2) Initialize stabilization of disturbed areas immediately after clearing, grading, excavating, or other earth disturbing activities have:
 - a) Permanently ceased on any portion of the site, or
 - b) Temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days.
 - 3) Staged permanent and/or temporary stabilizing seeding and mulching shall be completed as the disturbed areas are completed. Incomplete areas shall be stabilized according to paragraph III, C, 1, a, 2, b above.
 - 4) Permanent and Temporary Stabilization practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation (105-4) in the C or R sheets.
 - 5) Preservation of existing vegetation within right-of-way or easements will act as vegetative buffer strips.
 - 6) Preservation of topsoil: Bid items to be used for this project are located in the Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets. Additional information may be found in the Tabulations in the C or T Tabulation sheets, or is referenced in Section 2105 of the Standard Specifications.
 - b. Structural Practices
 - 1) Structural practices will be implemented to divert flows from exposed soils and detain or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Additionally, structural practices may include: silt basins that provide 3600 cubic feet of storage per acre drained or equivalent sediment controls, outlet structures that withdraw water from surface when discharging basins, and controls to direct storm water to vegetated areas.
 - 2) Structural practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the devices to be used on this project can be found on the B or R sheets or are referenced in the Standard Road Plans Tabulation (105-4) located in the C or R sheets.
 - c. Storm Water Management

Measures shall be installed during the construction process to control pollutants in storm water discharges that will occur after construction operations have been completed. This may include velocity dissipation devices at discharge locations and along length of outfall channel as necessary to provide a non-erosion velocity flow from structure to water course. If included with this project, these items are located in the storm water site map and Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation. The installation of these devices may be subject to Section 404 of the Clean Water Act.

Contractor disposal of unused construction materials and construction material wastes shall comply with applicable state and local waste disposal, sanitary sewer, or septic system regulations. In the event of a conflict with other governmental

laws, rules and regulations, the more restrictive laws, rules or regulations shall apply.

- a. Vehicle Entrances and Exits Construct and maintain entrances and exits to prevent tracking of sediments onto roadways.
- b. Material Delivery, Storage and Use Implement practices to prevent discharge of construction materials during delivery, storage, and use.
- c. Stockpile Management Install controls to reduce or eliminate pollution of storm water from stockpiles of soil and paving.
- d. Waste Disposal Do not discharge any materials, including building materials, into waters of the state, except as authorized by a Section 404 permit.
- e. Spill Prevention and Control Implement chemical spill and leak prevention and response procedures to contain and clean up spills and prevent material discharges to the storm drain system and waters of the state.
- f. Concrete Residuals and Washout Wastes Waste shall not be discharged to a surface water and is not allowed to adversely affect a water of the state. Designate temporary concrete washout facilities for rinsing out concrete trucks. Provide directions to truck drivers where designated washout facilities are located. Designated washout areas should be located at least 50 feet away from storm drains, streams or other water bodies. Care should be taken to ensure these facilities do not overflow during storm events.
- g. Concrete Grooving/Grinding Slurry Do not discharge slurry to a waterbody or storm drain. Slurry may be applied on foreslopes or removed from the project.
- h. Vehicle and Equipment Storage and Maintenance Areas Perform on site fueling and maintenance in accordance with all environment laws such as proper storage of onsite fuels and proper disposal of used engine oil or other fluids on site. Employ washing practices that prevent contamination of surface and ground water from wash water. Wash waters must be treated in a sediment basin or alternative control that provides equivalent or better treatment prior to discharge.
- i. Litter Management Ensure employees properly dispose of litter. Minimize exposure of trash if exposure to precipitation or storm water would result in a discharge of pollutants.
- Dewatering Properly treat water to remove suspended sediment before it re-enters a waterbody or discharges off-site. Measures are also to be taken to prevent scour erosion at dewatering discharge point.
- 3. APPROVED STATE OR LOCAL PLANS

During the course of this construction, it is possible that situations will arise where unknown materials will be encountered. When such situations are encountered, they will be handled according to all federal, state, and local regulations in effect at 110-12 10-20-20

POLLUTION PREVENTION PLAN

IV. MAINTENANCE PROCEDURES

The Contractor is required to maintain all temporary erosion and sediment control measures in proper working order, including cleaning, repairing, or replacing them throughout the contract period. This shall begin when the features have lost 50% of their capacity.

V. INSPECTION REQUIREMENTS

- A. Inspections shall be made jointly by the Contractor and the Contracting Authority's inspector at least once every seven calendar days. Storm water site inspections will include:
- 1. Date of the inspection.
- 2. Summary of the scope of the inspection.
- 3. Name and qualifications of the personnel making the inspection.
- 5. Review of erosion and sediment control measures within disturbed areas for the effectiveness in preventing impacts to receiving waters.
- 6. Major observations related to the implementation of the PPP.
- 7. Identification of corrective actions required to maintain or modify erosion and sediment control measures.
- B. Include storm water site inspection reports in the Amended PPP. Incorporate any additional erosion and sediment control measures determined as a result of the inspection. Immediately begin corrective actions on all deficiencies found within 3 calendar days of the inspection and complete within 7 calendar days following the inspection. If it is determined that making the corrections less than 72 hours after the inspection is impracticable, it should be documented why it is impracticable and indicate an estimated date by which the corrections will be made.

VI. NON-STORM WATER DISCHARGES

This includes subsurface drains (i.e. longitudinal and standard subdrains) and slope drains. The velocity of the discharge from these features may be controlled by the use of headwalls or blocks, Class A stone, erosion stone or other appropriate materials. This also includes uncontaminated groundwater from dewatering operations, which will be controlled as discussed in Section III of the PPP.

VII. POTENTIAL SOURCES OF OFF RIGHT-OF-WAY (ROW) POLLUTION

Silts, sediment, and other forms of pollution may be transported onto highway right-of-way (ROW) as a result of a storm event. Potential sources of pollution located outside highway ROW are beyond the control of this PPP. Pollution within highway ROW will be conveyed and controlled per this PPP.

VIII. DEFINITIONS


- A. Base PPP Initial Pollution Prevention Plan.
- B. Amended PPP Base PPP amended during construction. May include Plan Revisions or Contract Modifications for new items, storm water site inspection reports, fieldbook entries made by the inspector, amended PPP site map by the Contractor, ECIP, NOI, co-permittee certifications, and Subcontractor Request Forms. Items amending the PPP are stored electronically and are readily available upon request.
- C. Fieldbook Entries This contains the inspector's daily diary and bid item postings.
- D. Controls Methods, practices, or measures to minimize or prevent erosion, control sedimentation, control storm water, or minimize contaminants from other types of waste or materials. Also called Best Management Practices (BMPs).
- E. Signature Authority Representative authorized to sign various storm water documents.


......

CERTIFICATION STATEMENT

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature	
Printed or Typed Name	
Signature	





CELL L	EGEND OF EROSION CONTROL SHEETS
CELL	Design Element
	Temporary Sediment Control basin
•	Erosion Control for Circular Intake or Manhole Well
0	Erosion Control for Rectangular Intake or Manhole Well
	Grate Intake Sediment Filter Bag
	Silt Basin
Lee	Silt Fence Tail
—	Stormwater Drainage Basin Discharge Point


PLAN VIEW COLOR LEGEND OF EROSION CONTROL SHEETS LINEWORK Design Color No. Green (2) Existing Topographic Features and Labels Blue (1) Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation Existing Utilities Magenta Black (0) Permanent Erosion Control Features Blaze Orange (222) Temporary Erosion Control Features SHADING Design Color No. Transparency Citron (234) Mulching, All Types 50% (238) Special Ditch Control, Wood Excelsior Mat 0% Light Brown Grass Green (233) 8FT Mow Strip 50% Red (3) Delineates Restricted Areas 0%


PATTERN LEGEND C	OF EROSION CONTROL SHEETS
Seeding and Fertilizing	Turf Reinforcement Mat Type 1
Seeding and Fertilizing (Rural)	Turf Reinforcement Mat Type 2
Seeding and Fertilizing (Urban)	Turf Reinforcement Mat Type 3
Native Grass Seeding	Turf Reinforcement Mat Type 4
Salt Tolerant Seeding	Slope Protection, Wood Excelsior Mat
Wetland Grass Seeding	Transition Mat
Wildflower Seeding	Per Per Rock Features, Permanent
Sob	్రార్థ్ గాంగ్రార్థ్ స్టార్థ్ స్టార్థ్ స్టార్థ్

EROSION CONTROL
LEGEND AND SYMBOL
INFORMATION SHEET

(COVERS SHEET SERIES R)

FILE NO. 32350 ENGLISH DESIGN TEAM IOWA DOT/Shive-Hattery





	NOTES:	
Text		
	NOTES:	
Text		

CROSS SECTIONS LEGEND AND INFORMATION SHEET

(COVERS SHEET SERIES W, X, Y, & Z)

FILE NO. 32350 ENGLISH DESIGN TEAM IOWA DOT/Shive-Hattery CLINTON: OUNTY PROJECT NUMBER BRF-136-1(101)--38-23 SHEET NUMBER W.1

