	INDEX OF SHEETS
No.	DESCRIPTION
A Sheets	Title Sheets
* A.1	Title Sheet
* A.2	Location Map Sheet
* A.3 - 27	Concept
* A.28	Questions
B Sheets	Typical Cross Sections and Details
B.1 - 5	Typical Cross Sections and Details
D Sheets	Mainline Plan and Profile Sheets
* D.1	Plan & Profile Legend & Symbol Information Sheet
* D.2 - 3	US 20
E Sheets	Side Road Plan and Profile Sheets
* E.1 - 2	US 59
G Sheets	Survey Sheets
G.1 - 3	Reference Ties and Bench Marks
G.4 - 5	Horizontal Control Tab. & Super for all Alignments
	* Color Plan Sheets



PLANS OF PROPOSED IMPROVEMENT ON THE

PRIMARY ROAD SYSTEM

Unknown Pavement - Grade and New

W of W Jct US 59 to E of E Jct US 59

SCALES: As Noted

Refer to the Proposal Form for list of applicable specifications,

Value Engineering Saves, Refer to Article 1105,14 of the Specifications,





REVISIONS

Schedule

PROJECT IDENTIFICATION NUMBER 24-47-020-010 PROJECT NUMBER HSIPX-020-2(157)--3L-47 R.O.W. PROJECT NUMBER

> D03 - 09/05/2025 D05 - 12/19/2025 DM5 - 08/03/2027

D08 - 09/06/2027

DES	IGN [DATA RURAL
20 27	AADT	<u>3500</u> V.P.D.
20 47	AADT	<u>4700</u> V.P.D.
20 47	DHV	480 V.P.H.
TRUCK	S	<u>27</u> %
Total Design	ESALs	

ı	INDEX OF SEALS							
1	SHEET NO.	NAME	NAME TYPE					
1	A.1	X	Primary Signature Block X					
ı								
ı	Х	X	X	X				
ı								
ı								
ı								
J								




Subject to change by final design.

D2 PLAN - Date: Ø8/21/2025

DESIGN TEAM SCHROCK/TAMRAKAR

IDA COUNTY

PROJECT NUMBER HSIPX-020-2(157)--3L-47



IOWA DEPARTMENT OF TRANSPORTATION

TO OFFICE: District 3 **DATE:** June 18, 2024

ATTENTION: Jessica Felix **PROJECT:** Ida County

HSIPX-020-2(157)--3L-47

FROM: John Bartholomew PIN: 24-47-020-010

BUREAU: Design

SUBJECT: 2025 – HSIP-(District allocation) Project Concept - **FINAL**

The Draft Project Concept Statement was sent out for review and comments with concerns to be resolved by Wednesday, June 18, 2025. Comments received during the review period have been considered and resolved.

DATE OF REVIEW: January 03, 2024;

<u>PARTICIPANTS</u>: District – Shane Tymkowicz, Darwin Bishop, Kelly Mulvihill, Todd Huju, Laura Sievers, Dylan Pryor; Materials – Chris Brakke, Danny Zeimen; Design -Kevin Patel, John, Bartholomew, Anthony Apland

The three alternatives considered were:

- 1. Reconstruct existing intersections at US20 and US 59 (west/east Junctions) into reduced conflict (RCUT) intersections. Estimated cost of \$2,015,865
- 2. Reconstruct the existing intersections at US 20 and US 59 (west/east Junctions) into roundabout intersections. Estimated cost of \$6,107,760
- 3. Add intersection traffic signals at both east and west junctions of US 20 and US 59. Estimate cost \$507,500. This alternative was dismissed

Alternative 1 is the preferred alternative due to improved safety, lower right of way impacts, corridor continuity, and lower cost. Estimated FY '28 construction cost \$2,300,450

PROJECT DATA:

ROUTE: US-20 From W of W Jet US 59 to E of E Jet US 59

LENGTH: 2 miles

PLANNING CLASSIFICATION: COMMERCIAL AND INDUSTRIAL NETWORK

MAINTENANCE SERVICE LEVEL: PRINCIPAL ARTERIAL

TRAFFIC: 2027 --- 3500 ADT with 27% trucks 2047 --- 4700 ADT with 27% trucks

Ida County HSIPX-020-2(157)--3L-47 PIN: 24-47-020-010 Page 2

PRESENT PAVEMENT SURFACE: PCC PRESENT PAVEMENT WIDTH: 24 ft.

PRESENT SHOULDER WIDTH: 4 ft. TYPE: COMBO PAVED AND GRAVEL

MP to MP	Dir.	Туре	Avg. Str. No.	80% Str. No.	Jt. Str. No.	PCI	IRI	K Value
45.02 to 47	1	PCC	Null	Null	Null	92	53	Null

PAVEMENT HISTORY:

Original pavement: 18ft wide, 10in PCC, Varying width shoulders

Year constructed: Pre 1964

Coarse aggregate source: Ft. Dodge min / Class: Crushed Limestone

Year: 1964, Resurface with widening: 24ft wide, AAC (1.5in), 10ft Paved / Gravel

shoulders

Coarse aggregate source: Cherokee / Class: Gravel

Year: 1991, Resurfaced: AAC (3in)

Coarse aggregate source: Cherokee / Class: Gravel

Year: 1999, Resurfaced: MSS

Coarse aggregate source: Dell Rapids / Class: Quartz

Year: 2012, Resurfaced: HMA resurface (1.5in), 2in scarification

Year: 2018, Grade and New, 10in PCC Coarse aggregate Class: Modified Subbase

EXISTING CONDITIONS AND CAUSES OF DISTRESS:

Overall the existing pavement is good condition with no noticeable signs of deterioration along the longitudinal or transverse joints. This project is being pursued for improves intersection safety and performance.

FILE NO. -- ENGLISH DESIGN TEAM SCHROCK/TAMRAKAR

5:03:18 PM 8/16/2025 jacker1 pw:\\NTPwint1.dot.int.lan:PWMain\Documents\Projects\4702001024\Design\CADD Files\Sheet Files\SHT 47020157Z04 A01.dgn

IDA COUNTY

PROJECT NUMBER HSIPX-020-2(157)--3L-47

Ida County HSIPX-020-2(157)--3L-47 PIN: 24-47-020-010 Page 3



Eastview 2023

Westview 2023

SAFETY CONSIDERATION:

During the five-year study period from January 1, 2020 through December 31, 2024, there were 32 crashes including, 1 fatal crashes, 2 serious injury crashes, 5 minor injusy crashes, 2 unknown injury crashes, and 22 property damage crashes. The PCR rating is "3.452", Considered High.

FEASIBLE ALTERNATES:

ALTERNATIVE 1: RECONSTRUCT INTO REDUCED CONFLICT (RCUT) **INTERSECTIONS:**

US 20 in the project area is a 4-lane divided highway with 6 ft. inside and 10 ft. outside combination shoulders, and a 50 ft wide median. Existing pavement was reconstructed in 2018 with 10 in. PCC pavement.

These intersections are located on US 20 at mileposts 45.42 (west junction) and 46.83 (east junction). These intersections have been flagged as 'High' for all crashes, and severe crashes.

To improve safety at these intersections, both east and west junctions of US 20 and US 59 will be reconstructed with a reduced conflict (RCUT) design. This intersection design will close off US 59 through traffic from crossing 4-lanes of US 20, and also remove the US 29 Ida County HSIPX-020-2(157)--3L-47 PIN: 24-47-020-010 Page 4

to US 20 left turn movements by utilizing a raised median with a standard curb to prevent these movements. The proposed work will include reconstruction of US 20 to US 59 left turn lanes, and US 20 to US 59 right turn lanes. The project will also include paved turn arounds for the RCUT left turning movements. The existing median intersection, paved and granular shoulders at the intersections will be removed and replaced with 10 in. PCC pavement on top of 12 in. of modified subbase with 100 percent modified subdrain coverage.


Traffic on US 20 will remain open during construction, however, lane closures will be necessary during construction of the turn lanes. Traffic on US 59 may need to be detoured during the intersection and raised median construction.

STAGING:

Stage 1: Shift US 20 traffic to the outside lanes, reconstruct median turn lanes and RCUT turn-arounds. Remove US 59 to U 20 left turning movement at east junction:



(US 20/59 west junction)




(US 20/59 east junction)

Ida County HSIPX-020-2(157)--3L-47 PIN: 24-47-020-010 Page 5

Stage 2: Shift US 20 traffic to the median lanes. Reconstruct outside turning lanes and intersection connections to US 59. Temporary detours may be needed for US 59 traffic at this stage:



(US 20/59 west junction)



Ida County HSIPX-020-2(157)--3L-47 PIN: 24-47-020-010 Page 6

Stage 3: Open to Traffic



(US 20/59 west junction)



(US 20/59 east junction)

Rumble strips will be milled into the inside and outside shoulders. No safety edge is required on the mainline paved shoulders.

Right of way is not required for this project.

ESTIMATED COST:

Item	Estimated Cost
PCC Pavement	\$574,875
Subgrade prep	38,325
Granular Subbase	91,980
Excavation, Class 10 borrow	90,600
Granular shoulder removal	50,000
Topsoil, strip salvage and spread	95,130
Longitudinal Subdrains (Includes Outlets)	96 000

Ida County

HSIPX-020-2(157)--3L-47

PIN: 24-47-020-010

Page 7

Paved Median (PCC)	128,000
Granular shoulder	50,000
Pavement Markings	35,000
Signing	17,000
Erosion control	50,000
Surface restoration	27,000
Staging (10%)	134,391
Traffic Control (5%)	67,195
Mobilization (5%)	67,196
M & C (30%)	403,173
Total Alternative No. 1	\$2,015,865

ALTERNATIVE 2: RECONSTRUCT INTO ROUNDABOUT INTERSECTIONS

US 20 in the project area is a 4-lane divided highway with 6 ft. inside and 10 ft. outside combination shoulders, and a 50 ft wide median. Existing pavement was reconstructed in 2018 with 10 in. PCC pavement.

These intersections are located on US 20 at mileposts 45.42 (west junction) and 46.83 (east junction). These intersections have been flagged as 'High' for all crashes, and severe crashes.

To improve safety at these intersections, both east and west junctions of US 20 and US 59 will be reconstructed with roundabout intersections utilizing staged construction. The existing mainline pavement, paved and granular shoulders at the intersections will be removed and replaced with 10 in. PCC pavement on top of 12 in. of modified subbase with 100 percent modified subdrain coverage.

Lanes within the roundabout will be 12 ft. with a 3 ft. sloped curb on the inside and a 25 ft. wide truck apron. Surmountable truck aprons will be included on all quadrants of the roundabout.

Temporary pavement/shoulder strengthening may be needed for staged traffic shifts.

Since this alternative was not selected, detail staging notes were not developed for the concept document.

Right of way may be required for this alternative.

Ida County HSIPX-020-2(157)--3L-47 PIN: 24-47-020-010 Page 8

FINAL CONDITION:



(east junction US20/US59)

Ida County

HSIPX-020-2(157)--3L-47

PIN: 24-47-020-010

Page 9

ESTIMATED COST:

<u>Item</u>	Estimated Cost
Excavation, Class 10	\$216,000
Granular subbase	246,540
Subbase prep	102,725
Modified subbase	66,150
Topsoil, strip salvage and spread	113,400
Longitudinal subdrain	91,200
Pavement removal	633,600
PCC Pavement, 10 in.	1,560,825
PCC pavement, 13.5 in	464,400
Median	210,000
Pavement markings	28,500
Signing (includes trusses)	260,000
Surface restoration	28,500
Erosion control	50,000
Traffic Control (5%)	203,592
Mobilization (5%)	203,592
Staging (10%)	407,184
M & C (30%)	<u>1,221,552</u>
Total Alternative No. 2	\$6,107,760

RECOMMENDATIONS:

The recommended method of rehabilitation for this project is reconstructing the intersections at US 20 and US 59 (east and west junctions) with reduced conflict (RCUT) intersections as shown in Alternative 1. Estimated FY '28 construction cost \$2,300,450

Right of way will not be required

FUNDS PROGRAMMED:

This proposed HSIP project is not listed in the 2026-2030 program. It has been identified by the district 3 office for construction in FY 2028. A schedule of events for plan development will be determined following approval of the Project Concept. Note, if project exceeds district allocated HSIP funding, the remainder of the project will be funded through district 3R funds.

Ida County

HSIPX-020-2(157)--3L-47

PIN: 24-47-020-010

Page 10

JEB:

S. Tracy

FHWA

B. Waltersdorf

cc:

C. Purcell	K. D. Nicholson	Y. Jia
M. Dell	J. S. Nelson	M. Nop
M. A. Swenson	D. E. Sprengeler	C. C. Poole
S. Majors	A. Poole	K. Brink
D. L. Newell	D. Breitbach	J. W. Laaser-Webb
W. A. Sorenson	E. C. Wright	M. E. Ross
A. A. Welch	J. Harris	M. Van Dyke
B. Hofer	G. Karssen	D. Johnson
D. Lorenzen	S. Anderson	D. Stokes
J. Holst	R. Harris	B. Dolan
T. Lovan	M. Solberg	T. Gustafson
D. Dudley	L. Armstrong	B. Smith
A. Yates	C. Brakke	A. Buss
D. Zeimen		
J. Klemme	S. Tymkowicz	M. Solberg
J. Becker	T. Huju	M. Thayer

B. Strueker

PROJECT NUMBER HSIPX-020-2(157)--3L-47

C. Schwienebart

SHEET NUMBER A.7

J. Pottorff

T. Quam







US 20 & US 59 Intersection Study Single Lane- Pavement Marking Concept ■

Ida County, Iowa 4/4/2024

FILE NO. --

DESIGN TEAM SCHROCK/TAMRAKAR

IDA COUNTY

PROJECT NUMBER HSIPX-020-2(157)--3L-47







US 20 & US 59 Intersection Study

Reduced Conflict Intersection (RCI) Concept

Ida County, Iowa 3/27/2024

SHEET NUMBER A.09 PROJECT NUMBER $pw: \NTPwint1.dot.int.lan: PWMain \Documents \Projects \A702001024 \Design \CADD_Files \Sheet_Files \ShT_47020157Z04_A01.dgn$



FILE NO. --

NGLISH DESIGN T

SNYDER & ASSOCIATES

DESIGN TEAM SCHROCK/TAMRAKAR

US 20 & US 59 Intersection Study

Roundabout Intersection Concept

Ida County, Iowa

3/27/2024

IDA COUNTY

PROJECT NUMBER HSIPX-020-2(157)--3L-47

			تاسمي	TILITO		Y EVAL	UATIO	100	L (ICL)	1 100	E33 IC	JOL 31	AGE 2				
Project Name:	US 20 & US 59	E Jct					Review N										
Intersection:	US 20 at US 59						Review N	_									
Location:	: Holstein, IA						Attendee	s (List):									
Analyst:	TDC			Date:	2/14/2024	4											
						7.	CONTE	XT & EQ	UITY SU	MMARY	1						
udy area travel modes vesent and/or likely:				nsit	No key cor	nsiderations	/ Studies (<mark>s were ident</mark>	ified from th	he data.								
avel needs for ansporation mode(s):	Access to US highw	ays. No pede	strian or bicycle a	ccess is nee	ded.		The focus The percei	area percer	ition with a	panic and l	Latin was sl less in the f	ightly highe focus area,	r in the focu 14.0% com	s area (4.3%) co pared to 16.3%.	mpared to 3.9% i	n the comp	arison area.
story of neighborhood & ad development:	Very little change ov	ver time. US 2	?0 recently widens	ed to 4-lane o	divided east	of intersecti	The percer	ntage of pop	overty was s pulation und much lower	ler 10 years	s was high i	n the focus	area but lov	ver for the 75yea n the compariso	rs and over group า area.	ing.	
urrounding land uses / adside development:	Rural, one residence	e south of inte	ersection and one	west of inter	section.												
							8. SF	LECTIO	N CRITE	RIA							
		Meets Equity	Stakeholder		ge Vehicle		Wor	st Vehicle I	Delay	20-Flag	Results		ve Safety	Construction	Life Cycle		
tersection Form		Goals?	Support	AM Peak	PM Peak	Mid Day	AM Peak	PM Peak	Mid Day	Ped	Bike	PDO	Fatal/Inj	Cost	Costs	B/C	Environmental Feasib
ultilane Roundabout		Yes	Unknown	5	5	-	5	5	-	-	-	0.15	0.03	\$2,764,810	\$2,808,581	-	No perceived impac
CUT / J-Turn (stop co	ontrol)	Yes	Unknown	8	9	-	34	34	-	-	-	0.25	0.08	\$660,585	\$675,175	-	No perceived impac
raffic Signal		Yes	Unknown	10	10	-	10	10	-	-	-	1.28	0.26	\$217,500	\$330,319	-	No perceived impac
inor Street Stop (TW	SC)	Yes	Unknown	2	2	-	15	16	-	-	-	0.33	0.17	\$0	N/A	N/A	No perceived impac
					9. RE	VIEW M	EETING	NOTES	AND RE	COMME	ENDATIO	ONS					
ecommended Inter	rsection Concer	ot:	<select r<="" td=""><td>ecomme</td><td>nded Al</td><td>ternative</td><td>e></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></select>	ecomme	nded Al	ternative	e>										
otes from review tea	am meeting:																

Existing Traffic Analysis Results				AM Peal	ί.		PM Peal	(
Intersection	Control Type	Approach / Movement	Delay / Vehicle (s)	LOS	95th % Queue (ft)	Delay / Vehicle (s)	LOS	95th % Queue (ft)
		Eastbound	10	В	64	10	A	41
		Westbound	10	A	40	8	A	35
	Signal	Northbound	9	A	37	7	A	23
		Southbound	7	A	31	6	A	47
		Overall	10	A	-	8	A	-
		Eastbound Left	9	A	-	9	A	-
		Westbound Left	9	A	-	9	A	-
		Northbound Left	42	D	-	41	D	- 1
	DOLLE	Northbound Thru	42	D	-	41	D	-
	RCUT	Northbound Right	10	A	-	10	A	-
		Southbound Left	41	D	-	42	D	-
US 20 & US 59		Southbound Thru	41	D	-	42	D	-
(West Jct)		Southbound Right	10	A	_	10	A	_
		Eastbound	5	A	22	5	A	16
		Westbound	6	A	22	5	A	19
	RAB	Northbound	6	A	15	5	A	6
		Southbound	5	A	12	6	A	26
		Overall	6	A	-	5	A	-
		Eastbound	5	A	22	5	A	16
	RAB	Westbound	4	A	15	3	A	9
	(WB RT	Northbound	6	A	15	5	A	6
	Bypass Lane)	Southbound	5	A	12	6	A	26
		Overall	5	A	-	5	A	-
	Stop Control	Northbound	11	В	6	12	В	10
	(NB)	Westbound Left	8	A	0	8	A	0
		Eastbound	4	A	20	4	A	24
	G:1	Westbound	17	В	42	16	В	40
	Signal	Northbound	12	В	38	12	В	42
US 20 & US 59		Overall	10	В	-	10	A	-
(East Jct)		Westbound Left	8	A	-	9	A	-
(East Jet)	RCUT	Northbound Left	34	С	-	34	С	-
		Northbound Right	10	A	-	10	A	-
		Eastbound	4	A	15	5	A	19
	RAB	Westbound	5	A	13	5	A	13
	KAD	Northbound	5	A	6	5	A	9
		Overall	5	A	-	5	A	-

Opening Y	ear (2027) Ana	alysis Results	,	AM Peal	ζ	PM Peak		
Intersection	Control	Approach /	Delay /	LOS	95th %	Delay / LOS		95th %
Intersection	Type	Movement	Vehicle (s)	LUS	Queue (ft)	Vehicle (s)	LOS	Queue (ft)
		Eastbound	11	В	70	10	A	43
		Westbound	11	В	43	8	A	37
	Signal	Northbound	9	A	39	7	A	24
		Southbound	8	A	33	7	A	49
		Overall	10	В	-	8	A	-
		Eastbound Left	9	A	-	9	A	-
		Westbound Left	9	A	-	9	A	-
		Northbound Left	42	D	-	41	D	-
	RCUT	Northbound Thru	42	D	-	41	D	-
	RCUI	Northbound Right	10	A	-	10	A	-
		Southbound Left	42	D	-	42	D	-
US 20 & US 59		Southbound Thru	42	D	-	42	D	-
(West Jct)		Southbound Right	10	A	-	11	В	-
		Eastbound	6	A	25	5	A	19
		Westbound	6	A	25	5	A	19
	RAB	Northbound	7	A	15	6	A	6
		Southbound	6	A	15	6	A	29
		Overall	6	A	-	6	A	-
		Eastbound	6	A	25	5	A	19
	RAB	Westbound	4	A	15	3	A	12
	(WB RT	Northbound	7	A	15	6	A	6
	Bypass Lane)	Southbound	6	A	15	6	A	29
		Overall	5	A	-	5	A	-
	Stop Control	Northbound	12	В	8	13	В	10
	(NB)	Westbound Left	8	A	0	8	A	0
		Eastbound	4	A	22	4	A	25
	6: 1	Westbound	16	В	47	17	В	43
	Signal	Northbound	12	В	39	13	В	47
110 20 0 110 50		Overall	10	В	-	10	A	-
US 20 & US 59 (East Jct)		Westbound Left	8	A	-	9	A	-
(East JCt)	RCUT	Northbound Left	34	С	-	34	С	-
		Northbound Right	10	A	-	10	A	-
		Eastbound	5	A	15	5	A	19
	DAD	Westbound	5	A	16	5	A	13
	RAB	Northbound	5	A	9	5	A	9
		Overall	5	A	-	5	A	-


Design Ye	ar (2047) Ana	lysis Results		AM Peal	ζ		Z .	
Intersection	Control	Approach /	Delay /	LOS	95th %	Delay /	LOS	95th %
Theer section	Type	Movement	Vehicle (s)		Queue (ft)	Vehicle (s)		Queue (ft)
		Eastbound	16	В	114	11	В	65
		Westbound	12	В	60	10	В	54
	Signal	Northbound	13	В	52	8	A	31
		Southbound	10	A	44	8	A	70
		Overall	14	В	-	10	A	-
		Eastbound Left	10	A	-	9	A	-
		Westbound Left	9	A	-	9	A	-
		Northbound Left	43	D	-	42	D	-
	RCUT	Northbound Thru	43	D	-	42	D	-
	Reor	Northbound Right	11	В	-	11	A	-
US 20 & US 59		Southbound Left	43	D	-	44	D	-
		Southbound Thru	43	D	-	44	D	-
(West Jct)		Southbound Right	11	В	-	12	В	-
		Eastbound	7	A	37	6	A	28
	RAB	Westbound	7	A	37	6	A	28
		Northbound	9	A	28	7	A	12
		Southbound	7	A	23	9	A	49
		Overall	7	A	-	7	A	-
		Eastbound	7	A	37	6	A	28
	RAB	Westbound	5	A	25	3	A	15
	(WB RT	Northbound	9	A	28	7	A	12
	Bypass Lane)	Southbound	7	A	23	9	A	49
		Overall	6	A	-	6	A	-
	Stop Control	Northbound	14	В	12	16	С	20
	(NB)	Westbound Left	8	A	0	9	A	0
		Eastbound	4	A	31	4	A	37
	G:1	Westbound	31	С	103	30	С	95
	Signal	Northbound	15	В	48	17	В	58
US 20 & US 59		Overall	17	В	-	15	В	-
(East Jct)		Westbound Left	9	A	-	9	A	-
(East Jet)	RCUT	Northbound Left	35	С	-	35	С	-
		Northbound Right	10	В	-	10	В	-
		Eastbound	5	A	22	5	A	28
	D.A.D.	Westbound	5	A	22	5	A	19
	RAB	Northbound	5	A	12	6	A	14
		Overall	5	A	-	5	A	-


NCHRP 17-98 Equity Assessment Worksheet - Stage 2

Instructions

This worksheet is intended to record the results from the Stage 1 and Stage 2 Equity assessment, developed through project NCHRP 17-98: Guide for Intersection Control Evaluation. All fields are designed as either open-ended answer fields to document Stage 1 assessment questions or as tables to record the more detailed demographic assessment completed in Stage 2. For further detailes, the user is encouraged to consult the final project report and the example problem contained there. An agency is open to customize this worksheet to fit its specific equity assessment process.

	Over	rview	
Project Name	US 20 & US 59 E Jct	Organization	Iowa DOT / Snyder & Associates, Inc.
Major Roadway	US 20	Analyst	Tim Crouch
Minor Rowadway	US 59	Data Completed	2/20/2025
Analysis Year	2019-2023	Link to Location	





	Safe	ety Performan	ce for Intersection	n Control Evaluation To	ool
			Results		
		Sumr	mary of crash prediction results f	or each alternative	
			Project Informati	on	
Project Name:	US 20 & US 59 Inters	ections Study		Intersection Type	At-Grade Intersections
Intersection:	US 20 & S Main St (U	S 59) - East Junction		Opening Year	2027
Agency:	Snyder & Associates			Design Year	2047
Project Reference:	S&A Project # - 123.1	1784.01B		Facility Type	On Rural Multilane Highway
City:	Holstein			Number of Legs	3-leg
State:	lowa				
Date:	February 26th, 2025				
Analyst:	BMG				
			Crash Prediction Sun	nmary	
Control Strategy	Crash Type	Opening Year	Design Year	Total Project Life Cycle	AADT Within Prediction Range?
1-lane Roundabout	Total	0.12	0.18	3.04	N/A
1-lane Roundabout	Fatal & Injury	0.02	0.03	0.44	N/A
2-lane Roundabout	Total	0.12	0.18	3.04	N/A
2-laile Noullabout	Fatal & Injury	0.02	0.03	0.44	N/A
Minor Road Stop	Total	0.33	0.50	8.69	Yes
Willion Road Stop	Fatal & Injury	0.11	0.17	2.95	res
Traffic Signal	Total	No SPF	No SPF	No SPF	Yes
Hairic Signal	Fatal & Injury	No SPF	No SPF	No SPF	163
Unsignalized RCUT	Total	0.21	0.33	5.65	N/A
Choighanzea 11001	Fatal & Injury	0.05	0.08	1.36	1971

PROJECT NUMBER HSIPX-020-2(157)--3L-47



ENGINEER'S PRELIMINARY OPINION OF PROBABLE PROJECT COST

UPDATED 03/20/25

US 20 & US 59 EAST JUNCTION - RCUT HOLSTEIN, IOWA

DESCRIPTION	E Jct RCUT QUANTITY	UNIT	UI	NIT PRICE	E Jct RCUT COST	COMMENTS
EXCAVATION, CLASS 10 ROADWAY AND BORROW	2600	CY	\$	12.00	\$ 31,200.00	
GRANULAR SUBBASE	2100	SY	\$	12.00	\$ 25,200.00	
SUBGRADE PREP	2100	SY	\$	5.00	\$ 10,500.00	
TOPSOIL, STRIP SALVAGE AND SPREAD	2600	CY	\$	12.60	\$ 32,760.00	
SUBDRAIN	4000	LF	\$	12.00	\$ 48,000.00	
GRANULAR SHOULDER REMOVAL	700	SY	\$	20.00	\$ 14,000.00	
PAVEMENT, PCC	2000	SY	\$	78.75	\$ 157,500.00	
GRANULAR SHOULDER	700	SY	\$	20.00	\$ 14,000.00	
PAVED MEDIAN, PCC	500	SY	\$	80.00	\$ 40,000.00	
PAVEMENT MARKINGS	1	LS	\$	15,000.00	\$ 15,000.00	
SIGNAGE	1	LS	\$	7,000.00	\$ 7,000.00	
SURFACE RESTORATION	1	LS	\$	12,000.00	\$ 12,000.00	
EROSION CONTROL & SWPPP	1	LS	\$	7,000.00	\$ 7,000.00	
TRAFFIC CONTROL (5%)	1	LS	\$	20,708.00	\$ 20,708.00	
MOBILIZATION (5%)	1	LS	\$	20,708.00	\$ 20,708.00	

Subtotal: \$ 455,576

Other Project Costs

ENGINEERING (15%) \$ 68,336 CONTINGENCY (30%) \$ 136,673

TOTAL PROJECT COST: \$ 660,585

 $V: \label{thm:linear_control_cost} V: \label{thm:linear_cost} V: \label{t$

3/20/2025 Page 3 of 4

FILE NO	ENGLISH	DESIGN TEAM SCHROCK/TAMRAKAR	IDA COUNTY	PROJECT NUMBER HSIPX-020-2(157)3L-47	SHEET NUMBER A.16	
---------	---------	------------------------------	------------	--------------------------------------	-------------------	--



ENGINEER'S PRELIMINARY OPINION OF PROBABLE PROJECT COST

UPDATED 03/20/25

US 20 & US 59 EAST JUNCTION - ROUNDABOUT HOLSTEIN, IOWA

DESCRIPTION	E Jct RAB QUANTITY	UNIT	UNI	IT PRICE	E Jct RAB COST	COMMENTS
EXCAVATION, CLASS 10 ROADWAY AND BORROW	8000	CY	\$	12.00	\$ 96,000.00	
GRANULAR SUBBASE	9100	SY	\$	12.00	\$ 109,200.00	
SUBGRADE PREP	9100	SY	\$	5.00	\$ 45,500.00	
SPECIAL BACKFILL	800	CY	\$	36.75	\$ 29,400.00	
TOPSOIL, STRIP SALVAGE AND SPREAD	4000	CY	\$	12.60	\$ 50,400.00	
SUBDRAIN	3600	LF	\$	12.00	\$ 43,200.00	
PAVEMENT REMOVAL	7040	SY	\$	40.00	\$ 281,600.00	
PAVEMENT, PCC	8920	SY	\$	78.75	\$ 702,450.00	
PAVED SHOULDER, HMA	3440	SY	\$	60.00	\$ 206,400.00	
PAVEMENT MARKINGS	1	LS	\$	13,500.00	\$ 13,500.00	
SIGNAGE	1	LS	\$ 1	130,000.00	\$ 130,000.00	Includes 2 trusses for US 20 approaches
SURFACE RESTORATION	1	LS	\$	13,500.00	\$ 13,500.00	
 EROSION CONTROL & SWPPP	1	LS	\$	13,500.00	\$ 13,500.00	
TRAFFIC CONTROL (5%)	1	LS	\$	86,057.50	\$ 86,057.50	
MOBILIZATION (5%)	1	LS	\$	86,057.50	\$ 86,057.50	

1,906,765 Subtotal: \$

Other Project Costs

ENGINEERING (15%) \$ 286,015 CONTINGENCY (30%) \$ 572,030 TOTAL PROJECT COST: \$ 2,764,810

 $V: \label{thm:costOpinion-Exhibit} $$V:\Pr\ ostOpinion-Exhibit_ 2025-02-26_US59-US20-Holstein_Intersection-Alternatives.xlsx $$V:Pointersection-Alternatives.xlsx $$V:Pointe$

3/20/2025 Page 4 of 4

DESIGN TEAM SCHROCK/TAMRAKAR IDA COUNTY PROJECT NUMBER HSIPX-020-2(157)--3L-47 SHEET NUMBER A.17 FILE NO. --5:03:40 PM 8/16/2025


Life Cycle Cost Evaluation Tool

	Outputs								
	nis sheet compiles the data from summary tables in individual alternatives sheets. To populate the output sheet press the "Setup forksheets" button in the Alternatives_Mastertist tab.								
Agency: Iowa Department of Transportation									
Project Name: US 59 & US 20 Intersections Study									
Project Reference:	=IF(NOT(ISBLANK('Organization Information'!B7)),'Organization Information'!B7,"")								
Intersection:	ntersection: US 59 & US 20 East Junction								
City:	Holstein								
State:	Iowa								
Performing Department or Organization:	Snyder & Associates								
Date:	3/18/2025								
Analyst:	BMG								
Analysis Type	At-Grade Intersection								

	Analys	is S	Summary				
			Net Present \	/alu	e of Costs		
Cost Categories	Minor Road Stop		Traffic Signal		Roundabout	Un	signalized Restricted
	millor Roda Stop		Transcoignar		Roundabout	Cro	ossing U-Turn (RCUT)
Planning, Construction & Right of Way Costs	\$ -	\$	217,500	\$	2,764,810	\$	660,585
Post-Opening Costs	\$ 14,590	\$	127,409	\$	58,361	\$	29,181
Auto Passenger Delay	\$ 269,304	\$	1,633,690	\$	935,991	\$	699,096
Truck Delay	\$ 272,792	\$	1,654,849	\$	948,113	\$	708,150
Safety	\$ 1,071,279	\$	1,901,593	\$	207,962	\$	509,309
Total cost	 \$1,627,965		\$5,535,040		\$4,915,238		\$2,606,320

To exclude cost categories from the comparison clear all values in the row.

Select Base Case for Benefit-Cost Comparison: (Choose from list)	Minor F	Road Stop)	Note: The "Benefit-Cost Ratio" is only applicable for im						
	Net Present Value of Benefits Relative to Base Case									
Benefit Categories	Minor Road Stop	Tra	ffic Signal	R	oundabout	Unsignalized Restricted Crossing U-Turn (RCUT)				
Auto Passenger Delay		\$	(1,364,386)	\$	(666,687)	\$	(429,792			
Truck Delay		\$	(1,382,057)	\$	(675,322)	\$	(435,358			
Safety		\$	(830,314)	\$	863,317	\$	561,971			
Net Present Value of Benefits		\$	(3,576,757)	\$	(478,692)	\$	(303,180			
Net Present Value of Costs		\$	330,319	\$	2,808,581	\$	675,175			
Benefit-Cost (B/C) Ratio		Benefits ar	ategy not preferred. e less than base case reater than base case.	Benefits a	trategy not preferred. are less than base case greater than base case.	Benefits are	tegy not preferred. less than base case eater than base case			
Delay B/C		Benefits ar	ategy not preferred. e less than base case reater than base case.	Benefits a	trategy not preferred. are less than base case greater than base case.	Benefits are	tegy not preferred. less than base case eater than base case			
Safety B/C		Benefits ar	ategy not preferred. e less than base case reater than base case.		0.31		0.83			



				NTERS		TEVAL			E (ICE)	PROC		JOE 31	AGE 2				
<u> </u>	US 20 & US 59 V						Review N	-									
	US 20 at US 59 /	S Main St	/ Indorf Ave				Review N Attendee										
	Holstein, IA						Allendee	s (List).									
Analyst:	TDC			Date:	2/14/2024												
									UITY SU								
tudy area travel modes	Vehicles, Trucks, pos	ssibly oversiz	e/overweight. No	pedestrians	/bicycles/tra	ınsit			Studies (were ident			ieet):					
esent and/or likely:									ces betwee			rison areas					
avel needs for	Access to Holstein to	the north, a	ccess to the hote	and conven	ience store	on the south	Percentage	e of Latino i	s similar be	tween the f	ocus area a	and the com	parison are	a.			
ansporation mode(s):									percentage i								
	US 20 has been a 4-l	lane express	way near this into	ersection and	d recently ex	tended to th	Focus area	a has a high	ner percenta	ge in the u	nder 0.50 po	overty statu	s than the c	comparison area.		antia 75 au	aldan
istory of neighborhood & ad development:	So Zo nao Boon a 11	ано охргоос	may nour tino int	3100001011 0110	a rooonay ox	acondod to a	The focus	area nas a l area has a l	nigner perce much lower	entage of tr percentage	e populatio	n that is un olds with no	der 10 years vehicle tha	s of age, but a lo an the compariso	wer percentage tr n area	nat is 75 or	older.
ad development.								area nas a i	maon lower	percentage	or modeon	oldo with the	Vernole tria	in the companie	ii aica.		
urrounding land uses /	Southwest - Hotel, A	griculture, Sc	outheast - Comm	ercial/Manufa	acturing, Noi	rthwest - Ag											
adside development:																	
							8. SEI	LECTION	N CRITE	RIA							
		Meets		Avera	ge Vehicle	Delay	Wors	st Vehicle [Delay	20-Flag	Results	Predictiv	ve Safety		Life Cycle	Costs	
itersection Form		Equity Goals?	Stakeholder Support	AM Peak	PM Peak	Mid Day	AM Peak	PM Peak	Mid Day	Ped	Bike	PDO	Fatal/Inj	Construction Cost	Costs	B/C	Environmental Feasibi
ultilane Roundabout		Yes	Strong	5	5	_	6	6	_	31%	30%	0.66	0.16	\$3,356,401	\$3,400,172	1.88	No perceived impact
CUT / J-Turn (stop co		Yes	Negative	4	5		42	42	_	39%	36%	1.02	0.50	\$1,430,317	\$1,444,907	1.82	No perceived impact
raffic Signal		Yes	Unknown	10	8		10	10	_	41%	48%	5.14	3.88	\$290,000	\$402,819	0.00	No perceived impact
.a		103	• • • • • • • • • • • • • • • • • • •	10				10		4170	4070	0.1-4	0.00	4200,000	4402,010	0.00	nto porocitou impuot
					9. RE	VIEW MI	EETING	NOTES	AND RE	СОММЕ	NDATIC	ONS					
ecommended Inter	section Concep	t:	<select r<="" td=""><td>ecomme</td><td>nded Al</td><td>ternative</td><td>g></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></select>	ecomme	nded Al	ternative	g>										
otes from review tea		••															
	ŭ																

PROJECT NUMBER HSIPX-020-2(157)--3L-47

IDA COUNTY

Existing		AM Peal	ζ		PM Peak	ζ		
Intersection	Control Type	Approach / Movement	Delay / Vehicle (s)	LOS	95th % Queue (ft)	Delay / Vehicle (s)	Los	95th % Queue (ft)
	•	Eastbound	10	В	64	10	A	41
		Westbound	10	A	40	8	A	35
	Signal	Northbound	9	A	37	7	A	23
		Southbound	7	A	31	6	A	47
		Overall	10	A	-	8	A	-
		Eastbound Left	9	A	-	9	A	-
		Westbound Left	9	A	-	9	A	-
		Northbound Left	42	D	-	41	D	-
		Northbound Thru	42	D	-	41	D	-
	RCUT	Northbound Right	10	A	-	10	A	-
		Southbound Left	41	D	-	42	D	_
US 20 & US 59		Southbound Thru	41	D	-	42	D	_
(West Jct)		Southbound Right	10	A	_	10	A	_
		Eastbound	5	A	22	5	A	16
		Westbound	6	A	22	5	A	19
	RAB	Northbound	6	A	15	5	A	6
	ICID .	Southbound	5	A	12	6	A	26
		Overall	6	A	-	5	A	-
		Eastbound	5	A	22	5	A	16
	RAB	Westbound	4	A	15	3	A	9
	(WB RT	Northbound	6	A	15	5	A	6
	Bypass Lane)	Southbound	5	A	12	6	A	26
	,	Overall	5	A	-	5	A	-
	Stop Control	Northbound	11	В	6	12	В	10
	(NB)	Westbound Left	8	A	0	8	A	0
		Eastbound	4	A	20	4	A	24
		Westbound	17	B	42	16	В	40
	Signal	Northbound	12	В	38	12	В	42
		Overall	10	В	-	10	A	_
US 20 & US 59		Westbound Left	8	A	-	9	A	_
(East Jct)	RCUT	Northbound Left	34	С	-	34	C	-
		Northbound Right	10	A	-	10	A	_
		Eastbound	4	A	15	5	A	19
		Westbound	5	A	13	5	A	13
	RAB	Northbound	5	A	6	5	A	9
		Overall	5	A	-	5	A	-

Opening Y	ear (2027) Ana	alysis Results		AM Peal	ζ.		PM Peal	Ĭ.
Intersection	Control Type	Approach / Movement	Delay / Vehicle (s)	Los	95th % Queue (ft)	Delay / Vehicle (s)	Los	95th % Oueue (ft)
	- / F -	Eastbound	11	В	70	10	A	43
		Westbound	11	В	43	8	A	37
	Signal	Northbound	9	A	39	7	A	24
	Ü	Southbound	8	A	33	7	A	49
		Overall	10	В	-	8	A	-
		Eastbound Left	9	A	-	9	A	-
		Westbound Left	9	A	-	9	A	-
		Northbound Left	42	D	-	41	D	-
		Northbound Thru	42	D	-	41	D	-
	RCUT	Northbound Right	10	A	-	10	A	-
		Southbound Left	42	D	-	42	D	-
US 20 & US 59		Southbound Thru	42	D	-	42	D	_
(West Jct)		Southbound Right	10	A	-	11	В	-
l		Eastbound	6	A	25	5	A	19
	RAB	Westbound	6	A	25	5	A	19
		Northbound	7	A	15	6	A	6
		Southbound	6	A	15	6	A	29
		Overall	6	A	-	6	A	-
		Eastbound	6	A	25	5	A	19
	RAB	Westbound	4	A	15	3	A	12
	(WB RT	Northbound	7	A	15	6	A	6
	Bypass Lane)	Southbound	6	A	15	6	A	29
		Overall	5	A	-	5	A	-
	Stop Control	Northbound	12	В	8	13	В	10
	(NB)	Westbound Left	8	A	0	8	A	0
		Eastbound	4	A	22	4	A	25
	Signal	Westbound	16	В	47	17	В	43
	Signai	Northbound	12	В	39	13	В	47
US 20 & US 59		Overall	10	В	-	10	A	-
(East Jct)		Westbound Left	8	A	-	9	A	-
(East Jet)	RCUT	Northbound Left	34	С	-	34	С	-
		Northbound Right	10	A	-	10	A	-
		Eastbound	5	A	15	5	A	19
	RAB	Westbound	5	A	16	5	A	13
	KAB	Northbound	5	A	9	5	A	9
		Overall	5	A	-	5	A	-

5:03:44 PM 8/16/2025


Type	Design Ye	ar (2047) Ana	lysis Results	4	AM Peal	ζ		PM Peak	
Type Movement Vehicle (s) Queue (it) Queue (i	T / /:	Control	Approach /	Delay /	LOC	95th %	Delay /	LOC	95th %
Signal Westbound 12	Intersection	Type	Movement	Vehicle (s)	LUS	Queue (ft)	Vehicle (s)	LUS	Queue (ft)
Signal Northbound 13			Eastbound	16	В	114	11	В	65
Southbound 10								В	
Coverall 14		Signal			В			A	
RCUT Westbound Left 9				10	A	44	8	A	70
RCUT			Overall	14	В	-	10	A	-
Northbound Left			Eastbound Left		A	-		A	-
Northbound Thru			Westbound Left	9	A	-	9	A	-
Northbound Right 11			Northbound Left	43	D	-	42	D	-
Northbound Right 11		DOLLE	Northbound Thru	43	D	-	42	D	-
Southbound Thru		RCUI	Northbound Right	11	В	-	11	A	-
Company	**** **		Southbound Left	43	D	-	44	D	-
Eastbound T			Southbound Thru	43	D	-	44	D	-
RAB	(West Jct)		Southbound Right	11	В	-	12	В	-
RAB			Eastbound	7	A	37	6	A	28
Southbound 7		RAB	Westbound	7	A	37	6	A	28
Overall 7			Northbound	9	A	28	7	A	12
RAB (Westbound 7			Southbound	7	A	23	9	A	49
RAB			Overall	7	A	-	7	A	-
Company Comp				7	A	37	6		28
Bypass Lane Southbound 7		RAB	Westbound	5	A	25	3	A	15
Stop Control (NB) Northbound 14		(WB RT	Northbound	9	A	28	7	A	12
Stop Control (NB)		Bypass Lane)	Southbound	7	A	23	9	A	49
Company Comp			Overall	6	A	-	6	A	-
Eastbound		Stop Control	Northbound	14	В	12	16	С	20
Signal Westbound 31 C 103 30 C 95 Northbound 15 B 48 17 B 58 Overall 17 B - 15 B - (East Jct) RCUT R		(NB)	Westbound Left	8	A	0	9	A	0
Signal Northbound 15 B 48 17 B 58			Eastbound	4	A	31	4	A	37
US 20 & US 59 (East Jct) RCUT RCUT RCUT RCUT RCUT RCUT RCUT Northbound Left So C Northbound Right 10 B - 10 B - 9 A - 9 A - 9 A - 10 B - 10 B		Siana1	Westbound	31	С	103	30	С	95
RCUT		Signai	Northbound	15	В	48	17	В	58
(East Jct) Westbound Left Northbound Left Northbound Left Northbound Right 9 A - 9 A - Northbound Left Northbound Right Northbound S 35 C - 35 C - RAB Eastbound S A 22 5 A 28 Westbound S A 22 5 A 19 Northbound S A 12 6 A 14	TIC 20 P. TIC 50		Overall	17	В	-	15	В	-
RCUI Northbound Lett 35 C - 35 C - Northbound Right 10 B - 10 B - Eastbound 5 A 22 5 A 28 Westbound 5 A 22 5 A 19 Northbound 5 A 12 6 A 14			Westbound Left	9	A	-	9	A	-
RAB Eastbound 5 A 22 5 A 28 Westbound 5 A 22 5 A 19 Northbound 5 A 12 6 A 14	(East Jet)	RCUT	Northbound Left	35	С	-	35	С	-
RAB Westbound 5 A 22 5 A 19 Northbound 5 A 12 6 A 14			Northbound Right	10	В	-	10	В	-
RAB Northbound 5 A 12 6 A 14			Eastbound	5	A	22	5	A	28
Northbound 5 A 12 6 A 14		DAD	Westbound	5	A	22	5	A	19
Overall 5 A - 5 A -		KAD	Northbound	5	A	12	6	A	14
			Overall	5	A	-	5	A	-

NCHRP 17-98 Equity Assessment Worksheet - Stage 2

Instructions

This worksheet is intended to record the results from the Stage 1 and Stage 2 Equity assessment, developed through project NCHRP 17-98: Guide for Intersection Control Evaluation. All fields are designed as either open-ended answer fields to document Stage 1 assessment questions or as tables to record the more detailed demographic assessment completed in Stage 2. For further detailes, the user is encouraged to consult the final project report and the example problem contained there. An agency is open to customize this worksheet to fit its specific equity assessment process.


Overview							
Project Name	US 20 & US 59 W Jct	Organization	Iowa DOT / Snyder & Associates, Inc.				
Major Roadway	US 20	Analyst	Tim Crouch				
Minor Rowadway	US 59 / Main St	Data Completed	2/20/2025				
Analysis Year	2019-2023	Link to Location					



jacker1

5:03:54 PM

8/16/2025




Design Flag Assessment NCHRP 7-25 Method


Results Summary


Intersection:

US 20 & US 59 West Junction

		Scenario 1	Scenario 2	Scenario 3
		Roundabout	RCUT	Traffic Signals
	Percent Yellow Flags	21%	27%	29%
Pedestrian	Percent Red Flags	10%	12%	12%
	Percent Not Flagged	69%	62%	60%
	Percent Yellow Flags	24%	18%	24%
Bicycle	Percent Red Flags	6%	18%	24%
	Percent Not Flagged	71%	65%	53%
	Percent Yellow Flags	22%	23%	27%
All	Percent Red Flags	8%	14%	16%
	Percent Not Flagged	70%	63%	57%







	Safe	ety Performan	ce for Intersection	າ Control Evaluation To	pol				
Results									
Summary of crash prediction results for each alternative									
			Project Informati	on					
Project Name:	US 20 & US 59 Inters	ections Study		Intersection Type	At-Grade Intersections				
Intersection:	US 20 & S Main St (U	S 59) - West Junction		Opening Year	2027				
Agency:	Snyder & Associates			Design Year	2047				
Project Reference:	S&A Project # - 123.1	.784.01B		Facility Type	On Rural Multilane Highway				
City:	Holstein			Number of Legs	4-leg				
State:	lowa								
Date:	February 26th, 2025								
Analyst:	BMG								
			Crash Prediction Sun	nmary					
Control Strategy	Crash Type	Opening Year	Design Year	Total Project Life Cycle	AADT Within Prediction Range?				
1-lane Roundabout	Total	0.62	0.82	15.15	N/A				
1-latte Routidabout	Fatal & Injury	0.12	0.16	3.01	IN/A				
2-lane Roundabout	Total	0.62	0.82	15.15	N/A				
2-latte Routidabout	Fatal & Injury	0.12	0.16	3.01	IN/A				
Minor Bood Ston	Total	1.78	2.34	43.28	Yes				
Minor Road Stop	Fatal & Injury	0.82	1.10	20.08	res				
Traffic Signal	Total	7.18	9.02	170.17	Yes				
Traffic Signal	Fatal & Injury	3.19	3.88	74.34	165				
Unsignalized RCUT	Total	1.16	1.52	28.13	N/A				
Ondigitalized Red I	Fatal & Injury	0.38	0.50	9.24	14/1				



ENGINEER'S PRELIMINARY OPINION OF PROBABLE PROJECT COST

UPDATED 03/20/25

US 20 & US 59 WEST JUNCTION - RCUT **HOLSTEIN, IOWA**

DESCRIPTION	W Jct RCUT QUANTITY	UNIT	U	NIT PRICE	W Jct RCUT COST	COMMENTS
EXCAVATION, CLASS 10 ROADWAY AND BORROW	4950	CY	\$	12.00	\$ 59,400.00	
GRANULAR SUBBASE	5565	SY	\$	12.00	\$ 66,780.00	
SUBGRADE PREP	5565	SY	\$	5.00	\$ 27,825.00	
TOPSOIL, STRIP SALVAGE AND SPREAD	4950	CY	\$	12.60	\$ 62,370.00	
SUBDRAIN	4000	LF	\$	12.00	\$ 48,000.00	
GRANULAR SHOULDER REMOVAL	1800	SY	\$	20.00	\$ 36,000.00	
PAVEMENT, PCC	5300	SY	\$	78.75	\$ 417,375.00	
GRANULAR SHOULDER	1800	SY	\$	20.00	\$ 36,000.00	
PAVED MEDIAN, PCC	1100	SY	\$	80.00	\$ 88,000.00	
PAVEMENT MARKINGS	1	LS	\$	20,000.00	\$ 20,000.00	
SIGNAGE	1	LS	\$	10,000.00	\$ 10,000.00	
SURFACE RESTORATION	1	LS	\$	15,000.00	\$ 15,000.00	
EROSION CONTROL & SWPPP	1	LS	\$	10,000.00	\$ 10,000.00	
TRAFFIC CONTROL (5%)	1	LS	\$	44,837.50	\$ 44,837.50	
MOBILIZATION (5%)	1	LS	\$	44,837.50	\$ 44,837.50	

Subtotal: \$ 986,425

Other Project Costs

ENGINEERING (15%) \$ 147,964 CONTINGENCY (30%) \$ 295,928 TOTAL PROJECT COST: \$ 1,430,317

 $V: \label{eq:v:projects} \ 2023 \ 123.1784.01 B \ Design \ Traffic \ Cost Opinion-Exhibit_2025-02-26_US59-US20-Holstein_Intersection-Alternatives.x lsx$

3/20/2025 Page 1 of 4

DESIGN TEAM SCHROCK/TAMRAKAR IDA COUNTY PROJECT NUMBER HSIPX-020-2(157)--3L-47 SHEET NUMBER A.25 FILE NO. ==



ENGINEER'S PRELIMINARY OPINION OF PROBABLE PROJECT COST

UPDATED 03/20/25

US 20 & US 59 WEST JUNCTION - ROUNDABOUT HOLSTEIN, IOWA

DESCRIPTION	W Jct RAB QUANTITY	UNIT	U	NIT PRICE	w	Jct RAB COST	COMMENTS
EXCAVATION, CLASS 10 ROADWAY AND BORROW	10000	CY	\$	12.00	\$	120,000.00	
GRANULAR SUBBASE	11445	SY	\$	12.00	\$	137,340.00	
SUBGRADE PREP	11445	SY	\$	5.00	\$	57,225.00	
SPECIAL BACKFILL	1000	CY	\$	36.75	\$	36,750.00	
TOPSOIL, STRIP SALVAGE AND SPREAD	5000	CY	\$	12.60	\$	63,000.00	
SUBDRAIN	4000	LF	\$	12.00	\$	48,000.00	
PAVEMENT REMOVAL	8800	SY	\$	40.00	\$	352,000.00	
PAVEMENT, PCC	10900	SY	\$	78.75	\$	858,375.00	
PAVED SHOULDER, HMA	4300	SY	\$	60.00	\$	258,000.00	
PAVEMENT MARKINGS	1	LS	\$	15,000.00	\$	15,000.00	
SIGNAGE	1	LS	\$	130,000.00	\$	130,000.00	Includes 2 trusses for US 20 approaches
SURFACE RESTORATION	1	LS	\$	15,000.00	\$	15,000.00	
EROSION CONTROL & SWPPP	1	LS	\$	15,000.00	\$	15,000.00	
TRAFFIC CONTROL (5%)	1	LS	\$	104,534.50	\$	104,534.50	
MOBILIZATION (5%)	1	LS	\$	104,534.50	\$	104,534.50	

2,314,759 Subtotal: \$

Other Project Costs

ENGINEERING (15%) \$ 347,214 CONTINGENCY (30%) \$ 694,428 TOTAL PROJECT COST: \$ 3,356,401

 $V: \label{lem:v:projects} \ 2023 \ 123.1784.01 B \ Design \ Traffic \ Cost Opinion-Exhibit_2025-02-26_US59-US20-Holstein_Intersection-Alternatives.x lsx$

3/20/2025 Page 2 of 4

SHEET NUMBER A.26


DESIGN TEAM SCHROCK/TAMRAKAR IDA COUNTY PROJECT NUMBER HSIPX-020-2(157)--3L-47 FILE NO. - $pw: \NTPwint1.dot.int.lan: PWMain\Documents\Projects\A702001024\Design\CADD_Files\Sheet_Files\SHT_47020157Z04_A21.dgn$

Life Cycle Cost Evaluation Tool

Outputs						
This sheet compiles the data from summary tables in individual alternatives sheets. To populate the output sheet press the "Setup Worksheets" button in the Alternatives_MasterList tab.						
Agency: lowa Department of Transportation						
Project Name: US 59 & US 20 Intersections Study						
Project Reference:	-IF(NOT(ISBLANK('Organization Information'!B7)),'Organization Information'!B7,"")					
Intersection:	US 59 & US 20 West Junction					
City:	Holstein					
State:	lowa					
Performing Department or Organization:	Snyder & Associates					
Date:	3/18/2025					
Analyst:	BMG					
Analysis Type	At-Grade Intersection					

Analysis Summary									
				Net Present \	/alu	e of Costs			
Cost Categories		Minor Road Stop		Traffic Signal		Roundabout		Unsignalized Restricted Crossing U-Turn (RCUT)	
Planning, Construction & Right of Way Costs	\$		\$	290,000	\$	3,356,401	\$	1,430,317	
Post-Opening Costs	\$	14,590	\$	127,409	\$	58,361	\$	29,181	
Auto Passenger Delay	\$	1,594,891	\$	2,032,877	\$	1,478,606	\$	2,212,158	
Truck Delay	\$	1,615,548	\$	2,059,206	\$	1,497,756	\$	2,240,809	
Safety	\$	7,312,916	\$	27,321,205	\$	1,156,559	\$	3,443,356	
Total cost	Г	\$10,537,945		\$31,830,696		\$7,547,683		\$9,355,821	

Select Base Case for Benefit-Cost Comparison: (Choose from list)	Minor F	Road Stop	Not	Note: The "Benefit-Cost Ratio" is only applicable for in							
	Net Present Value of Benefits Relative to Base Case										
Benefit Categories	Minor Road Stop	Traffic Signal		Roundabout	Unsignalized Restricted Crossing U-Turn (RCUT)						
Auto Passenger Delay		\$ (437,985) \$	116,286	\$ (617	,267)					
Truck Delay		\$ (443,658)) \$	117,792	\$ (625	,261)					
Safety		\$ (20,008,289)) \$	6,156,356	\$ 3,869	,559					
Net Present Value of Benefits		\$ (20,889,932) \$	6,390,434	\$ 2,62	7,032					
Net Present Value of Costs		\$ 402,819	\$	3,400,172	\$ 1,444	1,907					
Benefit-Cost (B/C) Ratio		Control Strategy not preferred. Benefits are less than base case and cost is greater than base case	1.88		1.82						
Delay B/C		Control Strategy not preferred. Benefits are less than base case 0.07 and cost is greater than base case.		Control Strategy not preferred. Benefits are less than base case and cost is greater than base case.							
Safety B/C		Control Strategy not preferred. Benefits are less than base case and cost is greater than base case.		1.81	2.68						



Questions:

PROJECT NUMBER HSIPX-020-2(157)--3L-47

IDA COUNTY


SHEET NUMBER A.28


What size of wind blades make these turns?


Do the wind blade turn paths need paved or is granular acceptable?


The current turn lanes have granular shoulders. Should the new ones have granular or paved?


What is the preferred type of transition on US 59 at the west junction to connect to the 4-lane?











SURVEY SYMBOLS

T, Above Ground Storage Tank , Billboard B, Bottom of Bridge Beam	00
L, Bridge Centerline , Bridge Deck —	×
N, Grain Bin — , Topo Breakline —	
D, Building or Foundation	Δ
S, Bridge Low Steel 1, Bench Mark	□ RRB
K, Stream Bank	X
G, Bridge Centerline BL of Road -ML or SR	
V, Cave	*
L, Cell Phone Tower 5, Cistern	C RT
N, Concrete or A/C Slab	Ō
, Control Point P, Corporation Line	O A
, Curve Point	<u> </u>
, Back of Curb —	
L, Culvert Centerline Draw or Stream -Down —	
B, Drainage Area Boundary	(58)
K, Centerline of Dike or Dam M, Photogrammetry Elv Control Check	□ SIGN ⊚ SL
l, Centerline Draw or Stream -Up	—
, Electrical Box	<u>s</u>
, Edge of Gravel Road P, Edge Paved Entrance and Park Lot —	99
T, Centerline BL of Entrance	I
U, Edge Unpaved Entrance and Parking	A
, Edge of Paved Roads -ML or SR — /, Edge of Water —	
L, Chain Link and Security Fence	TA
NO, FENO Monument D. Fire Hydrants	□ TB
D, Fire Hydrants G, Flag Poles	0
, Filler Pipe /, Wire Fence	
/D, Wood Fence	*
C, Guard Rail Cable	€
L, Guard Rail Steel , Guard Post -Less Than 4 Posts —	-
R, Guard Post -4 or More Posts —	
, Ground Shot V, Grave	
, Gutter In Front of Curb , Gas Valve	-
r, Gas Valve OG, Hedge Row	$\stackrel{\bullet}{\Rightarrow}$
, Hydric Soil -Wetlands	ŏ
, Electrical Highline Tower Storm Sewer Intake	
B, Storm Sewer Beehive Intake	□ TSB
, Lot Corner	*
l, Miscellaneous Line , L.P. Tank	* Q
M Luminairo	O TV
i, Utility Access -Manhole S. Miscellaneous	
4, MIIE MARKER POST	0
IT, Tile Outlet	*
P, Photo Control Point	U8
T, Photo Control Target	<u>_</u>
l angent Point	D X
, Location of Photo -Wetlands	• WH
G, Location of General Photo	⊚ WHU
ST, Spiral Point	>-
I, Utility Access -Manhole S, Miscellaneous 1, Mile Marker Post IT, Tile Outlet P, Photo Control Point T, Photo Control Target Tangent Point P, Pipe Culvert L, Location of Photo -Wetlands G, Location of General Photo C, Curve Point	

PR, Electic Riser Pole PRO, Profile Shot PT, Curve Point REF, Reference Tie Point RIP, Rip-Rap ROC, Rock Outcropping ROW, Right of Way Mark RR, Centerline of Railroad Tracks RRB, Railroad Signal Box RRF, Railroad Frog RRR, Railroad Rail RRS, Railroad Signal RRW, Railroad Switch RT, Radio Tower S. Soil Sampling Site -Wetlands SBR, Size of Bridge SC, Spiral Point SCR, Section Corner SEP, Septic Tank SF, Septic Tank
SF, Silt Fence -Wetlands
SG, Staff Gauge -Wetlands
SH, Paved Shoulder
SHR, Shrub SI, Sign SL, Speed Limit Sign SLN, Section Line SLO, Silo SNK, Sink Hole SNP, Unpaved Shoulder SP, Stream Profile STP, Stump SWK, Sidewalk SWP. Swamp or Marsh SWP, Swamp or Marsn
TA, Tower Anchor
TBO, Telephone Booth
TCB, Traffic Signal Box
TDC, Tree Deciduous
TDL, Trafic Detection Loop TER, Terrace TEV, Evergeen Tree TFR, Tree Fruit TGP, Telegraph Pole TGP, Telegraph Pole
TIL, Tile Line
TLNL, Tree Line Left
TLNR, Tree Line Right
TOP, Top of Bridge Pier
TPA, Telephone Pole Co. 1
TPB, Telephone Pole Co. 3
TR, Telephone Pole Co. 3
TR, Telephone Riser Pole
TRL, Trail
TS, Spiral Point
TSB, Telephone Switch Box
TSG, Traffic Signal
TSL, Traffic Signal and Luminare
TV, Satelite TV Dish
TVP, TV Pedestal TVP, TV Pedestal TW, Top of Water UB, Utility Box
UE, Utility Box
UE, Utility Elevation
UPH, Utility Pot Hole - Quality A
UST, Underground Tank
UV, Underground Utility Vault VS, Channel Cross Section WC, Wild Card -Misc. Field Shot WEL, Well WHD, Water Hydrant WHU, RV Water Hook Up WM, Wind Mill WND, Wind Turbine

UTILITY LEGEND

Sub-Surface Utility Mapping Quality Level is in accordance with CI/ASCE 38-02 Standard Guidelines for the Collection and Depiction of Existing Subsurface

Remark Abbreviations

QLA Quality Level A Highest guideline quality level QLD Quality Level D Lowest guideline quality level

> North West Rural Electric Cooperative Electric Distribution North West Rural Electric Cooperative Electric Transmission

LINEWORK

Doug Alons, Operations Director 1505 Albany Place S.E. Box 435 Orange City, IA, 51041 ph: 7127074935 dalons@nwrec.coop

PPA, Northwest REC EL1D, Northwest REC - Quality D

HOLSTEIN, City of Sanitary Sewer HOLSTEIN, City of Water Ken Neiemeier, Public Works Director 119 S Main Holstein, IA, 51025-0500 (712) 368 4898 holsteinpw@netllc.net

WL1D, City of Holstien - Quality D — SAN. — SA1D, City of Holstien - Quality D

> Long Lines Ltd. Fiber Distribution Long Lines Ltd. Telephone Tom Connors, Construction/Design Manager PO Box 128 Jefferson, SD, 57038 ph: 7123331352 cell: 7123331352 tom.connors@longlines.biz

FO1D, Long Lines - Quality D

Frontier Communications Fiber Distribution Frontier Communications Telephone
Charles Salen, OSP Engineer 334 1st Ave SW Le Mars, IA 51031 ph: 712-541-1941 cell: 712-541-1941 charles_salen@ftr.com

FO2D, Frontier Comm - Quality D

Windstream Communications Fiber Distribution Windstream Communications Telephone
Windstream Communications Fiber Transmission Dan Hogan, Engineering Manager - IA 1614 230th St Manchester, IA, 52057 ph: 5639202428 cell: 5639202428 Dan.Hogan@windstream.com

FO3D, Windstream Comm - Quality D

Aureon Network Services Fiber Distribution Aureon Network Services Fiber Transmission
Jeff Klocko, OSP Engineer
7760 Office Plaza Drive South West Des Moines, IA,

ph: 5158300445 jeff.klocko@aureon.com

FO5D, Aureon - Quality D

— F03 —

Lumen Centurylink Fiber Distribution Lumen Centurylink Telephone
Steve Parker, Manager of Engineering & Construction
2103 E. University Ave. Des Moines, IA, 50317 ph: 5152650968 cell: 5073581978 . Steven.Parker4@lumen.com

— F06 — FO6D, Centurylink - Quality D

FO4D. Mcleod - Quality D

TL1D, Schaller Telephone COOP - Quality D EL2D, Iowa DOT - Quality D

ST1D. Iowa DOT - Quality D GL1D, Midamerican Energy - Quality D


> Adesta Flber Transmission Cecil Kuhse, Program Manager 565 Willowbrook Centre Parkway Willowbrook , IL, 60527 ph: 630-739-0546 cell: 732-675-2268 cecil.kuhse@aus.com

PLAN VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS Design Color No

LINEWORK	Design Co	IOT NO.							
Green	(2)	Existing Topographic Features and Labels							
Blue	(1)	Proposed Alignment, Stationing, Tic Marks, and Alignment Annotation							
Magenta	(5)	Existing Utilities	xisting Utilities						
SHADING	Design Col	or No.	Transparency						
Pink, Dark	(13)	Temporary Pavement Shading	50%						
Yellow	(4)	Proposed Pavement Shading	50%						
Orange	(6)	Proposed Granular Shading	50%						
Orange	(70)	Proposed Shoulder Granular Shading	50%						
Yellow	(68)	Proposed Shoulder Paved Full Depth Shading	50%						
Yellow	(132)	Proposed Shoulder Paved Partial Depth Shading	50%						
Brown, Light	(236)	Grading Shading	50%						
Orange, Light	(134)	Proposed Granular Entrance Shading	50%						
Yellow	(220)	Proposed Paved Entrance Shading	50%						
Tan	(8)	Proposed Sidewalk Shading	50%						
Blue, Light	(230)	Proposed Sidewalk Landing Shading	50%						
Pink	(11)	Proposed Sidewalk Ramp Shading	50%						
Red	(3)	Proposed Structure Shading	50%						
Red	(3)	Delineates Restricted Areas	0%						

PROFILE VIEW COLOR LEGEND OF PLAN AND PROFILE SHEETS

LINEWORK	Design Color No.
Green	(10) Existing Ground Line Profile
Blue	(1) Proposed Profile and Annotation
Magenta	(5) Existing Utilities
Blue, Light	(230) Proposed Ditch Grades, Left
Black	(0) Proposed Ditch Grades, Median
Rust	(14) Proposed Ditch Grades, Right





PLAN AND PROFILE LEGEND AND SYMBOL INFORMATION SHEET

(COVERS SHEET SERIES D, E, F, & K)

FILE NO. --**ENGLISH**

4:41:35 PM


DESIGN TEAM SCHROCK/TAMRAKAR


IDA COUNTY


PROJECT NUMBER HSIPX-020-2(157)--3L-47


SHEET NUMBER D.1

WV, Water Valve









Survey Information

SURVEY INDEX

County: Ida PIN: 24-47-020-010

Project Number: HSIPX-020-2(157)--3L-47 Location: W of W Jct US 59 to E of E Jct US 59

> Type of Work: Undecided **Project Directory: 4702001024**

Survey Personnel

Clayton Henningsen – Survey Party Chief Jason Arn - Survey Party Chief

Date(s) of Survey

04/14/2024 Begin Date End Date 08/03/2024

General Information

This survey is for US Hwy 20 west of the west junction US 59 to east of the east junction US 59. This survey request was for the US Hwy 20 corridor only. This project is a Full Field DTM survey.

Utility Information

For logging data and other utility details see Utility Survey and Ownership Report in the Utility folder of the PrelimSurvey project directory.

Project Control

Coordinates were determined for primary project control points by conducting concurrent six-hour static observations. Post processing is constrained to nearby lowa Real Time Network reference stations. For additional details of the control survey, contact the Preliminary Survey department.

PROJECT DATUM: NAD83(2011) for EPOCH 2010.00 (IaRTN 2019 ADJUSTMENT) **COORDINATE SYSTEM: IOWA REGIONAL COORDINATE SYSTEM ZONE 04**

(U.S. SURVEY FOOT) **VERTICAL DATUM: NAVD88 GEOID MODEL: 2018u2**

Alignment Information

The horizontal alignment for U.S. Hwy 20 this survey was provided by the district 3 survey office.

PROJECT NUMBER HSIPX-020-2(157)--3L-47

CONTROL POINT VICINITY MAP

This map is a guide to the vicinity of the primary project control points. Primary control is for use with RTK base stations and for RTN validation. Future surveys will use primary project control to establish temporary control as needed for construction or other surveying applications.



HORIZ. DATUM: NAD83(2011) for EPOCH 2010.00 (IaRTN 2019 Adjustment) - Iowa RCS Zone 04 (U.S. Survey Foot)

VERT. DATUM: NAVD88 - Geoid Model: 2018u2

PROJECT NUMBER HSIPX-020-2(157)--3L-47

SHEET NUMBER 6.2

Coordinate listing from next sheet will be used with IaRTN for monument recovery. No other reference ties are given.

HORIZONTAL AND VERTICAL PROJECT CONTROL COORDINATE LISTING

HORIZ. DATUM: NAD83(2011) for EPOCH 2010.00 (IaRTN 2019 Adjustment) la. Regional Coordinate System Zone 04 (U.S. Survey Foot)

VEDT DATIM: NAVD88

VERT. DATUM: NAVD88 Geoid Model: 2018u2

Point Name	<u>Northing</u>	<u>Easting</u>	<u>Elevation</u>	Feature Definition-Description
47020046	8579594.33	14311126.32	1414.34	CP SET FENO MONUMENT ON TOP OF NORTH BAKSLOPE NEAR MILE MARHER 46 44 FT SOUTH OF CURB 73 FT NORTH OF CL WESTBOUND US 20
470200452	8579406.01	14306702.78	1435.57	CP FD X ON BALL OF ROW RAIL ON SOUTH SIDE OF US 20
470200468	8579310.30	14315295.88	1391.88	CP FD REBAR W/ CENTER PUNCH IN SW QUAD US 20/ US 59 INTERSECTION 95 FT SOUTH OF CL EASTBOUND US 20
470200475	8579302.26	14318827.02	1428.30	CP SET FENO MONUMENT ON TOP SOUTH BACKSLOPE 73 FT SOUTH OF EASTBOUND US 20 230 FT EAST CL HARVEST AVE

	ALIGNMENT COORDINATES															101_16 10/25/24			
Line No.	Name Location	Point on Tangent Station	Point on Tangent Y Northing	Point on Tangent X Easting	Begin Spiral Station	Begin Spiral Y Northing	Begin Spiral X Easting	Begin Curve Station	Begin Curve \ Northing	Begin Curve X Easting	PI or Master	Simple Curve PI or Master PI Y Northing	PI or Master	End Curve Station	End Curve Y Northing	End Curve X Easting	End Spiral Station	End Spiral Y Northing	End Spiral X Easting
1.0	MLØ20							11464+73.11	8579518.42	14305151.05	11468+26.35	8579536.15	14305503.84	11471+79.37	8579532.19	14305857.06			1
3.0	ML020	11493+56.58	8579507.77	14308034.13															
4.0	ML020							11572+99.86	8579436.26	14315977.09	11574+67.20	8579434.76	14316144.42	11576+34.52	8579436.75	14316311.75			
5.0	ML020							11576+34.52	8579436.75	14316311.75	11578+01.86	8579438.74	14316479.08	11579+69.19	8579437.24	14316646.41			
6.0	ML020	11583+01.85	8579434.24	14316979.06															
7.0																			
8.0	SRS59	3502+02.07	8578742.33	14315529.9															
9.0	SRS59	3509+00.00	8579440.25	14315533.88															
10.0																			
11.0	SRN59	7494+04.30	8579507.76	14308035.79															
12.0	SRN59	7500+15.74	8580119.15	14308043.02															
13.0																			
14.0	SRINDORF	491+40.06	8579284.22	14308045.82															
15.0	SRINDORF	493+63.60	8579507.71	14308041.16															

	101_17 1/17/24 SPIRAL OR CIRCULAR CURVE DATA																
Line No.	Name	Location	scs	S	Ls	Ts	Es	Xc	Yc	L.T.	S.T.	С	Т	L	R	E	Remarks
1.0	C1	ML020										3.52	353.24	706.26	11497	5.43	
2.0	C2	ML020										1.20	167.34	334.67	16000	0.88	
3.0	C3	ML020										1.20	167.34	334.67	16000	0.88	



