IOWA DEPARTMENT OF TRANSPORTATION

To Office District 1 Date December 3, 2019

Attention Tony Gustafson, ADE Ref No. Franklin County

MBIN-035-1(514)157--0M-35

From WHKS/Joe Stanisz PIN 17-35-035-010

Design No. N/A

Bureau Bridges and Structures File No. N/A

FHWA No. 602425

Subject Final Concept for Bridge Approach Repair of a 314' x 30' Continuous Welded Plate

Girder Bridge

Bridge Maintenance No. 3556.70035

The bridge on Co. Rd. S13 over I-35, 5.0 mi N of Jct. Co. Rd. C70, has been scheduled for bridge approach repair to be let on 1/20/2021. The current cost estimate is \$181,286 including inflation and 20% contingency. The MB program budgeted amount is \$150,000. The bridge was inspected on 9/26/2019 by Josh Opheim and Kirk Romsey with WHKS. Others in attendance included Allison Smyth and Craig Van Der Wilt with the District.

The bridge location map and asset information can be viewed in SIIMS using the following link: https://siims.iowadot.gov/InspectTech/bridgedetail.aspx?type=0&as_id=67926

EXISTING CONDITIONS

The bridge was constructed in 1972 (Des. No. 2970).

Small hollows and PC patches in top of deck and in top of backwall adjacent to sliding plate joints. Bottom of deck contains transverse cracks with leaching.

Localized areas of girder paint failure and rust. Deck drains have been extended.

The retrofit rails and end sections are 34" tall with thrie beam connections (Des. No. 304).

Macadam stone slope protection was installed in 2003.

Co. Rd. S13 in the vicinity of the bridge is a 2-lane, 22-foot wide PCC pavement with 10-ft shoulders (approximately 4 ft. granular and 6 ft. earth). The roadway has no posted speed limit but is presumed to be 55 mph. It has a 2017 ADT of 460 vehicles per day.

The first two panels of both bridge approaches are in poor condition. Approach panels have settled 6 to 8-in at the end of wings and leveling courses have been placed. The approaches are level with the backwall at the bridge. There are EF type joints at 60 and 80 feet from the bridge on both ends.

The guardrail bridge connections are STS and the end treatments are FLEAT. The mounting height in the northwest corner is 31" but the other 3 corners average 28". Shoulders in front of the guardrail are granular.

Page 2 Franklin Co. December 3, 2019

RECOMMENDATIONS

It is recommended that the following repairs be made:

- 1. UAC sliding plate joints and paving notches.
- 2. Clean and seal barrier rails (incidental to Mobilization or approaches).
- 3. Replace the first 2 panels of both bridge approaches with BR-201 10" double reinforced approach.
- 4. Remove and reinstall the existing guardrail.
- 5. Pave from the edge of pavement to the guardrail posts with HMA as per Typical 7156.
- 6. Replace all 4 bridge end drains with DR-402 rock flumes.

Co. Rd. S13 will be closed to traffic during construction. See accompanying Traffic Control Statement for proposed detour route.

Traffic control will be road closure in accordance with Standard Road Plan TC-252. This project is not considered a Traffic Critical Project.

The District should provide a site survey of the utilities.

Estimated cost of repairs is as follows:

ROADWAY ESTIMATE:					
Item	Quantity	Unit	Rate	Amount	
Class 13 Excavation	131	CY	\$35	\$4,585	
Paved Shoulder, HMA, 9"	392	SY	\$59	\$23,128	
Pave Shoulder for Bridge End Drain	76	SY	\$140	\$10,640	
Bridge End Drain (DR-402)	4	EACH	\$4,300	\$17,200	
Remove and Reinstall Guardrail	350	LF	\$20	\$7,000	
Bridge Approach, 10"	249	SY	\$205	\$51,045	
Removal of Pavement	249	SY	\$15	\$3,735	
Traffic Control	1	LS	\$5,000	\$5,000	
Additional Roadway Items	1	LS	\$10,000	\$10,000	
Mobilization	1	LS	10%	\$12,233	
	Base Cost:			\$144,566	
Contingency:		20%	\$28,913		
	1 Years Inflation:		4.5%	\$7,807	
	ROADWA	ROADWAY TOTAL:		\$181,286	
	PROJECT 1	PROJECT TOTAL:		\$181,286	

Page 3 Franklin Co. December 3, 2019

JJO/KR

Distributed to: Scott Dockstader, District 1 Tony Gustafson, District 1 Lance Starbuck, District 1 Jesse Tibodeau, District 1 Craig Vander Wilt, District 1 Denny Howe, District 1 John Narigon, District 1 Allison Smyth, District 1 Charlie Purcell, Project Delivery Scott Marler, Systems Operations Michael Kennerly, Design Kent Nicholson, Design Stuart Nielson, Design Dan Harness, Design Yanxiao Jia. Design Dung Ta, Design Donald Tebben, Program Management Angela Poole, Program Management Mark A Swenson, Project Scheduling DeeAnn Newell, Location and Environment Jill Garton, Location and Environment Brad Azeltine, Location and Environment Valerie Brewer, Location and Environment Matt Donovan, Location and Environment Kenneth Brink, Location and Environment James Nelson, Bridges and Structures Mike Nop, Bridges and Structures David Evans, Bridges and Structures Jesse Peterson, Bridges and Structures Scott Neubauer, Bridges and Structures Joe Stanisz, Bridges and Structures Ronald Meyer, Bridges and Structures Curtis Carter, Construction and Materials Clayton Burke, Construction and Materials Sheri Harris, Document Services Dan Sprengeler, Traffic and Safety

Willy Sorenson, Traffic and Safety