

REVISIONS

PROJECT IDENTIFICATION NUMBER 22-56-027-010 PROJECT NUMBER NHSN-027-1(003)-2R-56 R.O.W. PROJECT NUMBER

PLANS OF PROPOSED IMPROVEMENT ON THE

PRIMARY ROAD SYSTEM SLIDE REPAIR

At the US 218 Interchange (NB)


SCALES: As Noted

Refer to the Proposal Form for list of applicable specifications.


Value Engineering Saves. Refer to Article 1105.14 of the Specifications.



	INDEX OF SHEETS							
No.	DESCRIPTION							
A Sheets	Title Sheets							
A.1	Title Sheet							
A.1	Location Map Sheet							
C Sheets	Sheets Quantities and General Information							
C.1	Estimated Project Quantities							
C.1 Estimate Reference Information								
C.2 Standard Road Plans								
C.2 General Notes								
CS Sheets	Soils Tabulations							
CS.1	Soils Tabulations							
D Sheets	Mainline Plan and Profile Sheets							
* D.1	IA 27							
J Sheets	Traffic Control and Staging Sheets							
J.1	Traffic Control Plan							
Q Sheets	Soils Sheets							
Q.1	IA 27							
R Sheets	Erosion Control Sheets							
RC.1 - 3	Est. Quantities, PPP, General Notes and Tabulations							
* RR.1	Erosion Control Legend and Symbol Information Sheet							
* RR.2	Erosion Control Plan Sheets							
	* Color Plan Sheets							
	. COTOL LIGHT SHEETS							



	INDEX OF SEALS											
SHEET NO.	NAME	TYPE										
A.1	Jason M. Holst	Primary Signature Block										
CS.1	Mark A. Dell	Geotechnical Design										
RC.1	Seana K. Godbold	Landscape Design										



hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Signature *

My license renewal date is December 31, 2021

Pages or sheets covered by this seal: <u>A.1, C.1-C.2, D.1, J.1</u>

LEE COUNTY

PROJECT NUMBER NHSN-027-1(003)--2R-56

SHEET NUMBER

LOCATION MAP SCALE

ESTIMATED PROJECT QUANTITIES AND REFERENCE NOTES

Item no.	Item Code	Item	Unit	Quantities Estimated Roadway Items	Estimate Reference Notes
1	2102-2625000	EMBANKMENT-IN-PLACE	CY	421	Refer to Tab. 103-12 in CS sheets. Material shall be provided by the Contractor.
2	2102-2710090	EXCAVATION, CLASS 10, WASTE	CY	665	All waste must be removed from the project site. Overhaul will not be measured or paid for , but shall be considered incidental to excavation on this project.
3	2105-8425005	TOPSOIL, FURNISH AND SPREAD	CY	244	Refer to Tab. 103-10 and 103-12 in the CS sheets.
4	2107-0875100	COMPACTION WITH MOISTURE CONTROL	CY	421	Refer to Tab. 103-6 in CS sheets. Cubic yards shown on the contract documents as determined by the template fill volume. Shrinkage will not be included in the moisture control quantity.
5		GRANULAR MATERIAL FOR BLANKET AND SUBDRAIN	CY	40	Refer to Tab. 103-12 in the CS sheets.
6		SUBDRAIN, LONGITUDINAL, (BACKSLOPE) 4 IN. DIA.	LF	330	Refer to Tab.104-9 in the CS sheets. Remove and dispose of the excavation material according to Article 1106.07 of the current specifications.
7	2502-8221306	SUBDRAIN OUTLET, DR-306	EACH	2	Refer to Tab. 104-9 in the CS sheets.
8	2528-8445110	TRAFFIC CONTROL	LS	1	Refer to Traffic Control Plan in J sheets.
9	2533-4980005	MOBILIZATION	LS	1	

Roadway Items: Roadway Items

Design Team :Jason Holst County Name :Lee Project Number:NHSN-027-1(003)--2R-56 12/02/2021 7:58 AM SHEET C.1

STANDARD ROAD PLANS

The following Standard Road Plans apply to construction work on this project.

Number Date Title

DR-303 10-17-17 Subdrains (Longitudinal)

DR-306 10-16-18 Precast Concrete Headwall for Subdrain Outlets

SI-881 04-16-19 Special Signs for Workzones

TC-1 10-15-19 Work Not Affecting Traffic (Two-Lane or Multi-Lane)

TC-402 04-21-15 Work Within 15 ft of Traveled Way

TC-415 04-21-20 Stort Term Lane Closure with TMA

TC-418 04-21-20 Lane Closure on Divided Highway

253-1 10-18-1

MEDIAN CROSSOVER

The Contractor is prohibited from using any established or other type median crossover on this project unless specifically designated for the Contractor's use by this plan.

SEE RC SHEETS FOR ADDITIONAL BID ITEMS AND QUANTITIES.

FILE NO. ENGLISH DESIGN TEAM HOIST\Dudley

LEE COUNTY PROJECT NUMBER NHSN-027-1(003)--2R-56 SHEET NUMBER C.2

1	03-	-12
10	20	20

SLIDE REPAIR

C1 C1 C1 10115 51 10115 C1 51 C1 C1	Remarks		Strip, Salvage & Spread	Tops Furnish & Spread	Macadam Stone Slope Protection	Gra. Material Blankets & Subdrain	Erosion Stone	Engineering Fabric	Class "E" Revetment	, Class 10 Waste	Excavation Roadway and Borrow	Embankment-in- Place	Class 13 Excavation Waste	Side		Locat Begin Sta.	Site - No.
1 173+98.00 174+46.00 Rt. 421 665 40 244 Stationing is in metric			CY	CY	SY	CY	Tons	SY	Tons	CY	CY	CY	CY				
71		Stationing is in metric		244		40				665		421		Rt.	174+46.00	173+98.00	1

		TOPSO	IL STRIP	PPING AND P	LACEMENT	103-10 04-18-17
Road Identification	Dir. of	Begin Station	End Station	Topsoil Stripping Thickness	Topsoil Placement Thickness	Remarks
	Trattic			IN	IN	
IA 27	NBL	173+98.00	174+46.00		8.0	Stationing is in metric
IA 27	NBL	173+98.00	174+46.00		8.0	Stationing is in metric

103-6 10-17-17

EMBANKMENT WITH MOISTURE CONTROL

Moisture Control is required for all Class 10 fill placed in all locations and depths. Stability berms placed outside the normal foreslope template and topsoil will not require Moisture Control

104-9 10-17-17

LONGITUDINAL SUBDRAIN SHOULDER AND BACKSLOPE

Refer to Soils Sheets

* Not a bid item. Bridge berm quantities assume a trench depth of 24 inches.

		Location						Longit	udinal S	ubdrain (DR-303)			Subd	rain Outlet							
Line	Road or Lane				Depth	Shou	ılder	Backs	slope	Bridge Berm (EW-	203 or E	N-204)	DR-303, D	R-305 or DR-306	Porous*	Class "A"* Crushed	Daviados				
No.	Identification	Station t	o Station	Side	(D)	Size	Length	Size	Length	Standard Road Plan	Size	Length	Station	Standard Road Plan Stone	Backfill Stone	Stone	Stone	Stone	Stone Stone	Stone	Remarks
					IN	IN	FT	IN	FT	and Type	IN	FT		and Type	CY	CY					
1	NBL	173+98.00	174+46.00	RT	66.0			4.0	165.0				174+21	DR-306	20.4		Place on upper bench. Stationing is in metric				
2	NBL	173+98.00	174+46.00	RT	66.0			4.0	165.0				174+23	DR-306	20.4		Place on middle bench. Stationing is in metric.				
Total						******************	0.0		330.0					DR-306 = 2							
					The state of the s		111111111111111111111111111111111111111														

PROFESSION A	by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of
Mark A. GINER	Signature II/22/2
21208	Mark A. Dell
MA ANTONIA O WA	Printed or Typed Name My license renewal date is December 31, 2021

FILE NO. ENGLISH DESIGN TEAM Megivern\Dell\Moyle


LEE COUNTY PROJECT NUMBER

NHSN-027-1(3)--2R-56

SHEET NUMBER

CS.1

gmoyle c:\pw work\pwmain\gmoyle\d1357865\56027003.xlsm



	108-23A
	08-01-08
COORDINA	TRAFFIC CONTROL PLAN
COOKDINA	shall be maintained at all times on IA 27 and the IA 27/US 218 interchange ramps.
Other work in progress duri include the construction of	lane closures on IA 27 will be limited only to the delivery and hauling of materials and equipment.
include the construction of	
onerations with those of ot	

111-01 04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work						
NHSN-218-1(80)2R-56	PCC PAVEMENT - GRADE AND NEW						

108-25 10-21-14

511 TRAVEL RESTRICTIONS

Route	Direction	County	Location Description	Feature Crossed	Object Type	Maint. Bridge No., Structure ID, or FHWA No.	Type of Restriction	Existing Measurement	Construction Measurement	Construction Measurement as Signed	Remarks
		None.									

IA 27, Lee Co. Slide Repair

GENERAL NOTES:

The design intent is to repair the foreslope instability along the east side of IA 27 at its interchange with US 218 located south of the City of Donnellson in Lee County, Iowa. Be aware that the actual limits of the repair discussed below may be found to have changed (enlarged) at the time of construction due to possible continued slope movements.

EXISTING CONDITIONS:

Based on field conditions observed on June 9, 2021, the foreslope instability can be described as a shallow circular slope failure which, as a result of the movement, has created a scarp located about 20 feet away from the outside edge of the gravel shoulder. The scarp has a maximum height of about 2 to 3 feet. Sloughed material was not evident at the toe of slope.


PROPOSED FORESLOPE REPAIR:

From Station 173+98 to Station 174+46 (metric stationing), cut benches in the existing foreslope as shown in the Typical Section below and waste excavated material off-site. Prior to benching, the surficial 12 inches of material shall be stripped from the foreslope and stockpiled to be used later to topsoil the reconstructed foreslope. The foreslope repair shall start at the toe of the existing foreslope and then extend up-slope to within about 10 feet from the outside edge of the gravel shoulder.

Install 6-inch diameter "backslope type" subdrains on specific cut benches to move water away more efficiently from the rebuilt foreslope. These drains shall be installed per Standard Road Plan DR-303 for Subdrains using Type 11 installation. Subdrains shall then outlet on the rebuilt foreslope using DR-306 outlets. Please refer to the Longitudinal Subdrain Shoulder and Backslope tab (104-9) on Sheet CS.1 for additional details regarding the drain and outlet locations.

The cut benches shall then be backfilled with suitable cohesive furnished embankment to rebuild the foreslope back to pre-existing conditions. Place 8 inches of furnished topsoil on the final foreslope surface. The rebuilt foreslope shall transition back to the existing foreslope at the limits of the repair.

Typical Section (Not to Scale)



Benches shall extend a minimum of 6 feet into the undisturbed foreslope.

			LANDSCAPE DESIGN
			Thereby certify that the portion of this technical submission described below was prepared by me or under my direct supervision and responsible charge. I am a duly licensed professional landscape architect under the laws of the state of Iowa. Seana K. Godbold 12/2/2021 Signature Date Seana K. Godbold Printed or Typed Name My license renewal date is June 30, 2023
			Pages or sheets covered by this seal: RC.1 - 3; RR.1 - 2
FILE NO. 12/3/2021 11:11:03 AM	PROBLISH DESIGN TEAM GODBOLD\POHLEN\MCDONALD npohlen c:\pw_work\pwmain\idotcentral_npohlen\d1357545\56027003_RC01.xlsm	LEE COUNTY PROJECT NUMBER	NHSN-027-1(3)2R-56 SHEET NUMBER RC.1

ESTIMATED PROJECT QUANTITIES AND REFERENCE NOTES

Item no.	Item Code	Item	Unit	Quantities Estimated Roadside Items	Estimate Reference Notes
1	2601-2643412	TURF REINFORCEMENT MAT, TYPE 2	SQ	112	
2	2602-0000020	SILT FENCE	LF	196.9	Refer to Tab. 100-17. The tabulation includes estimated locations for placement of "Silt Fence" to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 25% additional quantity for field adjustments and replacements.
3		REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	LF	196.9	This item is included for silt fence and silt fence for ditch check removal required for staging reasons, removal to allow for replacement (replacement to be paid separately), or for areas that have achieved 70% permanent growth. This item is included for silt fence and silt fence for ditch check removal. Remove silt fence and posts after mulching or vegetation is established and approved by the engineer.
4	2602-0000101	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	LF	19.7	This item is included for clean-out and repair of the silt fence and silt fence for ditch checks during the project.
5	2602-0000312	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	LF	196.9	Refer to Tab. 100-19. The tabulation includes estimated locations for placement of "Perimeter and Slope Sediment Control Device, 12 in. dia." to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 25% additional quantity for field adjustments and replacements. Use Perimeter and Slope Sediment Control Devices fabricated using wood excelsior.
6	2602-0000351	REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	LF	196.9	

Roadside Items: Roadside Items

Design Team :Godbold/Pohlen/McDonald County Name :Lee Project Number:NHSN-027-1(003)--2R-56 12/02/2021 SHEET RC.2

	TNDEY OF TABLE ATTONS	111-25 10-18-11
	INDEX OF TABULATIONS	
Tabulation	Tabulation Title	Sheet No.
RC Sheets		
	SIGNATURE SHEET	RC.1
	ESTIMATED PROJECT QUANTITIES AND REFERENCE NOTES	RC.2
100-17	TABULATION OF SILT FENCES	RC.3
100-19	PERIMETER, SLOPE AND DITCH CHECK SEDIMENT CONTROL DEVICES	RC.3
100-22	ROLLED EROSION CONTROL	RC.3
105-4	STANDARD ROAD PLANS	RC.3
111-25	INDEX OF TABULATIONS	RC.3
232-3A	EROSION CONTROL (RURAL SEEDING)	RC.3
232-11	EROSION CONTROL (STABILIZING CROP SEEDING)	RC.3
281-3	STORM WATER BEST MANAGEMENT PRACTICES	RC.3

STANDARD ROAD PLANS

		The following Standard Road Plans apply to construction work on this project.
Number	Date	Title
EC-104	04-17-18	Turf Reinforced Mat (TRM)
EC-201	04-20-21	Silt Fence
EC-204	04-20-21	Perimeter, Slope and Ditch Check Sediment Control Devices
EC-502	04-21-15	Seeding in Rural Areas

281-3 10-17-17

04-21-15

STORM WATER **BEST MANAGEMENT PRACTICES**

hen the following best management practices are used, they are intended to account for disturbed areas where storage volume cannot be provided: TRM Type 2, PSSCD, Seeding

04-16-19 **EROSION CONTROL**

(RURAL SEEDING)

Following the completion of work in a disturbed area and according to the seeding dates in Section 2601 of the Standard Specifications, place seed, fertilizer, and mulch on the disturbed area lying 8 feet adjacent to shoulder and median as follows:

Place seed and fertilize according to the requirements of Article 2601.03,C,3 and Section 4169 of the Standard Specifications.

Place mulch according to the requirements of Articles 2601.03,E,2,a and 4169.07,A of the Standard Specifications.

Preparing the seedbed, furnishing and applying seed, fertilizer, and mulch are all incidental to mobilization and will not be paid for separately.

232-11 04-16-19

10-18-1

232-3A

EROSION CONTROL

(STABILIZING CROP SEEDING)

If outside of permanent seeding dates in Section 2601 of the Standard Specifications, or if required by a storm water permit, place stabilizing crop, fertilizer, and mulch on the disturbed area as follows:

Place seed and fertilize according to the requirements of Article 2601.03,C,1 and Section 4169 of the Standard Specifications.

Place mulch according to the requirements of Articles 2601.03,E,2,a and 4169.07,A of the Standard Specifications.

Preparing the seedbed, furnishing and applying seed, fertilizer, and mulch are incidental to mobilization and will not be paid for separately.

ROLLED EROSION CONTROL

					Ret	er to EC-	101, EC-10:	3 and EC-16	14				
L	ocatio	n					Turf Rei	nforcement	Mat (TRM)	(FC-104)	Slope Protection	Special Ditch	
Road Identification		Begin	End	Side	(L)	(W)	Type 1	Type 2	Type 3	Type 4	· ·	Control (EC-101)	Remarks
		Station	Station		FT	FT	Squares	Squares	Squares	Squares	Squares	Squares	
I	A 27	173+98.00	174+46.00	Rt	160	70		112					
		Rolled Erosi	ion Control Tab	Totals:				112					
1													


100-19 Modified PERIMETER, SLOPE AND DITCH CHECK SEDIMENT CONTROL DEVICES Possible Standards: EC-204 Location Perimeter and Slope Ditch Check Length of Installation Length of Installation Remarks Side 9 inch Dia 12 inch Dia 20 inch Dia 12 inch Dia 20 inch Dia Begin Station End Station 173+98.00 174+46.00 Rt 45' OS Station in Metric 157.5 CD Tab Totals: 157.5 CD Bid Totals: 125% of Bid Total PSSCD Removal Totals: 196.9 100% of Bid Total

TABULATION OF SILT FENCES Refer to EC-201 Length Remarks Begin Station End Station Side 173+98.00 174+46.00 Rt 157.5 Station in Metric SF Tab Totals: SF Bid Totals: 196.9 | 125% of Tab Total 19.7 10% of Bid Total SF maintenance Totals: SF Removal Totals: 196.9 | 100% of Bid Total

Silt Fence Perimeter and Slope Sediment Control Device (9") Perimeter and Slope Sediment Control Device (12") Perimeter and Slope Sediment Control Device (20") Open-Throat Curb Intake Sediment Filter Concentrated Flow Sheet Flow

CELL LEGEND OF EROSION CONTROL SHEETS Temporary Sediment Control basin Erosion Control for Circular Intake or Manhole Well Erosion Control for Rectangular Intake or Manhole Well Grate Intake Sediment Filter Bag Silt Basin Silt Fence Tail Stormwater Drainage Basin Discharge Point

Green Blue	(2) (1)	Existing Topographic Features and Labels Proposed Alignment, Stationing, Tic Marks, and	Alignment Annotation
Magenta Black	(5)	■ Existing Utilities ■ Permanent Erosion Control Features	
Blaze Orange	(222)		
SHADING	Design Co	lor No.	Transparency
Citron	(234)	Mulching, All Types	50%
Light Brown	(238)	Special Ditch Control, Wood Excelsior Mat	0%



EROSION CONTROL LEGEND AND SYMBOL INFORMATION SHEET

(COVERS SHEET SERIES R)

FILE NO. ENGLISH

