

HMA RESURFACING WITH MILLING
NHSX-092-5(70)--3H-91

WARREN COUNTY

LETTING DATE
11-15-2022



PLANS OF PROPOSED IMPROVEMENT ON THE
PRIMARY ROAD SYSTEM
WARREN COUNTY
HMA RESURFACING WITH MILLING
0.3 mi E of I-35 to Kennedy St

SCALES: As Noted

Refer to the Proposal Form for list of applicable specifications.

Value Engineering Saves. Refer to Article 1105.14 of the Specifications.



REVISIONS

TOTAL

PROJECT IDENTIFICATION NUMBER

22-91-092-010


PROJECT NUMBER

NHSX-092-5(70)--3H-91

R.O.W. PROJECT NUMBER


INDEX OF SHEETS

No.	DESCRIPTION
A Sheets	Title Sheets
A.1	Title Sheet and Location Map
* A.2 - 11	Project Concept
* A.12	Design Criteria
* A.13 - 17	D2 Questions - with Answers
B Sheets	Typical Cross Sections and Details
B.1 - 2	Typical Cross Sections and Details
D Sheets	Mainline Plan and Profile Sheets
D.1 - 17	IA 92 As-Built Plan and Profile
J Sheets	Traffic Control and Staging Sheets
J.1	Traffic Control Plan
J.1	Coordinated Operations
* J.2	Centerline Rumble Strips (Two-Lane) Traffic Detail
	* Color Plan Sheets



4/13/2022 FIELD EXAM NOTES:
Refer to 'D2 Questions - with Answers' on Sheets A.13 to A.17 for compilation of Notes taken during the 4/13/2022 Field Exam and subsequent follow-up information.

Project Design Events:
DM5 - 08-02-2022
D7 - 09-06-2022



WARREN COUNTY DESIGN DATA RURAL	
2023 AADT	3,863 V.P.D.
2043 AADT	5,021 V.P.D.
2043 DHV	520 V.P.H.
TRUCKS	11 %
Total Design ESALs	920,430

INDEX OF SEALS		
A.1	Jonathan W. Bahr	Primary Signature Block
X	X	X

PRELIMINARY PLANS

Subject to change by final design.

D2 PLAN - Date: 04-21-2022



County

Project Number

Date

TO OFFICE: District 5

DATE: October 26, 2021

ATTENTION: Bob Younie

COUNTY: Warren County

FROM: Gary Kretlow

PROJ. NO.: NHSX-092-5(70)--3H-91


OFFICE: District 5

PIN: 22-91-092-010

FOLDER: [ProjectWise Link](#)

SUBJECT: FY 2023 3R Concept Statement - **FINAL**

PROJECT LOCATION:



PROJECT DATA:

ROUTE: Iowa 92
 LENGTH: 6.65 miles
 PLANNING CLASSIFICATION: Other Principal Arterial
 MAINTENANCE SERVICE LEVEL: C
 NHS ROUTE: Yes
 TRAFFIC: Current Year: 3900 ADT with 11% Trucks
 Design Year: 5000 ADT with 11% Trucks

PURPOSE AND NEED:

The existing pavement has deteriorated and is in need of rehabilitation.

FEASIBLE ALTERNATIVES:

- 1a. CIP West of IA 28-\$821,400
- 1b. CIP East of IA 28-\$1,420,000
- 2a. Scarification & Resurfacing W. of IA 28-\$516,600
- 2b. Scarification & Resurfacing E. of IA 28-\$1,146,000

West of IA 28 Costs and Alternatives

HMA Mill and Fill (2" Scarification, 4" Overlay) Alternative 2A					
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL
1	2" SCARIFICATION	SY	19,800	\$ 2.00	\$ 39,600.00
2	4" HMA RESURFACING (24' x 2")	TON	4,300	\$ 32.00	\$ 137,600.00
3	ASPHALT BINDER	TON	260	\$ 450.00	\$ 117,000.00
4	CENTERLINE RUMBLE STRIPS, HMA	STA	100	\$ 12.00	\$ 1,200.00
5	LONGITUDINAL SUBDRAINS	LF	7,400	\$ 10.00	\$ 74,000.00
6	PAINTED PAVEMENT MARKINGS	STA	300	\$ 11.00	\$ 3,300.00
7	TRAFFIC CONTROL	LS	1		\$ 69,300.00
8	MOBILIZATION	LS	1		\$ 50,000.00
				SUBTOTAL	\$ 492,000.00
	Contingency			5%	\$ 24,600.00
				TOTAL	\$ 516,600.00

2" CIP & 4" HMA OVERLAY (Alternative 1A)					
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL
1	CIPR ASPHALT PAVEMENT, 2"	SY	19,800	\$ 1.60	\$ 31,680.00
2	ASPHALT STABILIZING AGENT (F.A.)	TON	90	\$ 450.00	\$ 40,500.00
3	HMA RESURFACING (24' x 4" THICK)	TON	4,300	\$ 32.00	\$ 137,600.00
4	ASPHALT BINDER	TON	260	\$ 450.00	\$ 117,000.00
5	LONGITUDINAL SUBDRAINS	LF	7,400	\$ 10.00	\$ 74,000.00
6	PAINTED PAVEMENT MARKINGS	STA	300	\$ 11.00	\$ 3,300.00
7	CENTERLINE RUMBLE STRIPS, HMA	STA	100	\$ 12.00	\$ 1,200.00
8	TRAFFIC CONTROL (Flaggers/Pilot Cars)	LS	1		\$ 248,000.00
9	MOBILIZATION	LS	1		\$ 50,000.00
				SUBTOTAL	\$ 782,140.00
	Contingency			5%	\$ 39,200.00
				TOTAL	\$ 821,340.00

East of IA 28 Costs and Alternatives

HMA Mill and Fill (2" Scarification, 3" Overlay) Alternative 2B						
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL	
1	2" SCARIFICATION	SY	62,400	\$ 2.00	\$ 124,800.00	
2	4" HMA RESURFACING (24' x 2")	TON	10,200	\$ 32.00	\$ 326,400.00	
3	ASPHALT BINDER	TON	610	\$ 450.00	\$ 274,500.00	
4	CENTERLINE RUMBLE STRIPS, HMA	STA	300	\$ 12.00	\$ 3,600.00	
5	LONGITUDINAL SUBDRAINS	LF	23400	\$ 10.00	\$ 234,000.00	
6	PAINTED PAVEMENT MARKINGS	STA	800	\$ 11.00	\$ 8,800.00	
7	TRAFFIC CONTROL	LS	1		\$ 69,300.00	
8	MOBILIZATION	LS	1		\$ 50,000.00	
				SUBTOTAL	\$ 1,091,400.00	
	Contingency			5%	\$ 54,600.00	
				TOTAL	\$ 1,146,000.00	
2" CIP & 4" HMA OVERLAY (Alternative 1B)						
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL	
1	CIPR ASPHALT PAVEMENT, 2"	SY	62,400	\$ 1.60	\$ 99,840.00	
2	ASPHALT STABILIZING AGENT (F.A.)	TON	140	\$ 450.00	\$ 63,000.00	
3	HMA RESURFACING (24' x 2" THICK)	TON	6,800	\$ 32.00	\$ 217,600.00	
4	ASPHALT BINDER	TON	410	\$ 450.00	\$ 184,500.00	
5	LONGITUDINAL SUBDRAINS	LF	23,400	\$ 10.00	\$ 234,000.00	
6	PAINTED PAVEMENT MARKINGS	STA	300	\$ 11.00	\$ 3,300.00	
7	CENTERLINE RUMBLE STRIPS, HMA	STA	100	\$ 12.00	\$ 1,200.00	
8	TRAFFIC CONTROL (Flaggers/Pilot Cars)	LS	1		\$ 248,000.00	
9	MOBILIZATION	LS	1		\$ 50,000.00	
				SUBTOTAL	\$ 1,350,680.00	
	Contingency			5%	\$ 67,600.00	
				TOTAL	\$ 1,418,280.00	

RECOMMENDATIONS:

Options 2a and 2b are recommended at a cost of \$1,662,600.

FUNDS PROGRAMMED:

This project will be funded with FY 2023 3R funds.

PROJECT IMPACTS:

Designed by: District/Design/Consultant

Design Impact	Assistance Requested (Y/N)	Remarks
ADA:	N	
Agreements/Notification Letters:	Y	Warren County-Agreement Martensdale-Notification
Bridges and Structures:	Y	See culverts & pipes section

Consultant:	N	
Contracts:	N	
Design/Methods:	Y	
Location and Environment:	Y	Preliminary Review
Maintenance: (Martensdale)	Y	Update culvert inventory
Project Management:	N	
Railroad:	N	
RCE: (Chariton)	Y	Patching, Guardrail, and Clearing & Grubbing
Right of Way:	N	
Soils:	N	
Survey/Photogrammetry:	N	
Systems Planning:	N	
Traffic and Safety:	N	
Utilities:	N	
Other:		

CONCEPT ANALYSIS & SUPPORTING DATA:

Necessary supporting data may be linked in the analysis to ProjectWise.

Date of Field Review:

May 18th, 2021

Participants:

Todd Netley-Martensdale HMS
Gary Kretlow-District 1

PAVEMENT:

Existing Conditions:

The current IA 92 pavement is distressed and has multiple transverse and longitudinal cracks. The current IRI for the project is between 112 and 121.

Pavement History:

See attached sheets.

PMIS Data:

See attached sheet.

Pavement Design & dTIMS Recommendation:

The pavement design section is recommending a 4" overlay from 119.45 to 120.85 and from 121.46 to 125.94 is recommending 2.5". dTims is recommending CIR for both sections.

The gap from 120.85 to 121.46 is a newer PCC section from when the intersection with IA 28 was reconstructed. It will be UAC'd with this project.

This project will be 24' wide lanes with a 4' wide paved and 4' granular shoulder. The 4' paved shoulder will be UAC'd.

See the typical 7152 B below. The proposed HMA scarification/overlay is to have a longitudinal runout along the edge of the PCC gutter. HMA overlay is not to be placed onto the PCC gutter pan, nor the face of the curb.

There are 11 locations along hilltops where there is no ditch, and the backslope previously eroded onto the prior granular shoulder. The locations placed a 5.5 ft width HMA paved shoulder with a 2.0 ft sloped PCC curb at those locations and tied the backslopes/hilltop to the top of the curb similar to typical 7152 B below.

**TYPICAL SECTION PAVED SHOULDER
HOT MIX ASPHALT WITH
6" SLOPED CURB AND GUTTER UNIT
ALONG HILLTOPS**

DESIGN RATES	
ITEM	RATE
HMA Base	145 lbs/cu ft
Asphalt Binder	6% Content
Type "B" Granular	140 lbs/cu ft
Tack Coat *	0.05 gal/sq yd

* Not a bid item

Location		Side	Feet	Quantities (1)				
Road Identification	Station to Station			6" Sloped Curb Stations (2)	CL 13 Excav. Roadway & Borrow Du.Yds. (2)	Paved Shoulder Sq.Yds. (2)	Hot Mix Asphalt Tons (4)	Tack Coat Gal. (5)
Begin Project								
Stop Project, Equation:	131+19.42 BK 231+35.00 AH							
Resume Project, Equation:	257+93.00 BK 19458.33 AH							
Middle River Bridge, Maint # 9121.75092, FHWA # 51111								
IA 92	65+30.00 67+30.00	RT	7	2.00	26.85	61.11	19.94	3.06 1.20
IA 92	87+60.00 90+15.00	RT	7	2.55	26.85	61.11	19.94	3.06 1.20
IA 92	98+25.00 103+90.00	RT	7	5.65	26.85	61.11	19.94	3.06 1.20
IA 92	99+70.00 100+95.00	LT	7	1.25	26.85	61.11	19.94	3.06 1.20
IA 92	132+60.00 135+50.00	RT	7	2.90	26.85	61.11	19.94	3.06 1.20
IA 92	140+35.00 145+45.00	RT	7	5.10	26.85	61.11	19.94	3.06 1.20
IA 92	186+00.00 192+50.00	RT	7	6.50	26.85	61.11	19.94	3.06 1.20
IA 92	227+00.00 230+90.00	LT	7	3.90	26.85	61.11	19.94	3.06 1.20
IA 92	227+00.00 230+90.00	RT	7	3.90	26.85	61.11	19.94	3.06 1.20
IA 92	241+70.00 246+20.00	RT	7	4.50	26.85	61.11	19.94	3.06 1.20
IA 92	253+15.00 256+49.40	RT	7	3.34	26.85	61.11	19.94	3.06 1.20
Totals				41.590	1116.85	2541.85	829.29	127.09 49.77

Subdrains:

IA 92 currently has 50% coverage with all longitudinal subdrain along the eastbound lane. To get 100%, approximately 33,000 linear feet of subdrain would need to be installed along the westbound lane.

Patching/Curb Repairs:

During the field review, maintenance asked to review current curbed sections for possible extensions to help with erosion issues. There is specifically an issue at the addresses of 7600-7602 IA 92 on the south side that when it rains, water doesn't drain to the entrance pipe but goes over the driveway. Looks like an area for a possible shoulder fillet. A patch tab will need to be put together by the Chariton RCE office.

ADA/Sidewalk/Trails:

Complete streets analysis.

SAFETY:

3R Design Criteria:

Acceptable Values for 3R Roadway Features						Project Values
DESIGN ELEMENT	FREEWAY	NON-FREEWAY				
Regulatory Speed (mph)	65/55	55	45	35	25	55
Minimum Vertical Curve (mph)	65/55	35	25	15	5	35
Maximum Horizontal Curve (degrees)	3	6	8	14	28	6
Maximum Gradient	3%	6%	7%	10%	13%	6%
Lane Width (feet)	12	12	11	11	11	12
Parking Lane Width (feet)	--	--	8	8	8	N/A
Shoulder Width (feet)	10/6	6	4	4	2	6
Foreslopes	3:1	3:1	3:1	--	--	3:1
Transverse Slopes	6:1	6:1	6:1	--	--	6:1
Horizontal Clearance (feet)						
Bridge Width	Approach Lanes + Shoulder Width		Approach Lanes + Offset			
Vertical Clearance - Over NHS (feet)	16.5	16.5	16.5	16.5	16.5	N/A
Vertical Clearance - Over Local (feet)	14.5	14.5	14.5	14.5	14.5	N/A

Crash Analysis:

ICAT quick report with 5 year crash history summary and intersection diagrams in this link.

<W:\Highway\District1\Design\District 5 Concepts\Warren 92\Crash>

Corridor Crash History:

There were 55 crashes within the project limits between 2016-2020. There were 0 fatal crashes, 1 suspected serious injury crash, and 7 minor/possible injury crashes. 27 of the 55 crashes were animal related. The next major cause was 7 run off the road right or left.

Intersection Crash History:

All the intersections within the project limits are Tier 2 locations on the PCR (potential for crash reduction) website.

Intersection Analysis:

Review the need for turn lanes at County Road R45 (St. Marys Road).

Additional Safety & Operation Considerations:

Identify impacts to District Road Safety Plan, 4-to 3 lane conversion, rumble strips, safety dikes, Super 2 Highway, freight bottle neck, etc.

STRUCTURES and DRAINAGE:

Bridges: (from Scoping Tool or SIIMS)

FHWA No.	Maint. No.	Size/Type	Year Built	BDO/Rehab Year	Bridge Rail Height	End Post Type	Vertical Clearance	Future Projects
051111	9121.7s092	261' x 40' Prestres Conc. Beam	1982		32"	Concrete Vertical Face	N/A	None
051120	9123.2s092	21' x 97' Concrete Box Culvert	1928	1966 and 1992	N/A	N/A	N/A	None

Bridges are in good shape. Do not appear to need any work at this time.

Culverts/Pipes:

Here is a link to the culvert/pipe inventory from the database.

<W:\Highway\District1\Design\District 5 Concepts\Warren 92\EastCulverts.xlsx>

<W:\Highway\District1\Design\District 5 Concepts\Warren 92\WestCulverts.xlsx>

BSB is requested to review the structure at Station 65 (MM 119.7) based on recent review by the Martensdale garage staff.

Guardrail:

Here is a link to the steal beam guardrail within the project limits.

<W:\Highway\District1\Design\District 5 Concepts\Warren 92\Steel Beam Guardrail.xlsx>

Paved shoulders were installed in 2017. Updated guardrail was installed at that time. Will want to review to make sure guardrail is meeting current standards.

Drainage District:

No known drainage districts within the project limits.

PROJECT IMPACTS:

Impacts Map:

- Location**
 - Railroad Crossings (0)
 - Major Pipelines (2)
 - Runways (0)
 - Active Rail Lines (0)
 - Maintenance Garages (1)
 - MPO (0)
 - RPA (1)
 - Trails (0)
 - Abandoned Rail Lines (6)
 - Transmission Lines (0)
 - Cell Towers (0)
 - Rest Areas (0)
 - 5 Year Program (2021 Pts) (0)
 - 5 Year Program (2021) (0)
 - 5 Year Program (2022 Pts) (0)
 - 5 Year Program (2022) (0)
 - 5 Year Program (2023 Pts) (0)
 - 5 Year Program (2023) (0)
 - 5 Year Program (2024 Pts) (0)
 - 5 Year Program (2024) (0)
 - 5 Year Program (2025 Pts) (0)
 - 5 Year Program (2025) (0)
 - Construction History (22)
 - Historic Rail Lines (30)
- Waterway**
 - Topeka Shiner Streams (0)
 - Outstanding Iowa Waters (0)
 - Paddling Routes (1)
 - NRI (0)
 - Floodplains (1)
 - Public Lakes Watersheds (0)
 - Stream Watersheds (2)
 - TMDL Watersheds (1)
 - Streams (71)
- Environmental**
 - Loess Hills (0)
 - LUST Sites (1)
 - T&E (0)
 - Environmental Hotspots (3)
 - Conservation & Rec Lands (1)
 - Public Lands (0)
 - Parks (0)
 - WMA (0)
 - Wildlife Refuges (0)
 - Wetlands (NWI) (50)
- Route**
 - Park and Ride (0)
 - L RTP Bridges (1)
 - L RTP Capacity (0)
 - L RTP Freight (0)
 - L RTP Mobility & Safety (0)
 - L RTP Operations (39)
 - L RTP Park & Ride (0)
 - L RTP Condition (15)
- Safety**
 - SICL Intersections (11)
 - Fatal Crashes (2)
 - Major Injury Crashes (4)
 - Minor Injury Crashes (9)
 - PDO Crashes (70)
 - Unknown Crashes (5)
- Traffic**
 - LOS C (Existing) (0)
 - LOS D (Existing) (0)
 - LOS E (Existing) (0)
 - LOS F (Existing) (0)



Environmental:

Clearing and grubbing will be needed within the project limits. Chariton RCE will need to tabulate limits by January 1, 2022.

TSMO/Traffic Control:

IA 92 traffic will be maintained at all times via flagger and/or pilot cars.

ROW:

No right of way needs are anticipated.

County

Project Number

Date

County

Project Number

Date

Agreements/Notification Letters:

An agreement may be needed with Warren county if they elect to pave any unpaved side road approaches. The city of Martensdale will need a notification letter.

Project Coordination:

No coordination anticipated.

Previous Projects List:

kIFA-365	1932	PCC 7"
P-1023(2)	1956	HMA 4"
FN-92-5(20)21-91	1982	BSC
FN-92-5(31)21-91	1992	HMA 3"

Future Projects List:

No future projects anticipated.

FEASIBLE ALTERNATIVES & RECOMMENDATION:

FEASIBLE ALTERNATIVES:

- 1a. CIP West of IA 28-\$821,400
- 1b. CIP East of IA 28-\$1,420,000
- 2a. Scarification & Resurfacing W. of IA 28-\$516,600
- 2b. Scarification & Resurfacing E. of IA 28-\$1,146,000

West of IA 28 Costs and Alternatives

HMA Mill and Fill (2" Scarification, 4" Overlay) Alternative 2A						
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL	
1	2" SCARIFICATION	SY	19,800	\$ 2.00	\$	39,600.00
2	4" HMA RESURFACING (24' x 2")	TON	4,300	\$ 32.00	\$	137,600.00
3	ASPHALT BINDER	TON	260	\$ 450.00	\$	117,000.00
4	CENTERLINE RUMBLE STRIPS, HMA	STA	100	\$ 12.00	\$	1,200.00
5	LONGITUDINAL SUBDRAINS	LF	7400	\$ 10.00	\$	74,000.00
6	PAINTED PAVEMENT MARKINGS	STA	300	\$ 11.00	\$	3,300.00
7	TRAFFIC CONTROL	LS	1		\$	69,300.00
8	MOBILIZATION	LS	1		\$	50,000.00
					SUBTOTAL	\$ 492,000.00
	Contingency			5%	\$	24,600.00
					TOTAL	\$ 516,600.00
2" CIP & 4" HMA OVERLAY (Alternative 1A)						
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL	
1	CIPR ASPHALT PAVEMENT, 2"	SY	19,800	\$ 1.60	\$	31,680.00
2	ASPHALT STABILIZING AGENT (F.A.)	TON	90	\$ 450.00	\$	40,500.00
3	HMA RESURFACING (24' x 4" THICK)	TON	4,300	\$ 32.00	\$	137,600.00
4	ASPHALT BINDER	TON	260	\$ 450.00	\$	117,000.00
5	LONGITUDINAL SUBDRAINS	LF	7,400	\$ 10.00	\$	74,000.00
6	PAINTED PAVEMENT MARKINGS	STA	300	\$ 11.00	\$	3,300.00
7	CENTERLINE RUMBLE STRIPS, HMA	STA	100	\$ 12.00	\$	1,200.00
8	TRAFFIC CONTROL (Flaggers/Pilot Cars)	LS	1		\$	248,000.00
9	MOBILIZATION	LS	1		\$	50,000.00
					SUBTOTAL	\$ 782,140.00
	Contingency			5%	\$	39,200.00
					TOTAL	\$ 821,340.00

East of IA 28 Costs and Alternatives

HMA Mill and Fill (2" Scarification, 3" Overlay) Alternative 2B						
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL	
1	2" SCARIFICATION	SY	62,400	\$ 2.00	\$ 124,800.00	
2	4" HMA RESURFACING (24' x 2")	TON	10,200	\$ 32.00	\$ 326,400.00	
3	ASPHALT BINDER	TON	610	\$ 450.00	\$ 274,500.00	
4	CENTERLINE RUMBLE STRIPS, HMA	STA	300	\$ 12.00	\$ 3,600.00	
5	LONGITUDINAL SUBDRAINS	LF	23400	\$ 10.00	\$ 234,000.00	
6	PAINTED PAVEMENT MARKINGS	STA	800	\$ 11.00	\$ 8,800.00	
7	TRAFFIC CONTROL	LS	1		\$ 69,300.00	
8	MOBILIZATION	LS	1		\$ 50,000.00	
				SUBTOTAL	\$ 1,091,400.00	
	Contingency			5%	\$ 54,600.00	
				TOTAL	\$ 1,146,000.00	
2" CIP & 4" HMA OVERLAY (Alternative 1B)						
ITEM#	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL	
1	CIPR ASPHALT PAVEMENT, 2"	SY	62,400	\$ 1.60	\$ 99,840.00	
2	ASPHALT STABILIZING AGENT (F.A.)	TON	140	\$ 450.00	\$ 63,000.00	
3	HMA RESURFACING (24' x 2" THICK)	TON	6,800	\$ 32.00	\$ 217,600.00	
4	ASPHALT BINDER	TON	410	\$ 450.00	\$ 184,500.00	
5	LONGITUDINAL SUBDRAINS	LF	23,400	\$ 10.00	\$ 234,000.00	
6	PAINTED PAVEMENT MARKINGS	STA	300	\$ 11.00	\$ 3,300.00	
7	CENTERLINE RUMBLE STRIPS, HMA	STA	100	\$ 12.00	\$ 1,200.00	
8	TRAFFIC CONTROL (Flaggers/Pilot Cars)	LS	1		\$ 248,000.00	
9	MOBILIZATION	LS	1		\$ 50,000.00	
				SUBTOTAL	\$ 1,350,680.00	
	Contingency			5%	\$ 67,600.00	
				TOTAL	\$ 1,418,280.00	

W. A. Sorenson	E. C. Wright	M. E. Ross
A. A. Welch	J. Harris	C. C. Poole
B. Hofer	J. Vortherms	G. Cagle
S. J. Gent	S. Anderson	D. Stokes
K. K. Patel	S. Godbold	S. Seivert
D. R. Claman	S. Neubauer	M. Buttz
C. Brakke	T. Hanson	F. Todey
S. McElmeel	J. R. Webb	B. Beavers
B. Lauderman	J. R. Phillips	J. Garton
J. Woodcock	B. M. Clancy	B. Porter
H. Torres-Cacho	D. E. Sprengeler	J. Schmitt
L. Finnarty		

RECOMMENDATIONS:

Options 2a and 2b are recommended at a cost of \$1,662,600.

FUNDS PROGRAMMED:

This project will be funded with FY 2023 3R funds.

Development Schedule:

Development schedule will be completed by District 5 after final concept.

Cc:

M. J. Dillavou	C. Purcell	M. J. Kennerly
K. D. Nicholson	S. J. Megivern	J. S. Nelson
M. Nop	M. A. Swenson	R. A. Younie
S. Majors	A. Poole	K. Brink
D. L. Newell	B. Bradley	J. W. Laaser-Webb



PMIS Section Report

PMIS Key: 09231119 45120 8591

National Highway System: Y County: 91 Begin Milepost: 119.45 Direction: 1
 Tested Section: Route: 92 End Milepost: 120.85 PMIS Year: 2018
 Section Description: From 0.5 Mi E Of JCT IA 92/I-35 East To WCL Martensdale

Location: Construction: Surface:
 District: Constructed: 1932 Type:
 Total Lanes: 2 Resurfaced: 1992 Multi Surface: N
 Median: N Surface Treatment: / AC Width (ft): 24
 Urban Area Code: Pavement Type: 3 Thickness (in): 13
 City Number: 0 Speed Limit: 55 Widened Drive Lane:

Shoulders and Curb (Left/Right): Planning: Subdrains:
 Type: PG / PG Planning Class: 3 Project Number: HES-92-5(27)--2H-91
 Width (ft): 4 / 4 Special Section: Percentage: 100
 Thickness (in): / PCI: Multiple Subdrain
 Tied: N / N Program Year:
 Curb and Gutter: N / N Program Comments:
 Curb: PIN:
 Dropoff

Field Survey: Relative Indexes: Road Rater:
 Structural Number: IRI: Average Struct Rating: 3.59
 IRI: 143. / Crack and Patch: Average K Rating: 140
 Friction: 02 / RDR: Thickness (in): 13
 FWD Test Date: RPI: 80% Structural Rating: 3.04
 Road Rater Test Date: Coverage (%) 100 Ave Struct Rating At Joints:
 Relative Strength Ratio:

Crack and Patch:			High	Medium	Low
Default:	Rut Depth: 0.24	LCrack	281	2,649	4,206
Provider:	Faulting: /	LCr WP	9	1,575	6,549
Test Date: 6/7/2017 12:00:00 AM	PatchA (Bad): 0	TCrack	3	101	896
	PatchA (Good): 0	AlligC	0	43	301
	Patches: 0	DCrack	0	0	
		Jspall	0	0	

Construction:

Year	Project Number	Type	Surface (in)	Base (in)	SubBase (in)
1	1992 FN-92-5(31)--21-91		AAC	3	
2	1983 FN-92-5(20)--21-91		BSC		
3	1956 P-1023(2)		AAC	2	AAC 2
4	1932 FA-365		PC7	7	
5					
6					
7					
8					

Agg Source	Agg Type	Class	Removal (in)	Remarks
1	UNIVERSITY	GRAVEL	MIL	1
2				
3	GENDLER	C.LST.		
4	WINTERSET	GRAVEL	1	
5				
6				
7				
8				

Asphalt Age Rating: Agg Rating:

Maintenance: Traffic Count: ESALS:
 Service Level: C Year: 2018 Predicted Lifetime:
 Maintenance District: 5 AADT: 4,400 Annual:
 Area: 6 Trucks: 416 Accum Since Resurf:
 Garage: Percent Trucks: 9 Accum Since Constr:
 Fed Func Class: 3 Percent Life Used:
 Concurrent Routes: /

Kmpoints: Coordinates: Longitude / Latitude:
 Base Rec Begin: Begin X: Begin LONG:
 Base Rec End: End X: End LONG:
 Trav Way Begin: Begin Y: Begin LAT:
 Trav Way End: End Y: End LAT:
 BR Route:
 Length:

Base Records:
 Begin Sequence: 2018
 End Sequence: 4400



PMIS Section Report

PMIS Key: 09231120 85121 4691

National Highway System: Y County: 91 Begin Milepost: 120 85 Direction: 1
 Tested Section: Route: 92 End Milepost: 121 46 PMIS Year: 2018
 Section Description: From WCL Martensdale east to 0.22mi E of INT IA 28

Location: Construction: Surface:
 District: Constructed: 2017 Type:
 Total Lanes: 2 Resurfaced: Multi Surface:
 Median: N Surface Treatment: / PC Width (ft): 31
 Urban Area Code: Pavement Type: 1 Thickness (in): 9.5
 City Number: 4805 Speed Limit: 45 Widened Drive Lane:

Shoulders and Curb (Left/Right): Planning: Subdrains:
 Type: G / G Planning Class: 3 Project Number:
 Width (ft): 9 / 9 Special Section: Percentage:
 Thickness (in): / PCI: Multiple Subdrain
 Tied: N / N Program Year:
 Curb and Gutter: N / N Program Comments:
 Curb: PIN:
 Dropoff

Field Survey: Relative Indexes: Road Rater:
 Structural Number: IRI: Average Struct Rating:
 IRI: 101. / Crack and Patch: Average K Rating:
 Friction: 14 / RDR: Thickness (in): 9.5
 FWD Test Date: RPI: 80% Structural Rating:
 Road Rater Test Date: Coverage (%) 0 Ave Struct Rating At Joints:
 Relative Strength Ratio:

Crack and Patch:
 Default: Rut Depth: 0 LCrack 0 0 0
 Provider: Faulting: 0 / LCr WP 0 0 0
 Test Date: PatchA (Bad): 0 TCrack 0 0 0
 PatchA (Good): 0 AlligC 0 0 0
 Patches: 0 DCrack 0 0
 Jspall 0 0

Construction:

Year	Project Number	Type	Surface (in)	Base (in)	SubBase (in)
1	2017 NHSN-092-5(56)--2R-91	O	PCC 10	SBF	12
2					
3					
4					
5					
6					
7					
8					

Agg Source	Agg Type	Class	Removal (in)	Remarks
1				
2				
3				
4				
5				
6				
7				
8				

Asphalt Age Rating: Agg Rating:

Maintenance: Traffic Count: ESALS:
 Service Level: C Year: 2018 Predicted Lifetime:
 Maintenance District: 5 AADT: 3,865 Annual:
 Area: Trucks: 351 Accum Since Resurf:
 Garage: Percent Trucks:9 Accum Since Constr:
 Fed Func Class: 3 Percent Life Used:
 Concurrent Routes: /

Kmpoints: Coordinates: Longitude / Latitude:
 Base Rec Begin: Begin X: Begin LONG:
 Base Rec End: End X: End LONG:
 Trav Way Begin: Begin Y: Begin LAT:
 Trav Way End: End Y: End LAT:
 BR Route:
 Length:

Base Records:
 Begin Sequence: 2018
 End Sequence: 3865



PMIS Section Report

PMIS Key: 09231120 85125 9791

National Highway System: Y County: 91 Begin Milepost: 120 85 Direction: 1
 Tested Section: Route: 92 End Milepost: 125 97 PMIS Year: 2018
 Section Description: From 0.22mi E of INT IA 28 East To WCL Indianola

Location: Construction: Surface:
 District: Constructed: 1930 Type:
 Total Lanes: 2 Resurfaced: 1992 Multi Surface: Y
 Median: N Surface Treatment: / AC Width (ft): 24
 Urban Area Code: Pavement Type: 3 Thickness (in): 13
 City Number: 0 Speed Limit: 55 Widened Drive Lane:

Shoulders and Curb (Left/Right): Planning: Subdrains:
 Type: PG / PG Planning Class: 3 Project Number: HES-92-5(27)--2H-91
 Width (ft): 4 / 4 Special Section: Percentage: 28
 Thickness (in): / PCI: Multiple Subdrain
 Tied: N / N Program Year:
 Curb and Gutter: N / N Program Comments:
 Curb: PIN:
 Dropoff

Field Survey: Relative Indexes: Road Rater:
 Structural Number: IRI: Average Struct Rating: 4
 IRI: 161. / Crack and Patch: Average K Rating: 198
 Friction: 93 / RDR: Thickness (in): 13
 43 / RPI: 80% Structural Rating: 3.31
 FWD Test Date: Coverage (%) 100 Ave Struct Rating At Joints:
 Road Rater Test Date: Relative Strength Ratio:

Crack and Patch:
 Default: Rut Depth: 0.27 LCrack 366 2,195 2,601
 Provider: Faulting: 0.3 / LCr WP 58 2,363 4,744
 Test Date: 6/7/2017 12:00:00 AM PatchA (Bad): 338 TCrack 11 193 774
 PatchA (Good): 0 AlligC 5 103 93
 Patches: 5 DCrack 0 0
 Jspall 6 1

Construction:

Year	Project Number	Type	Surface (in)	Base (in)	SubBase (in)
1	1992 FN-92-5(31)--21-91		AAC	3	
2	1983 FN-92-5(20)--21-91		BSC		
3	1952 P-1023W		BAC	2	TBB 2
4	1930 P-569		PC7	7	
5					
6					
7					
8					

Agg Source	Agg Type	Class	Removal (in)	Remarks
1	UNIVERSITY	GRAVEL	MIL 1	
2				
3				
4	EARLHAM	GRAVEL	1	
5				
6				
7				
8				

Asphalt Age Rating: Agg Rating:

Maintenance: Traffic Count: ESALS:
 Service Level: C Year: 2018 Predicted Lifetime:
 Maintenance District: 5 AADT: 3,625 Annual:
 Area: 6 Trucks: 353 Accum Since Resurf:
 Garage: Percent Trucks: 10 Accum Since Constr:
 Fed Func Class: 3 Percent Life Used:
 Concurrent Routes: /

Kmpoints: Coordinates: Longitude / Latitude:
 Base Rec Begin: Begin X: Begin LONG:
 Base Rec End: End X: End LONG:
 Trav Way Begin: Begin Y: Begin LAT:
 Trav Way End: End Y: End LAT:
 BR Route:
 Length:

Base Records:
 Begin Sequence: 2018
 End Sequence: 3625



PMIS Section Report

PMIS Key: 09231125 97129 9291

National Highway System: Y County: 91 Begin Milepost: 125 97 Direction: 1
 Tested Section: Route: 92 End Milepost: 129 92 PMIS Year: 2018
 Section Description: From WCL Martensdale East To WCL Indianola

Location: Construction: Surface:
 District: Constructed: 2015 Type:
 Total Lanes: 2 Resurfaced: Multi Surface: Y
 Median: N Surface Treatment: / AC Width (ft): 26
 Urban Area Code: 821 Pavement Type: 1 Thickness (in): 10
 City Number: 3680 Speed Limit: 55 Widened Drive Lane:
 Shoulders and Curb (Left/Right): Planning: Subdrains:
 Type: G / G Planning Class: 3 Project Number: HES-92-5(27)--2H-91
 Width (ft): 4 / 4 Special Section: Percentage: 28
 Thickness (in): / PCI: Multiple Subdrain
 Tied: N / N Program Year:
 Curb and Gutter: Y / Y Program Comments:
 Curb: PIN:
 Dropoff

Field Survey: Relative Indexes: Road Rater:
 Structural Number: IRI: Average Struct Rating: 5.68
 IRI: 85.59 / Crack and Patch: Average K Rating: 130
 Friction: 42 / RDR: Thickness (in): 10
 FWD Test Date: RPI: 80% Structural Rating: 4.5
 Road Rater Test Date: Coverage (%) 100 Ave Struct Rating At Joints:
 Relative Strength Ratio:

Crack and Patch:		High	Medium	Low	
Default:	Rut Depth: 0.18	LCrack	3	19	53
Provider:	Faulting: 0 /	LCr WP	0	0	5
Test Date: 6/7/2017 12:00:00 AM	PatchA (Bad): 0	TCrack	2	1	12
	PatchA (Good): 128	AlligC	0	40	0
	Patches: 2	DCrack	0	0	
		Jspall	0	0	

Construction:

Year	Project Number	Type	Surface (in)	Base (in)	SubBase (in)
1	2015 NHSX-092-5(51)--3H-91		PCC 10	GSB 6	SBF 6
2					
3					
4					
5					
6					
7					
8					

Agg Source	Agg Type	Class	Removal (in)	Remarks
1				
2				
3				
4				
5				
6				
7				
8				

Asphalt Age Rating: Agg Rating:

Maintenance: Traffic Count: ESALS:
 Service Level: C Year: 2018 Predicted Lifetime:
 Maintenance District: 5 AADT: 7,110 Annual:
 Area: 6 Trucks: 410 Accum Since Resurf:
 Garage: Percent Trucks:6 Accum Since Constr:
 Fed Func Class: 3 Percent Life Used:
 Concurrent Routes: /

Kmpoints: Coordinates: Longitude / Latitude:
 Base Rec Begin: Begin X: Begin LONG:
 Base Rec End: End X: End LONG:
 Trav Way Begin: Begin Y: Begin LAT:
 Trav Way End: End Y: End LAT:
 BR Route:
 Length:

Base Records:
 Begin Sequence: 2018
 End Sequence: 7110

Roadway	IA 92		
PIN Number	22-91-092-010	Submittal Date	03/24/22
Project Number	NHSX-092-5(70)--3H-91		Approval Date
District	District 5	Assistant District Engineer	Steven McElmeel
County	Warren	or	
Route	IA 92	Office Director	
Location	0.3 mi E of I-35 to Kennedy St		
Work Type	HMA RESURFACING WITH MILLING		
Segment Manager	Jason Holst		
Designer	Jonathan Bahr		

[Design Manual Section 1C-1](#)
Last Updated: 04-29-19

Rural Two-Lane Highways (Rural Arterials)

Design Element	Preferred	Acceptable	Project Values
Design speed (mph)	60	50	60
Maximum superelevation rate (Refer to Section 2A-2)	6%	8%	6% & 8% (note 1)
Design lane width (ft)	12	12	12
Full depth paved width (ft)	12	12	12
Right turn lane (ft)	12	10	n/a
Climbing Lane (ft)	12	12	n/a
Left turn lane (ft)	12	10	n/a
Pavement cross-slope (on tangent sections)	Through lanes	1.5% minimum, 2% maximum	2%
	Auxiliary and turn lanes	3% maximum	n/a
	Crown break at centerline	4% maximum	4%
Shoulder cross-slope (on tangent sections)	4%	Shoulder cross-slope cannot be less than the adjacent lane, 6% max for paved or granular shoulders, 8% max for earth shoulders	4%
Curb type (Refer to Section 3C-2)	Design speed = 50 or 55 mph	6-inch sloped	6-inch standard
	Design speed ≥ 60 mph	4-inch sloped	6-inch sloped
Foreslope (For fill areas greater than 40 ft, contact the Soils Design Section for assistance)	Adjacent to shoulder	10:1 for 4' then 6:1	3:1 (note 3)
	Beyond standard ditch depth and design clear zone	3.5:1	3:1
	Curbed roadways	2%	not steeper than 3:1
Backslope (For cut areas greater than 25 feet, contact the Soils Design Section for assistance with backslope benches.)	3:1	2.5:1	1.5:1 (note 4)
Transverse Slopes	w/ drainage structures	8:1	6:1 (note 5)
	w/o drainage structures	10:1	6:1 (note 5)
Ditches (Refer to Section 3G-1)	Outside ditch (depth x width) (ft)	5 x 10	--
Bridge width—new*	Bridge length ≤ 200 ft	design lane widths + effective shoulder widths	design lane widths + effective shoulder widths
	Bridge length > 200 ft	design lane widths + effective shoulder widths	design lane width + 4' right and left of the design lane widths
Bridge width—existing*		design lane widths + no less than 2 ft left and right	design lane widths + 2 ft. offset left and right
Vertical clearance (ft) (above lanes, shoulders and 25 feet left and right of the center of railroad tracks)	Over primary	16.5	16
	Over non-primary	16.5 at interchange locations, 15 at all other locations	14
	Over railroad	23.3	23.3
	Sign trusses and pedestrian bridges	17.5	17
Structural Capacity	Contact Office of Bridges and Structures	Contact Office of Bridges and Structures	n/a
Level of Service	B	B	C

*FHWA notification via email is required if acceptable criteria is not met on the NHS system (No formal design exception is required)

Note 1: Record Drawings (1932) indicate IA 92 was constructed with a maximum superelevation rate of 8% west of IA 28. Resurfaced roadway shall match existing superelevation rate.
Record Drawings (2017) indicate IA 92 was constructed with a maximum superelevation rate of 6% at the intersection of IA 28 and IA 92. Resurfaced roadway shall match existing superelevation rate.
Record Drawings (1931) indicate IA 92 was constructed with a maximum superelevation rate of 8% east of the intersection of IA 28 and IA 92. Resurfaced roadway shall match existing superelevation rate.

Note 2: Existing Curb is located at 11 locations through the project corridor per 2017 As-Builts. The curb was installed to mitigate erosion along hilltops.

Note 3: Record Drawings (1932) indicate IA 92 was constructed with a foreslope of 3:1.

Note 4: Record Drawings (1932) indicate IA 92 was constructed with a backslope of 1.5:1.

Note 5: 1991 Record Drawings indicate the 8:1 Transverse Slopes were installed at Culvert Extensions. Transverse Slopes will not be impacted by this project.

Note 6: 1932 Record Drawings indicate 2' minimum depth and 2' minimum width of existing ditches. Ditches will not be impacted by this project unless there is 'reshaping' to bring them to their original condition.

Design year ADT = See Note 7.

Effective Shoulder Width and Type for Two-Lane Highways

	Preferred (values shown in feet)		Acceptable (values shown in feet)		Project Values	
	Rural Roadways	Urban Roadways	Rural Roadways	Urban Roadways		
Turn lanes with shoulders	6	6	Turn lanes with shoulders	6	0	n/a
Turn lanes with curbs	6	See Section 3C-2	Turn lanes with curbs	6	0	n/a
	Effective Shoulder Width	Paved Width		Effective Shoulder Width	Paved Width	
Climbing Lanes	6	4	Climbing Lanes	4	0	n/a
Two-Lane Highways	Effective Shoulder Width	Paved Width	Two-Lane Highways	Effective Shoulder Width	Paved Width	
Routes where bicycles are to be accommodated	10	10	Design year ADT > 2000 vpd	8	0*	4' paved, 4' granular (note 7)
On roadways approaching urban areas (due to increased bike traffic)	10	10				
On all curves with a superelevation rate of 7.0% or greater	10	10	Design year ADT between 400 - 2000 vpd	6	0*	
On roadways with design year ADT > 5000	10	6				
On all other NHS	10	6	Design year ADT < 400 vpd	4	0*	
On non-NHS routes with design year ADT > 3000	10	6				
On non-NHS routes with design year ADT < 3000	8	0*				

*Requires safety edge-Refer to Section 3C-6

Curbs should be located beyond the outer edge of the effective shoulder width in rural areas

Refer to Section 3C-2 for curb offsets in urban areas

Notes:

Note 7: 4' Paved + 4' Granular shoulders were installed in 2014.

IA 92 is a NHS route and has a 2043 Design Year ADT of 5,021 VPD.

D2 Questions for District 5 – with Responses in GREEN Text:

Date 4/13/2022

Times: 8:30am to 10:00am at Maintenance Garage. 3:00pm to 4:15pm within Project Limits.

Description: D2 Field Exam

Location: Iowa DOT Martensdale Maintenance Garage (West of IA 92/IA 28 Intersection) and Project Limits

Attendees:

Jonathan Bahr (Ames Road Design)

William McNamara (Ames Road Design)

Kari Jackson (Ames Road Design)

Steven McElmeel (District 5 Assistant District Engineer)

Jim Phillips (District 5 Design Staff)

Jared Klein (District 5 Design Staff)

Liz Finarty (District 5 RCE)

Todd Netley (Martensdale Highway Maintenance Supervisor)

Nicholas Koeppe (Martensdale Garage Operations Assistant)

1. PROJECT LIMITS

- a. Beginning of Project is at a HMA transition joint 0.37 miles east of the midpoint of the IA 92 bridge over I-35. Please verify.
 - i. 2022-04-13 Field Exam Response: CONFIRMED. Beginning of Project location shall be located at a HMA transition joint 0.37 miles east of the midpoint of the IA 92 bridge over I-35.
- b. End of Project is at a transition from HMA to PCC, 0.40 miles west of the intersection of IA 92 and Kennedy Street. Please verify.
 - i. 2022-04-13 Field Exam Response: CONFIRMED. End of Project location shall be located at a transition from HMA to PCC, 0.40 miles west of the intersection of IA 92 and Kennedy Street.
- c. Review Milling and Resurfacing "STOP" and "RESUME" locations around the intersection of IA 92 and IA 28.
 - i. 2022-04-13 Field Exam Response: "STOP" and "RESUME" locations CONFIRMED.
 1. "STOP" location is at a HMA/PCC Transition location at the entrance to the Iowa DOT's Martensdale Maintenance Garage (located west of the intersection of IA 92 and IA 28, MP 120.98, STA 131+30).
 2. "RESUME" location is at the PCC/HMA transition location on the east end of the east 70' long PCC Approach of Bridge FHWA 51111 (MP 121.55, STA 23+38).

2. TYPE OF WORK

- a. The Type of Work Description in PSS is "HMA Resurfacing/Cold-in-Place Recycling". However, the Project Concept did not select the CIR option as the Recommended Treatment. Please confirm that the Type of Work should be revised to "HMA Resurfacing with Milling".
 - i. 2022-04-13 Field Exam Response: Ames Road Design will contact Contracts and suggest revising the "Type of Work" to "HMA Resurfacing with Milling".

3. ROADWAY RESURFACING TREATMENT WEST OF THE INTERSECTION OF IA 92 AND IA 28

- a. Page 2 of the Project Concept section for "West of IA 28 Cost" for Alternative 2A has the DESCRIPTION "HMA Mill and Fill (2" Scarification, 4" Overlay)" and has the following for ITEM #2: 4" HMA RESURFACING (24' x 2"). Page 4 of the Project Concept indicates the following: "The pavement design section is recommending a 4" overlay from 119.45 to 120.85 (West of IA 28) and from 121.46 to 125.94 (East of IA 28) is recommending 2.5". dTims is recommending CIR for both sections." Page 5 of the Project Concept goes on to indicate that "This project will be 24' wide lanes with a 4' wide paved and 4' granular shoulder. The 4' paved shoulder will be UAC'd." Please verify the pavement composition. Here are a couple of options:
 - i. KEEP DESCRIPTION and ITEM #1 as 2" SCARIFICATION and REVISE ITEM #2 to 4" HMA RESURFACING (24'x2" Intermediate Course AND 32'x2" Surface Course). This option assumes the 2" scarification is only over the 24' wide Traveled Way. Since the 24' wide Roadway Profile is being raised 2", then the existing 4' paved shoulders will need to be overlaid with the 2" Surface Course, hence the 32' wide x 2" Surface Course.
 - ii. KEEP DESCRIPTION and ITEM #1 as 2" SCARIFICATION and REVISE ITEM #2 to 4" HMA RESURFACING (32'x1.5" Intermediate Course AND 32'x1.5" Surface Course). This is assuming the 2" scarification is projected over the entire 32' wide Roadway (24' Traveled Way and 4' Paved Shoulders). This option maintains a 1.5" Intermediate Course and 1.5" HMA Surface Course.
 - iii. 2022-04-13 Field Exam Response: The resurfacing treatment to the west of the intersection of IA 92 and IA 28 shall be revised to the following: 32'x1.5" Pavement Scarification + 32'x1.5" HMA Intermediate Course + 32'x2" HMA Surface Course. District Staff confirmed the use of HMA Intermediate Course as opposed to Interlayer.
 1. The additional width of the scarifying operation and the HMA courses over the entire length of the project will increase the cost of this project (an estimated increase of \$360,000 was calculated during the meeting using unit costs from the Concept Estimate). To reduce the increase in cost the scarification depth was reduced from 2" to 1.5" and the total resurfacing thickness was reduced from 4" to 3.5". Also, reducing the amount of scarification by a 0.5" helps to counteract the impact to the overall Structural Number that would be brought about by reducing the total resurfacing thickness.
 2. FYI; Scarifying the 24' Traveled Way and not scarifying the Paved Shoulders would result in a 'bathtub' effect in the traveled way (the Shoulder pavement elevation would be higher than the scarified surface of the Traveled Way and would prevent runoff from escaping the Traveled Way). One way to mitigate the bathtub effect would be to mill channels/troughs at strategic locations (every couple hundred feet and at low points) in the shoulder to allow runoff from the Traveled Way to escape the roadway. This mitigation option does not work well on relatively flat stretches of road (like IA 92 west of the intersection of IA 92 and IA 28).

4. ROADWAY RESURFACING TREATMENT EAST OF THE INTERSECTION OF IA 92 AND IA 28

- a. Page 3 of the Project Concept section for "East of IA 28 Cost" for Alternative 2B has the DESCRIPTION "HMA Mill and Fill (2" Scarification, 3" Overlay)", but has ITEM #2 as the following 4" HMA RESURFACING (24' x 2"). Page 4 of the Project Concept indicates the following: "The pavement design section is recommending a 4" overlay from 119.45 to 120.85 (West of IA 28) and from 121.46 to 125.94 (East of IA 28) is recommending 2.5". dTims is recommending CIR for both sections." Page 5 of the Project Concept goes on to indicate that "This project will be 24' wide lanes with a 4' wide paved and 4' granular shoulder. The 4' paved shoulder will be UAC'd." Please verify the pavement composition. Here are a couple of options:
- KEEP DESCRIPTION and ITEM #1 as 2" SCARIFICATION and REVISE ITEM #2 to 3" HMA RESURFACING (24'x2" Intermediate Course AND 32'x1" Surface Course). This option assumes the 2" scarification is only over the 24' wide Traveled Way. Since the 24' wide Roadway Profile is being raised 1", then the existing 4' paved shoulders will need to be overlaid with the 1" Surface Course, hence the 32' wide x 1" Surface Course. A 1" Surface Course may be considered too thin.
 - REVISE DESCRIPTION and ITEM #1 to indicate 3" SCARIFICATION and REVISE ITEM #2 to 3" HMA RESURFACING (24'x1.5" Intermediate Course AND 24'x1.5" Surface Course). This will allow for the UAC of the existing paved shoulders since the roadway profile would not be raised. This option maintains a 1.5" Intermediate Course and 1.5" HMA Surface Course.
 - KEEP DESCRIPTION and ITEM #1 as 2" SCARIFICATION and REVISE ITEM #2 to 3" HMA RESURFACING (32'x1.5" Intermediate Course AND 32'x1.5" Surface Course). This is assuming the 2" scarification is projected over the entire 32' wide Roadway (24' Traveled Way and 4' Paved Shoulders). This option maintains a 1.5" Intermediate Course and 1.5" HMA Surface Course.
 - 2022-04-13 Field Exam Response: The general resurfacing treatment to the east of the intersection of IA 92 and IA 28 shall be revised to the following: 32'x1.5" Pavement Scarification + 32'x1.5" HMA Intermediate Course + 32'x1.5" HMA Surface Course. See GUARDRAIL section below for Typical Section exception at FHWA 51111. See ROADWAY RESURFACING TREATMENT WEST OF THE INTERSECTION OF IA 92 AND IA 28 section above for additional discussion.

5. GRANULAR SHOULDER

- a. The Concept Estimates on Pages 2 and 3 of the Project Concept did not indicate the placement of Granular Shoulder Material on this project. Shall we assume that Granular Shoulder will need to be placed on this project? This question is parallel with the 'ROADWAY RESURFACING TREATMENT' Sections above.
- 2022-04-13 Field Exam Response: Add Granular Shoulder Material on this project. The addition of Granular Shoulder Material will increase the estimated cost of the project. FYI, the Concept Estimate included a 5% contingency for the overall project.
- b. Shall we assume Granular Shoulder is 1" below existing edge of pavement due to washout?
- 2022-04-13 Field Exam Response: Add 1" of Granular Shoulder Material to account for washout of the existing granular shoulder.

6. SHOULDER AND CENTERLINE RUMBLES

- a. The Concept Estimates on Pages 2 and 3 of the Project Concept only indicate the installation of 'CENTERLINE RUMBLE STRIPS, HMA'. Please confirm that Shoulder Rumble Strips should also be utilized on this project. FYI, there are existing shoulder rumble strips along IA 92. This question is parallel with the 'ROADWAY RESURFACING TREATMENT' Sections above (Road Design Team assumes that if the existing 4' wide paved shoulders are overlaid then the new shoulder rumble strips would need to be installed).
- 2022-04-13 Field Exam Response: Add Shoulder Rumble Strips to the project. Also, confirmed the use of Shoulder Rumble Strips as opposed to Shoulder Rumble Stripes.
- b. Should the centerline rumbles (and shoulder rumbles if applicable) be skipped in the relatively residential area just west of the west end of the project (MP 126, west of Kennedy Street)? FYI, there are existing shoulder rumble strips along IA 92 in this area.
- 2022-04-13 Field Exam Response: Maintain Centerline Rumbles and Shoulder Rumbles through the Project Limits. There are relatively new existing rumbles in the more developed area east of Kennedy Street.

7. LONGITUDINAL SUBDRAINS

- a. Page 5 of the Project Concept indicates that the proposed improvement includes 50% placement of additional subdrains on the westbound lane (existing coverage is 50% on the eastbound lane). Please confirm that the District would like to install the additional 50% of subdrain on the westbound lane.
- 2022-04-13 Field Exam Response: Remove longitudinal subdrain from the scope of the project. The existing longitudinal subdrain was installed adjacent to the Traveled Way pavement when the roadway was widened, however the existing pavement would need to be trenched and replaced to install new subdrain for this project; which dramatically increases the cost of installation of new longitudinal subdrain. Installing new longitudinal subdrain outside of the existing shoulders would not provide the function intended if the Traveled Way Pavement is a different thickness than the Shoulder Pavement. The intended function would be to drain the subgrade at the joint where the Traveled Way and Shoulder Pavement meet. Removing the longitudinal subdrain is a cost savings of \$308,000 per the Concept Estimate.

8. STRUCTURES

- a. FHWA 51111, Maint. 9121.7S092 (261'X40' Prestressed Concrete Beam Bridge, STA 21+28, MP 121.52). Page 7 of the Project Concept indicates this Bridge is in good shape. Review traveled way and shoulder paving limits during Field Meeting. This bridge is east of the intersection of IA 92 and IA 28. See "ROADWAY RESURFACING TREATMENT" section above and the "GUARDRAIL" section below.
- b. FHWA 51120, Maint. 9123.2S092 (21'X97' Concrete Box Culvert, STA 106+97, MP 123.12). Page 7 of the Project Concept indicates this Culvert is in good shape. There don't appear to be any traveled way and shoulder paving limits that need to be reviewed during the Field Meeting.
 - i. 2022-04-13 Field Exam Response: There are no issues with maintaining the Roadway Typical Section over the FHWA 51120 Concrete Box Culvert. District Staff reviewed the culvert during the site visit and determined that District Maintenance staff shall grout culvert joints (the grouting of the culvert joints will NOT be associated with the 3R Project).

9. GUARDRAIL

- a. Page 7 of the Project Concept indicates "Paved shoulders were installed in 2017. Updated guardrail was installed at that time. Will want to review to make sure guardrail is meeting current standards." All the guardrail within this project corridor is located at the four quadrants of FHWA 51111 (Maint. 9121.7S092, 261'X40' Prestressed Concrete Beam Bridge, STA 21+28, MP 121.52). The two guardrails attached to the west end of the bridge are within a gapped area of the resurfacing for this project. The two guardrails attached to the east of may be impacted by a rise in roadway profile elevation (See "ROADWAY RESURFACING TREATMENT" section above and "STRUCTURES" section above). Has this location been reviewed?
 - i. 2022-04-13 Field Exam Response: The existing guardrail at all four quadrants of FHWA 51111 are up to current standards. The resurfacing treatment at the PCC/HMA transition location on the east end of the east 70' long PCC Approach of Bridge FHWA 51111 (MP 121.55, STA 23+38) shall be: 32'x1.5" Pavement Scarification + 32'x1.5" HMA Surface Course to eliminate the net profile change. The HMA Intermediate Course will be tapered out from the General Typical Section (See "ROADWAY RESURFACING TREATMENT EAST OF THE INTERSECTION OF IA 92 AND IA 28" section above). A Runout Detail will be added to the plans.

10. CULVERTS/PIPES

- a. Page 7 of the Project Concept indicates "BSB is requested to review the structure at Station 65 (MM 119.7) based on recent review by the Martensdale garage staff." Has this location been reviewed? What is the scope and responsibilities? Are there any potential ROW/Easements/Environmental Impact needs associated with this potential work?
 - i. 2022-04-13 Field Exam Response: Culvert is located at STA 66+51 (MP 119.74). The location was reviewed during the site visit. There is limited space for erosion mitigation. Jim Phillips (District 5) gathered dimensions and will add them to Field Tabulations.
 1. Rip Rap/Erosion Stone will be added to the outlet (south) side of the culvert.
 2. Revetment will be added to armor the curve in the bank on the outlet (south) side of the culvert.
 3. Erosion mitigation (possibly Rip Rap / Erosion Stone) may be added to the inlet (north) side of the culvert.

11. ADA/SIDEWALK/TRAILS

- a. Page 6 of the Project Concept states "Complete streets analysis." Has this analysis been performed?
 - i. 2022-04-13 Field Exam Response: Jim Phillips (District 5) shall contact Milly Ortiz-Pagan (Office of Systems Planning) to confirm needs for "Complete Streets Analysis". There are 10' paved shoulders east of Kennedy Street, but the D2 Discussion Group does not believe there is available ROW or shoulder space for this corridor to include 10' wide paved shoulders for a Bicycle Path. Such an addition would be an exponential increase to the cost of the project.
 - ii. 2022-04-19 Follow-Up Correspondence: Milly Ortiz-Pagan (Office of Systems Planning) confirmed in an e-mail reply to Jim Phillips (District 5) that "The cost of additional paved shoulder width would be excessively disproportionate to the need or probable use per Section 2.4 of the Complete Streets Policy." There will be no change in the Concepted Shoulder Width.

12. INTERSECTION CRASH HISTORY AND ANALYSIS

- a. Page 7 of the Project Concept states "All the intersections within the project limits are Tier 2 locations on the PCR (potential for crash reduction) website." and "Review the need for turn lanes at County Road R45 (40th Ave/St. Mary's Road)." Has this analysis been performed?
 - i. 2022-04-13 Field Exam Response: County Road R45/40th Ave/St. Mary's Road (MP 121.75) is a Tier 3 intersection according to the current PCR website. District shall look at Turn Volumes, but there probably is not enough Volume plus Crashes to warrant Turn Lanes. If a Turn Lane was added, then it would probably be a Right Turn Lane for Eastbound IA 92 approaching County Road R45 (ROW would be required for construction of this Right Turn Lane).

13. ADDITIONAL SAFETY & OPERATION CONSIDERATION

- a. Page 7 of the Project Concept states “Identify impacts to District Road Safety Plan, 4-to-3 lane conversion, rumble strips, safety dikes, Super 2 Highway, freight bottle neck, etc.” Has this analysis been performed?
 - i. 2022-04-13 Field Exam Response: No additional analysis is required. FYI, the District Road Safety Plan is becoming outdated and is being replaced with up-to-date Safety Analysis via the Potential for Crash Reduction (PCR) Website (see the INTERSECTION CRASH HISTORY AND ANALYSIS section above).
 - 1. IA 92 is not a Super 2 Highway. There aren’t any candidate locations for Safety Dikes at Tee Intersections. A 4-to-3 lane conversion is not applicable. Rumble Stripes are being installed.

14. EXISTING DRAINAGE PROBLEMS

- a. Are there existing drainage problems within towns or in rural areas that may need to be mitigated (shoulder washout, standing water, etc.)?
- b. Page 6 of the Project Concept states “During the field review, maintenance asked to review current curbed sections for possible extensions to help with erosion issues. There is specifically an issue at the addresses of 7600-7602 IA 92 on the south side that when it rains, water doesn’t drain to the entrance pipe but goes over the driveway. Looks like an area for a possible shoulder fillet. A patch tab will need to be put together by the Chariton RCE office.” Review this location during the Field Meeting.
 - i. 2022-04-13 Field Exam Response: Reviewed the erosion issue location near the addresses of 7600-7602 IA 92 (south side, near STA 230+90, MP 125.46) during the site visit. 10’ of the existing curb will be removed (the team decided that removing the curb to an existing joint location ~20 feet from the east end of the curb was excessive). An erosion stone flume (ditch reshaping and rock ditch) shall be constructed in the area and shall be aligned to outlet to the entrance culvert for 7600-7602 IA 92. The entrance culvert for 7600-7602 IA 92 is scheduled to be removed and replaced with a new culvert.

15. STOCKPILED MATERIALS:

- a. Confirm that Maintenance would like the following Stockpiled Materials:
 - i. HMA Millings: 2022-04-13 Field Exam Response: Yes, District Maintenance would like to stockpile HMA Millings.
 - ii. Class 13 Excavation: 2022-04-13 Field Exam Response: Not Applicable; Class 13 Excavation is not included in this project.
 - iii. Steel Beam Guardrail (see “GUARDRAIL” section above): 2022-04-13 Field Exam Response: Not Applicable; Guardrail is not being removed for this project. FYI, District Maintenance rejected stockpiling of Steel Beam Guardrail for the concurrent FY 2023 IA 28 Warren County Project (STP-028-1(16)--2C-91).
 - iv. Steel Beam Guardrail Posts (see “GUARDRAIL” section above) 2022-04-13 Field Exam Response: Not Applicable; Guardrail is not being removed for this project. FYI, District Maintenance rejected stockpiling of Steel Beam Guardrail for the concurrent FY 2023 IA 28 Warren County Project (STP-028-1(16)--2C-91).
- b. Verify the location of Stockpiled Materials (Primary Location? Secondary location? Is there a preferred distribution of materials across the sites)
 - i. Primary Location: 2022-04-13 Field Exam Response: District Maintenance Staff requested that all of the stockpiled HMA Millings be delivered to the Iowa DOT’s Martensdale Maintenance Garage regardless if the total amount is over the 2,500 ton cap (a quick-calc of HMA Milling tonnage yielded 3,040 tons of stockpiled material after 50% was removed for RAP. The tonnage will be recalculated as the Project progresses.). District Staff instructed the Road Design Team to include the District Note regarding the height of Stockpiled Materials in the Estimate Reference Note for Contractor Stockpiled Shoulder Material (Contractor Stockpiled Shoulder Material is the bid item associated with the Stockpiling of HMA Millings). District Maintenance indicated that the District prefers that Class A Stone be delivered instead of HMA Millings (it’s still the Contractor’s choice, per the specification). Road Design Team shall add a note to the Delivery and Stockpile tab that indicates the District Maintenance preference for Class A Stone.
 - ii. Secondary Location: 2022-04-13 Field Exam Response: There is a secondary location 5 miles south of Indianola on US 65 (near the US 65/US 69 junction for Lake Ahquabi State Park). District Staff instructed the Road Design Team NOT to include the Secondary Location in the Delivery and Stockpile Tab.
- c. Maintenance Contact Person and Phone Number: 2022-04-13 Field Exam Response: Todd Netley, 515-250-3374.

16. CONTINGENCY PERCENTAGES

- a. HMA Pavement Contingency for Irregularities: 5.0% is Typical. Confirm. 2022-04-13 Field Exam Response: Confirmed, 5% HMA contingency for irregularities.
- b. Granular Shoulder: 20% has been used on recent projects. Confirm. 2022-04-13 Field Exam Response: Confirmed, 20% Granular Shoulder contingency.
- c. Patches Contingency: 15% is Typical. Confirm. 2022-04-13 Field Exam Response: Confirmed, 15% contingency for Patches.

17. LETTING DATE

- a. Letting Date is currently scheduled for 11/15/2022. Road Design Team suggests keeping the Letting Date as 11/15/2022. The Road Design recommends revising the FY 2023 IA 28 Warren County (STP-028-1(16)--2C-91) Project's 10/18/2022 Letting Date to match the 11/15/2022 Letting Date of this FY 2023 IA 92 Warren County Project (NHSX-092-5(70)--3H-91). This IA 92 Warren County passes by the beginning of the IA 28 Warren County project. This allows for the possibility to Tie the two projects as well as to stagger other District 5 Projects the Road Design Team is working on.
 - i. 2022-04-13 Field Exam Response: District Staff confirmed moving the IA 28 Warren County (STP-028-1(16)--2C-91) Letting Date to 11/15/2022 (FY 2023 IA 92 Warren County Project (NHSX-092-5(70)--3H-91) will stay as 11/15/2022). Road Design will Contact the Contract's Bureau and request the adjustment of the Letting Date for IA 28 Warren County.
 - ii. 2022-04-13 Field Exam Response: District Staff indicated that it was OK to assume the FY 2023 IA 28 Warren County (STP-028-1(16)--2C-91) and the FY 2023 IA 92 Warren County Project (NHSX-092-5(70)--3H-91) will be Tied. The Road Design Team will confirm the Tied status of the two projects as the Design progresses.

18. SPECIAL FEATURES

- a. Are there any special features not shown on the plans (Schools or businesses with particular entrance needs, mailboxes, signage, structures, traffic signal detector loops at signalized intersections) that need to be taken into consideration, either design or Traffic Control-wise? 2022-04-13 Field Exam Response: No Special Features or Traffic Control issues were identified.

19. SPECIAL EVENTS

- a. Are there any Special Events that need to be identified? If so, what are their schedules?
 - i. 2022-04-13 Field Exam Response: No Special Events for Martensdale or Norwalk are expected to impact construction.

20. FIELD MAINTENANCE TABS

- a. Please confirm that the FIELD Tabs (Tree Clearing, patching, curb repairs, culverts, etc.) are pending collection, review, and distribution to Road Design.
 - i. 2022-04-13 Field Exam Response: The Field Maintenance Tabs are being finalized by District Staff. Field Maintenance Tabs will be forwarded to Road Design Staff once they have been completed.

21. SIDEROAD AND ENTRANCE TREATMENT

- a. Discuss Treatment of Existing Sideroads and Entrances throughout the Project Limits.
 - i. 2022-04-13 Field Exam Response: District Staff confirmed that entrance fillets for existing gravel entrances that extend beyond the paved shoulder shall be removed and replaced with shoulder stone. Sideroads will have paved fillets that go to the "Full Shoulder Design Width" (outside of combination shoulder).

22. CURB TREATMENT

- a. Discuss Treatment of Existing Curb throughout the Project Limits (see Page 5 of the Project Concept).
 - i. 2022-04-13 Field Exam Response: A Detail for Longitudinal/Tapered Milling adjacent to the lip of the gutter pan will be added to the plans to illustrate that the resurfacing will tie in to the existing elevation at the lip of the gutter pan (no HMA will be placed on the gutter pan). The tapered milling does not need to begin at the edge line of the Traveled Way (the Tapered Milling can begin closer to the lip of the gutter pan).


23. ADDITIONAL TOPICS TO BE RESOLVED AS THE PROJECT PROGRESSES

- a. Project Coordination
- b. Tied Projects
- c. Pavement Specifications
- d. Traffic Control
- e. OLE Information
- f. City and County Agreements

Combination Shoulder

3R_Shldr_C_Milling_04-19-11			
STATION TO STATION		(P) Feet	(G) Feet
49+24.05	119+60	4	4
119+60	131+19.42*	4	8

EQUATION: STA 131+19.42 (BK) = 231+35 (AH)



3R_Overlay_04-19-11				
STATION TO STATION		(C) Feet	(L) Feet	(R) Feet
49+24.05	131+19.42	24	12	12

EQUATION: STA 131+19.42 (BK) = 231+35 (AH)

Combination Shoulder

3R_Shldr_C_Milling_04-19-11			
STATION TO STATION		(P) Feet	(G) Feet
49+24.05	119+60	4	4
119+60	131+19.42*	4	8

EQUATION: STA 131+19.42 (BK) = 231+35 (AH)

- ① Finished slope shall match existing pavement except the maximum allowable slope is 3.0% and the minimum allowable slope is 2.0%. Section may be modified as directed by the Engineer through areas of special shaping.
- ② Finished slope of Shoulder shall have a minimum allowable slope of 4% and a maximum allowable slope of 6%. Section may be modified as directed by the Engineer through areas of special shaping.
- ③ UAC existing subdrain. All existing subdrain shall remain functional at all times (do not plug or crush). New subdrain shall be in contact with the granular material below the existing mainline pavement (see Tab 104-9 on CS sheets for proposed locations).
- ④ The surface of the existing granular shoulder is estimated to be 1.0" below the surface of the edge of the existing pavement.

Notes:


- 1. Stationing on typical sections does not include gapping for bridges, sideroads, or entrances. Refer to tabulations and details for precise stationing and quantities.
- 2. See Tab 100-25 for Pavement quantities.
- 3. See Tab 112-9 for Granular Shoulder quantities.

IA 92 Mainline Milling & HMA Resurfacing

(Beginning of Project to West of IA 28 in Martensdale)

Combination Shoulder

3R_Shldr_C_Milling_04-19-11			
STATION TO STATION	(P) Feet	(G) Feet	
25+65	65+55	8	0
65+55	99+70	4	4
100+95	227+00	4	4
230+90	256+49.40	4	4



3R_Overlay_04-19-11				
STATION TO STATION	(C) Feet	(L) Feet	(R) Feet	
23+74.50	253+15	24	12	12


- ① Finished slope shall match existing pavement except the maximum allowable slope is 3.0% and the minimum allowable slope is 2.0%. Section may be modified as directed by the Engineer through areas of special shaping.
- ② Finished slope of Shoulder shall have a minimum allowable slope of 4% and a maximum allowable slope of 6%. Section may be modified as directed by the Engineer through areas of special shaping.
- ③ UAC existing subdrain. All existing subdrain shall remain functional at all times (do not plug or crush). New subdrain shall be in contact with the granular material below the existing mainline pavement (see Tab 104-9 on CS sheets for proposed locations).
- ④ The surface of the existing granular shoulder is estimated to be 1.0" below the surface of the edge of the existing pavement.

Curbed Shoulder

Shoulder Jointing:
Longitudinal joint not required when distance from back of curb to nearest joint is less than 15':

Single pour: L-2
Staged : KT-2
Transverse: C at 17' spacing

2_Curb_04-21-20			
STATION TO STATION	(P) Feet	Curb Type	See PV-102
99+70	100+95	5.5	UAC
227+00	230+90	5.5	UAC



Curbed Shoulder

Shoulder Jointing:
Longitudinal joint not required when distance from back of curb to nearest joint is less than 15':

Single pour: L-2
Staged : KT-2
Transverse: C at 17' spacing

2_Curb_04-21-20			
STATION TO STATION	(P) Feet	Curb Type	See PV-102
65+30	67+30	5.5	UAC
87+60	90+15	5.5	UAC
98+25	103+90	5.5	UAC
132+60	135+50	5.5	UAC
140+35	145+45	5.5	UAC
186+00	192+50	5.5	UAC
227+00	230+90	5.5	UAC
241+70	246+20	5.5	UAC
253+15	256+49.4	5.5	UAC

Notes:


- 1. Stationing on typical sections does not include gapping for bridges, sideroads, or entrances. Refer to tabulations and details for precise stationing and quantities.
- 2. See Tab 100-25 for Pavement quantities.
- 3. See Tab 112-9 for Granular Shoulder quantities.

IA 92 Mainline Milling & HMA Resurfacing


(East of IA 28 in Martensdale to End of Project)

JEFFERSON TWP
T.76N. R.25W.

DOMINICK SAMMON &
MARY EGAN




365 7 25



Sta. 44 + 69.6
8' x 6' x 477' R.C. Box
D.A. 207 AC.
Use as constructed

Bench Marks:
3 Sta 44 + 57.3 R.R. spk in N. hdw. of 8' x 6' R.C. Box opp R.R. trestle #3870 21' Lt. --- El. 641.99




PLAN SHEETED BY DATE
PROJECTED BY DATE
NOTED BY DATE
REVISIONS BY DATE


PROFILE SHEETED BY DATE
PROJECTED BY DATE
NOTED BY DATE
REVISIONS BY DATE

This Sheet
For Information Only

JEFFERSON TWP
T.76 N. R.25 W.




PER. D.	STATE	NO.	TOTAL
365	8	25	



BENCH MARKS
#4 Sta. 66+51' on center of N. Handrail of 32' x 24' I. Beam Br. opp R.R. Trestle # 3866 - 125' Lt. El. 816.00
#5 Sta. 85+90 RR Spike, in S. Side of 18' Twin Elm 1900' E. of 32' x 24' I. Beam Br. 160' Lt. El. 841.82

43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90																																		
32	24	15	0	0	0	17	5	2	7	13	17	20	26	30	34	37	40	43	45	47	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90																			
										C=375 Borr.=36 F+30%=427										C=174 Borr.=172 Available in ROW F+30%=346										C=F+30%=127																																																			
76	57	61	71	78	85	94	122	127	132	139	147	152	158	164	170	175	180	185	190	195	200	205	210	215	220	225	230	235	240	245	250	255	260	265	270	275	280	285	290	295	300	305	310	315	320	325	330	335	340	345	350	355	360	365	370	375	380	385	390	395	400	405	410	415	420	425	430	435	440	445	450	455	460	465	470	475	480	485	490	495	500



DATE
BY
CHECKED
NOTED
PLANNED
NOTED
PLANNED

DATE
BY
CHECKED
NOTED
PLANNED
NOTED
PLANNED

This Sheet
For Information Only

FED. ROAD DIST. NO.	STATE	PROJECT NO.	SHEET NO.	TOTAL SHEETS
5	OH	365	9	25

PLAN

DATE: _____

BY: _____

REVISIONS:

NO. 1 _____

NO. 2 _____

NO. 3 _____

NO. 4 _____

NO. 5 _____

NO. 6 _____

NO. 7 _____

NO. 8 _____

NO. 9 _____

NO. 10 _____

NO. 11 _____

NO. 12 _____

NO. 13 _____

NO. 14 _____

NO. 15 _____

NO. 16 _____

NO. 17 _____

NO. 18 _____

NO. 19 _____

NO. 20 _____

NO. 21 _____

NO. 22 _____

NO. 23 _____

NO. 24 _____

NO. 25 _____

NO. 26 _____

NO. 27 _____

NO. 28 _____

NO. 29 _____

NO. 30 _____

NO. 31 _____

NO. 32 _____

NO. 33 _____

NO. 34 _____

NO. 35 _____

NO. 36 _____

NO. 37 _____

NO. 38 _____

NO. 39 _____

NO. 40 _____

NO. 41 _____

NO. 42 _____

NO. 43 _____

NO. 44 _____

NO. 45 _____

NO. 46 _____

NO. 47 _____

NO. 48 _____

NO. 49 _____

NO. 50 _____

NO. 51 _____

NO. 52 _____

NO. 53 _____

NO. 54 _____

NO. 55 _____

NO. 56 _____

NO. 57 _____

NO. 58 _____

NO. 59 _____

NO. 60 _____

NO. 61 _____

NO. 62 _____

NO. 63 _____

NO. 64 _____

NO. 65 _____

NO. 66 _____

NO. 67 _____

NO. 68 _____

NO. 69 _____

NO. 70 _____

NO. 71 _____

NO. 72 _____

NO. 73 _____

NO. 74 _____

NO. 75 _____

NO. 76 _____

NO. 77 _____

NO. 78 _____

NO. 79 _____

NO. 80 _____

NO. 81 _____

NO. 82 _____

NO. 83 _____

NO. 84 _____

NO. 85 _____

NO. 86 _____

NO. 87 _____

NO. 88 _____

NO. 89 _____

NO. 90 _____

NO. 91 _____

NO. 92 _____

NO. 93 _____

NO. 94 _____

NO. 95 _____

NO. 96 _____

NO. 97 _____

NO. 98 _____

NO. 99 _____

NO. 100 _____

PROFILE

DATE: _____

BY: _____

REVISIONS:

NO. 1 _____

NO. 2 _____

NO. 3 _____

NO. 4 _____

NO. 5 _____

NO. 6 _____

NO. 7 _____

NO. 8 _____

NO. 9 _____

NO. 10 _____

NO. 11 _____

NO. 12 _____

NO. 13 _____

NO. 14 _____

NO. 15 _____

NO. 16 _____

NO. 17 _____

NO. 18 _____

NO. 19 _____

NO. 20 _____

NO. 21 _____

NO. 22 _____

NO. 23 _____

NO. 24 _____

NO. 25 _____

NO. 26 _____

NO. 27 _____

NO. 28 _____

NO. 29 _____

NO. 30 _____

NO. 31 _____

NO. 32 _____

NO. 33 _____

NO. 34 _____

NO. 35 _____

NO. 36 _____

NO. 37 _____

NO. 38 _____

NO. 39 _____

NO. 40 _____

NO. 41 _____

NO. 42 _____

NO. 43 _____

NO. 44 _____

NO. 45 _____

NO. 46 _____

NO. 47 _____

NO. 48 _____

NO. 49 _____

NO. 50 _____

NO. 51 _____

NO. 52 _____

NO. 53 _____

NO. 54 _____

NO. 55 _____

NO. 56 _____

NO. 57 _____

NO. 58 _____

NO. 59 _____

NO. 60 _____

NO. 61 _____

NO. 62 _____

NO. 63 _____

NO. 64 _____

NO. 65 _____

NO. 66 _____

NO. 67 _____

NO. 68 _____

NO. 69 _____

NO. 70 _____

NO. 71 _____

NO. 72 _____

NO. 73 _____

NO. 74 _____

NO. 75 _____

NO. 76 _____

NO. 77 _____

NO. 78 _____

NO. 79 _____

NO. 80 _____

NO. 81 _____

NO. 82 _____

NO. 83 _____

NO. 84 _____

NO. 85 _____

NO. 86 _____

NO. 87 _____

NO. 88 _____

NO. 89 _____

NO. 90 _____

NO. 91 _____

NO. 92 _____

NO. 93 _____

NO. 94 _____

NO. 95 _____



NO. 96 _____

NO. 97 _____

NO. 98 _____

NO. 99 _____



NO. 100 _____





This Sheet For Information Only

DATE: _____ BY: _____
 REVISIONS:
 1. _____
 2. _____
 3. _____
 4. _____
 5. _____
 6. _____
 7. _____
 8. _____
 9. _____
 10. _____
 11. _____
 12. _____
 13. _____
 14. _____
 15. _____
 16. _____
 17. _____
 18. _____
 19. _____
 20. _____
 21. _____
 22. _____
 23. _____
 24. _____
 25. _____
 26. _____
 27. _____
 28. _____
 29. _____
 30. _____
 31. _____
 32. _____
 33. _____
 34. _____
 35. _____
 36. _____
 37. _____
 38. _____
 39. _____
 40. _____
 41. _____
 42. _____
 43. _____
 44. _____
 45. _____
 46. _____
 47. _____
 48. _____
 49. _____
 50. _____
 51. _____
 52. _____
 53. _____
 54. _____
 55. _____
 56. _____
 57. _____
 58. _____
 59. _____
 60. _____
 61. _____
 62. _____
 63. _____
 64. _____
 65. _____
 66. _____
 67. _____
 68. _____
 69. _____
 70. _____
 71. _____
 72. _____
 73. _____
 74. _____
 75. _____
 76. _____
 77. _____
 78. _____
 79. _____
 80. _____
 81. _____
 82. _____
 83. _____
 84. _____
 85. _____
 86. _____
 87. _____
 88. _____
 89. _____
 90. _____
 91. _____
 92. _____
 93. _____
 94. _____
 95. _____
 96. _____
 97. _____
 98. _____
 99. _____
 100. _____

DATE: _____ BY: _____
 REVISIONS:
 1. _____
 2. _____
 3. _____
 4. _____
 5. _____
 6. _____
 7. _____
 8. _____
 9. _____
 10. _____
 11. _____
 12. _____
 13. _____
 14. _____
 15. _____
 16. _____
 17. _____
 18. _____
 19. _____
 20. _____
 21. _____
 22. _____
 23. _____
 24. _____
 25. _____
 26. _____
 27. _____
 28. _____
 29. _____
 30. _____
 31. _____
 32. _____
 33. _____
 34. _____
 35. _____
 36. _____
 37. _____
 38. _____
 39. _____
 40. _____
 41. _____
 42. _____
 43. _____
 44. _____
 45. _____
 46. _____
 47. _____
 48. _____
 49. _____
 50. _____
 51. _____
 52. _____
 53. _____
 54. _____
 55. _____
 56. _____
 57. _____
 58. _____
 59. _____
 60. _____
 61. _____
 62. _____
 63. _____
 64. _____
 65. _____
 66. _____
 67. _____
 68. _____
 69. _____
 70. _____
 71. _____
 72. _____
 73. _____
 74. _____
 75. _____
 76. _____
 77. _____
 78. _____
 79. _____
 80. _____
 81. _____
 82. _____
 83. _____
 84. _____
 85. _____
 86. _____
 87. _____
 88. _____
 89. _____
 90. _____
 91. _____
 92. _____
 93. _____
 94. _____
 95. _____
 96. _____
 97. _____
 98. _____
 99. _____
 100. _____




This Sheet For Information Only





FILE NO.	ENGLISH	DESIGN TEAM	WARREN COUNTY	PROJECT NUMBER	SHEET NUMBER
1:59:05 PM 3/21/2017 jstrum		Holst\Bennett	WARREN COUNTY	NHSN-092-5(56)--2R-91	D.2

This Sheet
For Information Only

FILE NO.	ENGLISH	DESIGN TEAM	WARREN COUNTY	PROJECT NUMBER	SHEET NUMBER
9:17:06 AM 3/24/2022 kjackso		HOLST / BAHR / JACKSON	WARREN COUNTY	NHSX-092-5(70)--3H-91	D.5



Curve Data
 $\Delta = 53^\circ 41' 47.25''$ (RT)
 $T = 759.29$
 $L = 1,405.77$
 $LPI = 1,500.00$
 $e = 181.23$
 $i = 5.2$
 $x = 48$



238	838.45	239	838.44	240	838.43	241	838.41	242	838.40	243	838.39	244	838.38	245	838.37	246	838.35	247	838.34	248	838.33	249	838.32	250	838.31	251	838.29	252	838.28	253	838.27	838.26	838.25	838.23	838.22	838.21	838.20	838.19	838.17	838.16	838.15	838.14	838.13	838.11	838.10	838.09	838.08	838.07	838.05	838.04	838.03	838.02	838.01	837.99	837.98	837.97	837.96	837.95	837.93	837.92	837.91	837.90	837.89	837.87	837.86	837.85	837.82	837.79	837.74	837.69	837.63	837.56	837.48	837.40	837.30	837.20	837.10	837.00	836.92	836.85	836.79	836.74	836.71	836.69	836.69	836.70	836.73	836.76	836.80	836.84
-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------



FILE NO. ENGLISH DESIGN TEAM **Holst/Bennett** WARREN COUNTY PROJECT NUMBER **NHSN-092-5(56)--2R-91** SHEET NUMBER **D.3**

1:59:06 PM 3/21/2017 jstrum pw:\projectwise.dot.int.lan:PWMain\Documents\Projects\9109201014\Design\91092056D2.dgn

This Sheet
For Information Only

FILE NO.	ENGLISH	DESIGN TEAM HOLST / BAHR / JACKSON	WARREN COUNTY	PROJECT NUMBER NHSX-092-5(70)--3H-91	SHEET NUMBER D.6
----------	---------	---	---------------	---	-------------------------

9:17:11 AM 3/24/2022 kjackso pw:\NTPwint1.dot.int.lan:PWMain\Documents\Projects\9109201022\Design\CADD_Files\Sheet_Files\91092070_D01_D17.dgn



250	837.20	251	836.85	252	836.70	253	836.88	254	837.03	255	837.31	256	837.75	257	838.20	258	838.43	259		260		261		262		263		264		265
-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--------	-----	--	-----	--	-----	--	-----	--	-----	--	-----	--	-----

FILE NO. ENGLISH DESIGN TEAM **Holst/Bennett** WARREN COUNTY PROJECT NUMBER **NHSN-092-5(56)--2R-91** SHEET NUMBER **D.4**

1:59:08 PM 3/21/2017 jstrum pw:\projectwise.dot.int.lan:PWMain\Documents\Projects\9109201014\Design\91092056D2.dgn

This Sheet
For Information Only



FILE NO.	ENGLISH	DESIGN TEAM HOLST / BAHR / JACKSON	WARREN COUNTY	PROJECT NUMBER NHSX-092-5(70)--3H-91	SHEET NUMBER D.7
----------	---------	---	---------------	---	-------------------------

9:17:16 AM 3/24/2022 kjackso pw:\NTPwint1.dot.int.lan:PWMain\Documents\Projects\9109201022\Design\CADD_Files\Sheet_Files\91092070_D01_D17.dgn

STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	560	3	60

JEFFERSON TWP
T76N-R25W
SEC. 21

JOHN E. MARTIN



$\Delta = 38^{\circ}55'$
D = 425.1
T = 92.62
L = 519.2
E = 73.1
R = 1206.3

$\Delta = 20^{\circ}00'$ Lt.
D = 10'
T = 573.0
L = 200.0
E = 237.3
R = 573.0

$\Delta = 11^{\circ}12'$
D = 2^o Lt.
D = 230.9
L = 560.0
E = 13.7
R = 2865.0


$\Delta = 53^{\circ}42'12''$
D = 7'
T = 414.4
L = 767.1
E = 28.9
R = 818.6

Sta. 21+75
D.A. 443.0 Mi.
Build 150' x 20' H.T. with
2-40' x 20' I. Beam approaches
Conc. floor and abutments.

Bench Marks:
#34 Sta. 8+00 Spk. in 24' Elm in field S of M. Dale. El. 530.29
#35 Dolt M. 1 km culv. on R. Rd 2+20 So. of M. Dale. El. 538.79
Note: Elev. on plan for Rd. as constructed. 537.06

DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	


DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	



This Sheet
For Information Only


STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	569	2	69

JEFFERSON TWP
T.70N. R.25W




DATE	BY
DATE	BY
DATE	BY

DATE	BY
DATE	BY
DATE	BY




$\Delta = 39^\circ$ Lt
 $D = 4^\circ$
 $T = 507.3$
 $L = 975.0$
 $E = 87.2$
 $R = 1432.5$

BENCH MARKS:
 No. 33 Sta. 17+00 Spike in 24" elm on west bank 200' S. to line... El. 835.45
 No. 32 Sta. 31+75 Spike in T.P. in field W. of R. road 4th from track... El. 831.36





This Sheet
For Information Only

STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	060	5	00




JEFFERSON TWP
T.76N. R.25W.
Sec. 22



DATE	BY	REVISION

NO.	DATE	BY	REVISION




DENCH MARKS:
No. 31. Sta. 46+20 Spike in 12" hard maple in yard N.E. of X road... El. 842.44.
No. 30. Sta. 65+10 Spike in root 30" maple W of hard maples in R.O.W. El. 884.21.




This Sheet
For Information Only

STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	560	0	60

JEFFERSON TWP
T. 76 N. R. 25 W.
SEC. 22




DATE: _____ BY: _____
 SURVEYED: _____
 PLAN: _____
 NOTE BOOK: _____
 ALIGNMENT CHECKED: _____
 RT. OF WAY CHECKED: _____



DATE: _____ BY: _____
 SURVEYED: _____
 PROFILE: _____
 GRADES CHECKED: _____
 B.M. NOTED: _____
 DISTANCE STATINGS CHECKED: _____






BENCH MARKS:
 No. 25 Sta. 88+75 Spike in 12" box elder N. corner from John Straham residence. E.I. 868.00
 No. 30 Sta. 65+10 Spike in root 30" maple W. of house maples in R.O.W. E.I. 864.81




This Sheet
For Information Only

STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	569	7	69

JEFFERSON TWP
T. 76N. R. 25W.
SEC. 23



BENCH MARKS:
No. 28 Sta 107+78 Spike in top pole 1st east of 20' steel bridge... El. 876.25
No. 27 Sta 115+00 Spike in root of 40' maple in yard North... El. 873.04



This Sheet
For Information Only

STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	569	8	69

JEFFERSON TWP.
T76N-R25W

F. J. MILLER

S. A. STRAHAN

SEC. 23

SEC. 24

NANNIE J. J. TAYLOR


F. J. MILLER

S. A. STRAHAN


SEC. 26

SEC. 25

ILO B. WALLACE &
HARRY L. BROWNE



Bench Marks:
 #24 Sta. 147+76 Spk. in T.P.S. at foot of big hill ----- E1-872.60
 #25 Sta. 142+60 Spk. in 36" Maple in Ho. yard, Top of hill ----- E1-818.00
 #26 Sta. 126+50 Spk. in 30" Elm in 1/4 Mi. W of Rd. N ----- E1-875.30






DATE: _____
 BY: _____
 CHECKED: _____
 DATE: _____

DATE: _____
 BY: _____
 CHECKED: _____
 DATE: _____

This Sheet
For Information Only

STATE	PRIM. ROAD PROJ. NO.	SHEET NO.	TOTAL SHEETS
IOWA	569	9	60


JEFFERSON TWP.
T76N-R25W
SEC. 24



DATE	BY	DATE	BY
PLAN	DATE	BY	DATE

DATE	BY	DATE	BY
PROFILE	DATE	BY	DATE

Bench Marks:
#22 Sta. 175+00 Spk. in T.P. 5 1/4 Mi. W of Cor. E.L. 237.26
#23 Sta. 160+00 Spk. in T.P. 8 in draw 1/2 Mi. W of Cor. E.L. 279.22



This Sheet
For Information Only

Warren Co. R.R. 569 Sheet No. 9.

ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.

JEFFERSON TWP
T. 76N. R. 25W.


SEC. 24

SEC. 19


LINCOLN TWP
T. 76N. R. 24W.

FED. ROAD DIST. NO.	STATE	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
			12	69

1930 PAVING



BENCH MARKS
 No. 19 Sta. 177+92 Iron Pin in Lt. Hdwl. of 2'x2'x37' Conc. Box 21' Rt. E1. 945.06
 No. 20 Sta. 185+94 Wood Spk. in root of 20' Elm 30' Lt. E1. 943.68
 No. 21 Sta. 205+87 Iron Pin in Lt. Hdwl. of 2'x2'x43' Conc. Box 19' Lt. E1. 941.74




This Sheet For Information Only

ESTABLISHED WIDTH OF RIGHT OF WAY FT.


LINCOLN TWP
T. 76N. R. 24W.
SEC. 30

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
		560		13	60

1930 PAVING



- BENCH MARKS:**
- No. 21 Sta 205+87 Iron Pin in Lt. Hdwl of 2'x2'x43.9' Conc. Box 19' Lt. --- E1-941.74
 - No. 22 Sta 209+86 Iron Pin in Lt. Hdwl of 2'x2'x42.1' Conc. Box 17' Lt. --- E1-933.65
 - No. 23 Sta 217+14 Spk. in Draced Gate Post on Lt. 40' Lt. --- E1-897.50
 - No. 24 Sta 226+53 Spk. in Cor. Pk. on Lt. 50' Lt. --- E1-883.54
 - No. 25 Sta 232+79 Iron Pin in Rt. Hdwl of 2'x2'x60.7' Conc. Box 21' Rt. --- E1-879.34



WARREN COUNTY, PROJ. NO. R560, SHEET NO. 13

This Sheet For Information Only


ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.

LINCOLN TWP.
T. 76 N. R. 24 W.


Ref for PI at Sta 263+46.7

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
		569		17	69

1930 PAVING



BENCH MARKS
 #26 Sta. 237+36 Iron pin in Rt Hdwl of 12x12x59.6' Conc. Box 30' Rt. -----El. 872.77
 #27 Sta. 251+76 Iron pin in Rt Hdwl of 3x3x58.8' Conc. Box 23' Rt. -----El. 836.67
 #28 Sta. 258+36 Iron pin in Rt Hdwl of 2x2x44.4' Conc. Box 18.7' Rt. -----El. 851.51



Warren COUNTY, PROJ. NO. R.569 SHEET NO. 14 1930 PAVING

This Sheet For Information Only


FILE NO.	ENGLISH	DESIGN TEAM HOLST / BAHR / JACKSON	WARREN COUNTY	PROJECT NUMBER NHSX-092-5(70)--3H-91	SHEET NUMBER D.17
----------	---------	------------------------------------	---------------	--------------------------------------	-------------------

108-23A 08-01-08
TRAFFIC CONTROL PLAN
<p>1. Through traffic on IA 92 shall be maintained at all times.</p> <p>2. Access to all properties shall be maintained at all times.</p> <p>3. The detail on J.2 is the Traffic Control Plan for Centerline Rumble Strip installation on HMA surfaces. Pavement markings shall be replaced within 48 hours of removal.</p> <p>4. If necessary to complete sideroad pavement replacement; lane closures and street closures shall be in accordance with TC-212, TC-251, and TC-252. Safety Closures or Type III barricades placed to protect work area will not be counted or paid for separately.</p>

111-01 04-17-12								
COORDINATED OPERATIONS								
Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.								
<table border="1" style="width: 100%;"> <tr> <th style="width: 50%;">Project</th> <th style="width: 50%;">Type of Work</th> </tr> <tr> <td>None anticipated</td> <td></td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>	Project	Type of Work	None anticipated					
Project	Type of Work							
None anticipated								

108-25 10-21-14												
511 TRAVEL RESTRICTIONS												
Route	Direction	County	Location Description	Feature Crossed	Object Type	Maint. Bridge No., Structure ID, or FHWA No.	Type of Restriction	Existing Measurement	Construction Measurement	Construction Measurement as Signed	Projected As Built Measurement	Remarks
IA 92	BOTH	Warren	0.3 mi E of I-35 to Kennedy St		Traffic Control Device		Horizontal	N/A	12'	11'	N/A	(1)
(1) Restriction is during milling and paving operations.												

108-26A 08-01-08
STAGING NOTES







All vehicles shall be equipped with an amber revolving light or an amber strobe light.

- ① Optional SYG sign background
- ② This arrow display may be operated in a four-corner caution mode.
- ③ This vehicle should move to the shoulder to accommodate passing traffic.
- ④ A vehicle-mounted CMS may be used in lieu of this sign.




01-17-19

**CENTERLINE
RUMBLE STRIPS
TWO-LANE**










This Sheet
For Information Only



This Sheet
For Information Only







This Sheet
For Information Only