

Allamakee COUNTY STP-076-2(63)--2C-03/HSIPX-076-2(64)--3L-03
 HMA Resurfacing
 LETTING DATE 4/19/2022



PLANS OF PROPOSED IMPROVEMENT ON THE
PRIMARY ROAD SYSTEM
Allamakee COUNTY
HMA Resurfacing
 Clayton County Line north to 0.2 miles west of the east junction of Co Rd X32

REVISIONS	TOTAL	61
	PROJECT IDENTIFICATION NUMBER	21-03-076-030
	PROJECT NUMBER	STP-076-2(63)--2C-03/HSIPX-076-2(64)--3L-03
	R.O.W. PROJECT NUMBER	

MILEAGE SUMMARY			105-1 09-27-94
Div.	Location	Lin. Ft.	Miles
** Section A	Sta. 202+35.36 to 397+03.0	19,467.64	3.69
	Sta. Eq. 223+96.40 Bk = 221+72.00 Ah	224.40	0.04
	Bridge at Sta. 223+56.5	-527.04	0.10
	Sta. Eq. 253+81.3 Bk = 253+67.20 Ah	14.10	0.00
	Sta. Eq. 326+85.20 Bk = 326+99.00 Ah	- 13.8	0.00
	Sta. Eq. 346+73.50 Bk = 348+36.90 Ah	-163.40	-0.03
	Sta. Eq. 387+64.6 Bk. = 388+31.7 Ah.	- 67.1	-0.01
** Section B	Sta. 835+00.0 to 376+50.0	45,850.0	8.68
	Sta. Eq. 397+03.0 Bk = 835+00.0 Ah	0.00	0.00
	Sta. Eq. 699+68.38 Bk = 699+72.76 Ah	- 4.38	0.00
	Sta. Eq. 604+37.07 Bk = 605+01.60 Ah	- 64.5	-0.01
	Sta. Eq. 456+22.53 Bk = 456+14.61 Ah	7.92	0.00
	Total	63,732.8	12.26

** In Section A, stationing increases northbound. In Section B the stationing reverses decreasing northbound. Right and left will go with stationing.

Refer to the Proposal Form for list of applicable specifications.
 Value Engineering Saves. Refer to Article 1105.14 of the Specifications.

SCALES: As Noted



INDEX OF SHEETS	
A.1-A.2	Title Sheet and Location Map
* B.1-6	Typical Cross Sections and Details
C.1-9	Estimate of Quantities and General Notes
C.10	Index of Tabulations
C.10-22	Tabulations
* D.1-25	As-Built Information Sheets
J.1	Traffic Control Sheet
* U.1- U.5	500 Series and Detail Sheets
* Denotes Color Sheets	

DESIGN DATA RURAL			
2022	AADT	2100	V.P.D.
2042	AADT	2400	V.P.D.
20	-- DHV	--	V.P.H.
	TRUCKS	17	%
	Total		
	Design ESALS	1,042,440	

INDEX OF SEALS		
SHEET NO.	NAME	TYPE
A.1	Mary K. Kelly	Primary Signature Block

PROFESSIONAL ENGINEER


MARY K.
KELLY
17552


IOWA

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Mary K. Kelly 1/31/2022
 Signature Date
 Mary K. Kelly
 Printed or Typed Name
 My license renewal date is December 31, 20 22.

Pages or sheets covered by this seal: A.1-A.2, B.1-B.6 C.1-C.22, D.1-D.25, J.1, U.1-U.5






Notes:

- ① Finished slope shall match existing pavement except that the maximum allowable slope is 3.0 %, minimum allowable slope is 2.0 %. Section may be modified as directed by the Engineer through areas of special shaping.

Location		(M)	(I)	(S)	(B)	(L)	(R)	(C)	(P)	Remarks
Station To Station		Inches	Inches	Inches	Inches	Feet	Feet	Feet	Feet	
202+35.36	220+92.98	2	1	2	5	12	12	28	2	BOP Bridge
226+20.02	387+64.6	2	1	2	5	12	12	28	2	
388+31.7	397+03.0	2	1	2	5	12	12	28	2	Equation
										Note: Equation Stations not shown. See Tabs. 100-25 and 112-9.


TYPICAL CROSS SECTION MILLING AND HMA RESURFACING



- Notes:
- ① HMA base widening shall be performed prior to cold-in-place recycling. The top 4" of the newly placed base widening unit shall be cold-in-place recycled.
 - ② Finished slope shall match existing pavement except that the maximum allowable slope is 3.0 %, minimum allowable slope is 2.0 %. Section may be modified as directed by the Engineer through areas of special shaping.
 - ③ Provide a clean vertical edge similar to what can be achieved with a milling machine. Incidental to "Class 13 Excavation for Widening".
 - ④ Foamed asphalt binder for C-I-P-R shall be PG 52-34S.
 - ⑤ Discontinue base widening at existing paved intersections; refer to Typical 7154B for additional information. Base widening to be extended through current unpaved sideroad intersections; see Typical 7149 for additional information.
 - ⑥ Suspend C-I-P-R at continuously reinforced PC patches and other PC patches as directed by the Engineer.

Location		(M)	(I)	(S)	(B)	(L)	(R)	(C)	(P)	Remarks
Station To	Station	Inches	Inches	Inches	Inches	Feet	Feet	Feet	Feet	
835+00.0	833+50.0	4	0-1.5	1.5	7	12	12	32	4	Equation
833+50.0	378+00.0	4	1.5	1.5	7	12	12	32	4	Equation
378+00.0	376+50.0	4	1.5-0	1.5	7	12	12	32	4	EOP
Note: Equation Stations not shown. See Tabs. 100-25 and 112-9.										

TYPICAL CROSS SECTION COLD-IN-PLACE RECYCLING WITH HMA RESURFACING




Notes: Discontinue Base Widening at turn lanes.
 Cold in Place Recycle existing turn lane pavement except for taper areas. Taper areas shall be scarified 1/2" prior to resurfacing. Scarification of turn lane tapers is incidental to Cold in Place Recycling.

① Finished slope shall match existing pavement except that the maximum allowable slope is 3.0 %, minimum allowable slope is 2.0 %. Section may be modified as directed by the Engineer through areas of special shaping.

See Typ. MK-2 for mainline information.

Location		(S)	(I)	(C)	(L)	(R)	(M)	(TL)	Remarks
Station To Station		Inches	Inches	Feet	Feet	Feet	Inches	Feet	
232+40.0	233+40.0	2	1	24-36	12	12	2	0-12	SB Passing Lane taper.
233+40.0	243+40.0	2	1	36	12	12	2	12	SB passing lane
243+40.0	245+00.0	2	1	36-24	12	12	2	12-0	SB passing lane taper
233+40.0	235+00.0	2	1	24-36	12	12	2	0-12	NB turn lane taper
235+00.0	239+60.0	2	1	36	12	12	2	12	NB turn lane & through Effigy Mounds Ent.

**TYPICAL CROSS SECTION
 EXISTING TURN LANE
 MILLING AND HMA RESURFACING**




Notes:
 Discontinue Base Widening at turn lanes.

① Finished slope shall match existing pavement except that the maximum allowable slope is 3.0 %, minimum allowable slope is 2.0 %. Section may be modified as directed by the Engineer through areas of special shaping.

③ See Typ. MK-1 for mainline information.


Location		(S)	(I)	(C)	(L)	(R)	(P)	(M)	(TL)	(B)	Remarks
Station To Station		Inches	Inches	Feet	Feet	Feet	Feet	Inches	Feet	Inches	
823+76.0	822+76.0	1.5	1.5	28-40	12	12	4	4	0-12	7	NB Right turn lane taper, X52 Taper, no CIPR
822+76.0	820+00.0	1.5	1.5	40	12	12	4	4	12	7	NB Right turn lane, X52

**TYPICAL CROSS SECTION
 EXISTING TURN LANE
 COLD-IN-PLACE RECYCLING WITH HMA RESURFACING**



RESHAPING DITCHES TYPICAL

7135
Modified




- HMA Paving
- Base Widening
- Granular

- ① Complete granular pre-shouldering prior to Class 13 Excavation to provide for a trench for base widening. Existing granular shoulder material from the outer shoulder area may be used as designated by the Engineer.
 - ② See Tabulation 112-9
- 6" thickness was assumed to account for low shoulders.


TYPICAL SECTION FOR TYPE 'B' GRANULAR SHOULDER
 ADJACENT TO HOT MIX ASPHALT RESURFACING

LOCATION			SIDE	① Inches
ROAD	STATION TO STATION ②			
IA 76	835+00.0	376+50.0	BOTH	6

7154A
10-20-09




With Newly Constructed Turn Lanes




At UAC Turn Lanes

**PAVED SHOULDER
DETAIL AT
TURN LANES**

7154B
10-20-09




With Newly Constructed Returns



At UAC Returns

**PAVED SHOULDER
DETAIL AT RETURNS**

7315
10-20-09




Notes:

- ① Notch: Min = nominal maximum aggregate size + 1/4". Max = T/2.
- ② 12:1 Slope
- ③ Optional step at toe of slope: Max = 1".

**LONGITUDINAL HMA
NOTCHED WEDGE JOINT
T = 2" OR GREATER**

MK-5


Posted Speed Limit (mph)	Runout Ratio (ft per inch)
45 or More	50
20 to 45	25
Under 20	10 *



** See Typical MK-1 and MK-2 and Tabulation 102-16 for more information.

Location Station	S Inches	I Inches	M Inches	Scarification S.Y.	Remarks
397+03.0	**	**	**	300	Equation

RUNOUT FOR TRIPLE COURSE RESURFACING



PLAN VIEW


9" HMA Paved Shoulder at guardrail. 8" PCC may be substituted with the following jointing layout:

Match mainline pavement joint spacing. When mainline pavement is 8" or greater in thickness, place additional transverse 'C' joints in shoulder at mid-panel of the mainline pavement. Place longitudinal 'C' joint at P/2 from edge of mainline pavement when P is greater than 10' wide. Terminate longitudinal joint at transverse joint less than 10' in length.


Compaction of HMA is required to face of guardrail post. Hand compaction will be allowed under guardrail. Removal and reinstallation of guardrail will be allowed with no additional payment.

Refer to Tabulation 112-9 for shoulder quantities.

- ① For subgrade treatment, refer to other details in the plan.
- ② PCC option only: When guardrail posts are installed prior to construction of PCC paved shoulder, fasten form board to the face of guardrail posts for the length shown. Refer to note 4 for final 2 posts.
- ③ Continue paved shoulder to existing paved shoulder or 20 feet beyond the center of the first post.
- ④ Shoulder may be notched for final 2 posts or post sleeves may be installed through pavement. Do not drive posts through pavement.
- ⑤ 'KT-1 joint for PCC shoulder. 'B' joint for HMA shoulder.




Section A-A



Section B-B


NEW CONSTRUCTION




Section C-C

Roll down at granular shoulder or earth.

PAVED SHOULDER AT GUARDRAIL



Section A-A



Section B-B

EXISTING SHOULDER

ESTIMATED PROJECT QUANTITIES AND REFERENCE NOTES

Division 1: Federal Aid Eligible
Division 2: Non-Participating

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
1	2101-0850001	CLEARING AND GRUBBING	ACRE	4.3		4.3	Refer to Tab. 110-17 for more information. All material generated as a result of Clearing and Grubbing shall become the property of the contractor and must be disposed off site. All wood material must be disposed of according to Iowa Department of Agriculture and Land Stewardship Emerald Ash Borer Quarantine Order. For more information see www.iowatreepests.com .
2	2101-0850002	CLEARING AND GRUBBING	UNIT	42.2		42.2	See Tab. 110-17 for more information. "All wood material generated as a result of Clearing and Grubbing must be disposed of according to Iowa Department of Agriculture and Land Stewardship Emerald Ash Borer Quarantine Order. For more information see www.iowatreepests.com ." Tree clearing is not restricted to the winter months and trees may be cleared/trimmed at anytime.
3	2102-2625000	EMBANKMENT-IN-PLACE	CY	236		236	See Tab. 104-13 and 107-23 for more information. Material shall be provided by the Contractor.
4	2102-2713090	EXCAVATION, CLASS 13, WASTE	CY	1,975.4		1,975.4	See Tab. 112-9, Typ. MK-1, MK-2, and MK-4 for more information. Removal of existing sideroad fillets shall be incidental to Class 13 excavation. Removal of existing widening shall be incidental to Class 13 excavation. Class 13 excavation shall become the property of the Contractor.
5	2122-5190501	PAVED SHOULDER, PORTLAND CEMENT CONCRETE (PAVED SHOULDER PANEL FOR BRIDGE END DRAIN)	SY	88.1		88.1	See Tab. 104-8A for more information.
6	2122-5500090	PAVED SHOULDER, HOT MIX ASPHALT MIXTURE, 9 IN.	SY	463		463	Refer to Tab. 112-9 for more information.
7	2123-7450000	SHOULDER CONSTRUCTION, EARTH	STA	1,086.7		1,086.7	See Tab. 112-9 and Typ. 7135 for more information. Includes 1086.7 stations of nominal 9.5 ft. wide shoulder.
8	2125-2225050	RESHAPING DITCHES	STA	0.4		0.4	Refer to typical MK-7 and Tab 104-13 for additional information. Item is to reshape ditch areas that can't be removed during normal handwork operations as found during culvert work (adding aprons) within project limits. Contractor shall supply all equipment and labor needed to reshape ditches. Sediment and debris to remain property of the contractor. Any damage to culverts shall be repaired by the Contractor. Verify method, prior to cleaning, with the Engineer. Contractor to prevent sediment from leaving the project in accordance with the Pollution Prevention Plan. A quantity length of 40LF has been applied to the contract for a ditch running south of Thomas Road at approximate station 363+05 left. Additional length shall be approved by the Engineer. Method of measurement and basis of payment is per LF of satisfactorily cleaned out culvert.
9	2212-5070310	PATCHES, FULL-DEPTH REPAIR	SY	191.6		191.6	Refer to Tab. 102-6C for more information.

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
10	2212-5070330	PATCHES BY COUNT (REPAIR)	EACH	6		6	
11	2214-5145150	PAVEMENT SCARIFICATION	SY	57,671.4		57,671.4	See Tab. 100-25 for more information.
12	2303-0002380	HOT MIX ASPHALT MIXTURE INTERLAYER BASE COURSE, 3/8 IN. MIX	TON	3,368.7		3,368.7	Refer to Tab. 100-25 for more information.
13	2303-1032500	HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	TON	10,159		10,159	
14	2303-1033504	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, FRICTION L-4	TON	16,761.7		16,761.7	
15	2303-1258283	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	TON	1,796.5		1,796.5	
16	2303-1258346	ASPHALT BINDER, PG 58-34E, EXTREMELY HIGH TRAFFIC	TON	269.5		269.5	
17	2303-6911000	HOT MIX ASPHALT PAVEMENT SAMPLES	LS	1		1	
18	2303-7000610	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)	EACH	13,460		13,460	
19	2303-7000620	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)	EACH	13,460		13,460	
20	2317-7000120	PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA PAVEMENT SMOOTHNESS (BY SCHEDULE)	EACH	86,310		86,310	
21	2318-1001100	COLD IN-PLACE RECYCLED ASPHALT PAVEMENT	SY	122,810.2		122,810.2	
22	2318-1001220	ASPHALT STABILIZING AGENT (FOAMED ASPHALT)	TON	540.4		540.4	
23	2401-6750001	REMOVALS, AS PER PLAN	LS	1		1	Includes all work for removal and off-site disposal. See tab. 110-2. Removal of scheduled items shall be in accordance with Section 2401, of the Standard Specifications. Any damage to material not to be removed shall be the responsibility of the Contractor and repaired at no extra cost to the state.
24	2402-2720100	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT	CY	146		146	Refer to Tab. 104-13 for more information.
25	2416-0100024	APRONS, CONCRETE, 24 IN. DIA.	EACH	9		9	Refer to Tab. 104-13 for more information.
26	2416-0100030	APRONS, CONCRETE, 30 IN. DIA.	EACH	1		1	Refer to Tab. 104-13 for more information.
27	2416-0101036	REMOVE AND REINSTALL CONCRETE PIPE APRONS LESS THAN OR EQUAL TO 36 IN.	EACH	3		3	
28	2416-1180024	CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	LF	18		18	
29	2422-0360018	APRONS, UNCLASSIFIED, 18 IN. DIA.	EACH	2		2	See Tab. 104-13 for more information.

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
30	2499-4000036	SLIPLINING EXISTING CULVERTS, LESS THAN OR EQUAL TO 36 IN. DIA. OR HEIGHT	LF	136		136	Liner shall be a nominal size to fit the existing 24 in RCP at Sta 378+00 in Section A and 384+90 in Section B. The liner shall be furnished and installed per DS-15090. Refer to Tab. 104-13. Estimate 3.4 CY and 3.6 CY of grouting, respectively.
31	2499-4000136	SLIPLINING EXISTING CULVERTS, GREATER THAN 36 IN. DIA. OR HEIGHT	LF	244		244	The liner shall be a nominal size of 66 inches and shall have an outside diameter small enough to accommodate the existing 6' x 6' RCB at Sta 774+88. The liner shall be furnished and installed as specified in DS-15090. Refer to Tab 104-13. The estimated quantity of flowable mortar is 111 CY and shall be incidental to this bid item.
32	2499-6000100	CLEAN OUT PIPE CULVERT	LF	40		40	Refer to typical MK-7 for additional information. Item is to remove sediment and debris from within culvert barrels that can't be removed during normal handwork operations as found during culvert work (adding aprons) within project limits. Contractor shall supply all equipment and labor needed to remove sediment and debris. Sediment and debris to remain property of the contractor. Any damage to culvert shall be repaired by the Contractor. Verify method, prior to cleaning, with the Engineer. Contractor to prevent sediment from leaving the project in accordance with the Pollution Prevention Plan. A quantity length of 40 LF has been applied to the contract per Tab 104-13. Additional length shall be approved by the Engineer. Method of measurement and basis of payment is per LF of satisfactorily cleaned out culvert.
33	2503-0500402	BRIDGE END DRAIN, DR-402	EACH	2		2	Refer to Tab. 104-8A for more information.
34	2505-4008120	REMOVAL OF STEEL BEAM GUARDRAIL	LF	238		238	Refer to Tab. 110-7A for more information.
35	2505-4008300	STEEL BEAM GUARDRAIL	LF	25		25	Refer to Tab. 108-8A for more information.
36	2505-4008410	STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-201	EACH	2		2	
37	2505-4008420	STEEL BEAM GUARDRAIL BARRIER TRANSITION SECTION, BA-221	EACH	2		2	
38	2505-4021010	STEEL BEAM GUARDRAIL END ANCHOR, BOLTED	EACH	4		4	
39	2505-4021720	STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-205	EACH	2		2	
40	2505-4021722	STEEL BEAM GUARDRAIL TANGENT END TERMINAL, BA-225	EACH	2		2	
41	2507-3250005	ENGINEERING FABRIC	SY	189.7		189.7	Refer to Tab. 100-23 for more information.
42	2507-6800061	REVTMENT, CLASS E	TON	117.6		117.6	Refer to Tab. 100-23 for more information.
43	2510-6745850	REMOVAL OF PAVEMENT	SY	77.3		77.3	Refer to Tab.110-1 for more information.

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
44	2520-3350010	FIELD LABORATORY	EACH	1		1	
45	2524-9089300	DELINEATOR, RIGID - TYPE III	EACH	98		98	Refer to Tabulation 190-25 for more information. Removal of existing delineator posts shall be incidental and become property of the contractor.
46	2524-9100020	OBJECT MARKER, TYPE 2	EACH	2		2	Refer to Tabulation 190-25 for locations and details. Object marker shall be installed at a height of 4' measured from the bottom of the object marker to the elevation of the near edge of traveled way. Each will be measured for payment. Payment is full compensation for removing existing object markers and furnishing all labor equipment and materials to erect new.
47	2526-8285000	CONSTRUCTION SURVEY	LS	1		1	DOT will be responsible for preservation of section corners including Public Land Survey Corner Certificates and shall not be included in this bid item. All other construction survey requirements shall apply.
48	2527-9263109	PAINTED PAVEMENT MARKING, WATERBORNE OR SOLVENT-BASED	STA	5,115		5,115	Refer to Tab. 108-22 for more information.
49	2527-9270111	GROOVES CUT FOR PAVEMENT MARKINGS	STA	1,278.01		1,278.01	Refer to Tab. 108-22 for more information.
50	2528-8445110	TRAFFIC CONTROL	LS	1		1	
51	2528-8445113	FLAGGERS	EACH	0		0	See Proposal.
52	2528-8445115	PILOT CARS	EACH	0		0	
53	2529-5070110	PATCHES, FULL-DEPTH FINISH, BY AREA	SY	53.4		53.4	Refer to Tab. 102-6C for more information.
54	2529-5070120	PATCHES, FULL-DEPTH FINISH, BY COUNT	EACH	2		2	
55	2533-4980005	MOBILIZATION	LS	1		1	--
56	2548-0000100	MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	STA	378.67		378.67	See Tab. 112-10 for more information.
57	2548-0000110	ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	GAL	410.4		410.4	
58	2548-0000310	MILLED CENTERLINE RUMBLE STRIPS, HMA SURFACE	STA	189.34		189.34	
59	2555-0000010	DELIVER AND STOCKPILE SALVAGED MATERIALS	LS		1	1	Refer to Tab. 110-13.
60	2595-0005125	RAILROAD PROTECTIVE LIABILITY INSURANCE FOR DAKOTA, MINNESOTA, AND EASTERN RAILROAD CORP.	LS	1		1	DS-15088 shall apply to this project.
61	2599-9999005	('EACH' ITEM) Type C Connection	EACH	13		13	See tab. 104-13. Each Type "C" Connection will be measured for payment. Payment is full compensation for repair or replacement of existing joint. It will include all cost of furnishing all materials, labor, and equipment to construct Type "C" connection.
62	2601-2632110	FERTILIZING	ACRE	20		20	

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
63	2601-2634100	MULCHING	ACRE	20		20	<p>Perform mulching according to Article 2601.03, E, 2, of the Standard Specifications. Anchor mulch into the soil using mulch anchoring equipment with a minimum of two passes.</p> <p>Item is included for areas requiring reshaping and seedbed preparation. Use mulch that is Certified Noxious Weed Seed Free Mulch as certified by the Iowa Crop Improvement Association or adjacent states Crop Improvement Associations.</p>
64	2601-2636043	SEEDING AND FERTILIZING (RURAL)	ACRE	20		20	<p>Seeding and fertilizing shall be placed along the granular shoulder in the area being disturbed with the earth shoulder finishing. Includes guardrail blisters and pipe construction areas.</p>
65	2601-2642100	STABILIZING CROP - SEEDING AND FERTILIZING	ACRE	20		20	<p>Item is included for disturbed areas.</p> <p>Seed and fertilize all disturbed areas according to Article 2601.03, C, 1, of the Standard Specifications. If permanent seeding cannot be placed due to the restrictive planting dates, stabilizing crop will need to be placed on all disturbed areas as temporary erosion control. Preparation and seeding shall be performed in accordance with Section 2601. Stabilizing crop will not be used when the application dates in Section 2601 allows permanent seeding.</p> <p>If stabilizing crop must be used, place immediately following completions of finished grading. Reseeding of these areas will be required at contractors expense if damage occurs due to contractors negligence during the contract period.</p>
66	2601-3000201	HERBICIDE APPLICATION, CUT STUMP	EACH	6		6	<p>Coordinate with the "Clearing" (Item Code 2101-0850002).</p> <p>Furnish and apply herbicide to cut stumps of cleared trees.</p> <p>Includes locating stumps, furnishing and applying herbicide and related activities with no extra compensation allowed.</p> <p>See Standard Note 231-2.</p> <p>TREATMENT No. 1: Only for use on stumps that will be treated with herbicide immediately after cutting and temperatures are above freezing.</p> <p>Cut stumps to less than 2 inches prior to herbicide application and brush away sawdust from the cut surface. Within 5 minutes of the stump cut, apply triclopyr herbicide. Leave stumps without any additional cutting or grinding for 6 weeks after herbicide treatment to allow for the herbicide to translocate.</p> <p>Use a water-based triethylamine or quaternary ammonium salt formation to triclopyr herbicide, labeled for use in and around standing water. Mix the herbicide at 3 pounds per gallon acid equivalent (ae) of triclopyr (For example, for products containing 3 pounds per gallon ae of triclopyr, apply undiluted.) Apply the herbicide according to label directions for cut surface treatments, using a brush or directed spray, wetting the outer 2 inches of sapwood and the cambium (the tissue just inside the bark) including the entire circumference and any torn bark areas. It is not necessary to treat the bark on the sides of the stump or exposed roots.</p> <p>TREATMENT No. 2: Use if stumps are not treated with herbicide immediately after cutting or if directed</p>

by the Engineer to be used during below freezing conditions.

Cut stumps initially to a height of not less than 6 inches and flag to relocated for herbicide treatment. Apply triclopyr herbicide within 7 days of the stump cut. After treating with herbicide, leave stumps without further cutting for not less than 6 weeks to allow time for the herbicide application to translocate, then cut or grind stumps to less than 2 inches. The cost for cutting and grinding stumps will not be paid for directly, but will be incidental to the price for Herbicide Application, Cut Stump.

Use an oil-soluble formulation of triclopyr, labeled for use on non-irrigation ditch banks and seasonally dry wetlands. Mix the herbicide with an oil carrier to a concentration of 1.0 pound per gallon ae of triclopyr (For example, for products containing 4 pounds per gallon ae of triclopyr, mix 1 quart herbicide with 3 quarts oil carrier, for a 25% solution.) For the oil carrier, use a penetrating oil labeled for basal or cut stump treatments. Diesel fuel and kerosene-based products will not be accepted. "Ready to Use" products containing 0.75 pounds per gallon ae of triclopyr and non-petroleum carrier may be approved.

Apply the herbicide mixture according to label directions for cut stump treatment to the outer 2 inches of the cut surface, wetting the sapwood and cambium (the tissues just inside the bark layer) around the entire tree circumference, also wetting the sides of the stump to ground line and any exposed roots.

Cautions: This herbicide is volatile and may cause off-target damage if used when temperatures exceed 85 degrees F during the three days following the application. It is a violation of federal law to apply this herbicide in areas with standing or flowing water. If soil is saturated or there is standing water in the spray area, do not use this treatment.

Preapproved products:

Triclopyr herbicide in a water-based formulation:

Garlon 3A

NuFarm Tahoe 3A

Ecotriclopyr

Vastlan (4 pounds per gallon ae)

Triclopyr herbicide in oil-soluble formulation:

Garlon 4 Ultra

NuFarm Tahoe 4E

Triclopyr 4EC

Pathfinder II (Ready-to-Use)

Custom Blended per-mixes must be approved by the Engineer

Oil Carrier:

Bark Oil Blue LT

Diluent Blue

Proprietary oil contained in Pathfinder II

Dye:

Hi-Light Blue

Red River Mark

Method of Measurement: The quantity of "Herbicide Application, Cut Stump" for which payment is made will be measured per each stump treated with herbicide and cut to ground line.

Basis of Payment:

Contractor will be paid the contract unit price per each. Payment is full compensation for furnishing all materials, equipment and labor and for performing all work necessary according to the contract documents.

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
67	2601-3000206	HERBICIDE APPLICATION, CUT STUMP	LS	1		1	<p>2601-3000206 Herbicide Application, Cut Stump</p> <p>Coordinate with the "Clearing" (Item Code 2101-0850001). Furnish and apply herbicide to cut stumps of cleared trees.</p> <p>Includes locating stumps, furnishing and applying herbicide and related activities with no extra compensation allowed.</p> <p>See Standard Note 231-2.</p> <p>See note for Item Code 2601-3000201 "Herbicide Application, Cut Stump" for treatment and products.</p> <p>Method of Measurement: The quantity of "Herbicide Application, Cut Stump" for which payment is made will be a lump sum for the stumps treated with herbicide and cut to ground line.</p> <p>Basis of Payment:</p> <p>Contractor will be paid the contract unit price lump sum. Payment is full compensation for furnishing all materials, equipment and labor and for performing all work necessary according to the contract documents.</p>
68	2602-0000020	SILT FENCE	LF	375		375	<p>Refer to Tab. 100-17 for more information.</p> <p>The tabulation includes estimated locations for placement of "Silt Fence" to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 25% additional quantity for field adjustments and replacements.</p>
69	2602-0000030	SILT FENCE FOR DITCH CHECKS	LF	72		72	<p>Refer to Tab 100-18 for more information.</p> <p>The tabulation includes estimated locations for placement of "Silt Fence for Ditch Checks" to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Bid item includes 50% additional quantity for field adjustments and replacements.</p>
70	2602-0000071	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	LF	447		447	<p>See Tab. 100-18 and 100-17. Included 50%.</p> <p>This item is included for silt fence and silt fence for ditch check removal required for staging reasons, removal to allow for replacement (replacement to be paid separately), or for areas that have achieved 70% permanent growth. This item is included for silt fence and silt fence for ditch check removal.</p> <p>Remove silt fence and posts after mulching or vegetation is established and approved by the engineer.</p>

Item no.	Item Code	Item	Unit	Quantities			Estimate Reference Notes
				Estimated			
				Division 1	Division 2	Total	
71	2602-0000101	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	LF	447		447	See Tabs. 100-18 and 100-17 for more information. This item is included for clean-out and repair of the silt fence and silt fence for ditch checks during the project. Bid item includes 50% additional quantity for field adjustments and replacements.
72	2602-0000312	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	LF	3,640		3,640	Refer to Tab. 100-19. The tabulation includes estimated locations for placement of "Perimeter and Slope Sediment Control Device, 12 in. dia." to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement.
73	2602-0000351	REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	LF	5,480		5,480	Refer to Tab. 100-19 for more information.
74	2602-0000362	DITCH CHECK SEDIMENT CONTROL DEVICE, 12 IN. DIA.	LF	1,840		1,840	Refer to Tab. 100-19 for more information.
75	2602-0010010	MOBILIZATIONS, EROSION CONTROL	EACH	1		1	

ESTIMATED PROJECT QUANTITIES AND REFERENCE NOTES

Roadway Items : Roadway Items

Item no.	Item Code	Item	Unit	Quantities		Estimate Reference Notes
				Estimated	Roadway Items	
1	2102-2713090	EXCAVATION, CLASS 13, WASTE	CY	9,377.4		See Tab. 112-9, Typ. MK-1, MK-2, and MK-4 for more information. Removal of existing sideroad fillets shall be incidental to Class 13 excavation. Removal of existing widening shall be incidental to Class 13 excavation. Class 13 excavation shall become the property of the Contractor.
2	2121-7425020	GRANULAR SHOULDERS, TYPE B	TON	21,450.6		Refer to Typical 7110 and Tab. 112-9 for more information.
3	2213-8200000	BASE WIDENING, HOT MIX ASPHALT MIXTURE	TON	18,356.3		
4	2303-1032500	HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	TON	3,386.3		
5	2303-1033504	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, FRICTION L-4	TON	3,386.3		
6	2303-1258283	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	TON	1,507.8		
7	2318-1001100	COLD IN-PLACE RECYCLED ASPHALT PAVEMENT	SY	71,639.3		
8	2318-1001220	ASPHALT STABILIZING AGENT (FOAMED ASPHALT)	TON	315.2		
9	2548-0000100	MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	STA	918.2		See Tab. 112-10 for more information.
10	2548-0000110	ASPHALT EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	GAL	994.8		Refer to Tab. 112-10 for more information.
11	2548-0000310	MILLED CENTERLINE RUMBLE STRIPS, HMA SURFACE	STA	459.1		See Tab. 112-10 for more information.

100-1D 10-18-05
PROJECT DESCRIPTION
This project involves resurfacing the roadway from Clayton County Line north to 0.2 miles west of the east junction of Co Rd X32. The purpose of the project is to improve the condition of the mainline pavement. Resurfacing the roadway will address this concern and adding paved shoulders will improve the safety of the corridor. Milled rumble strips and guardrail replacement will be part of this project.

105-4 10-18-11
STANDARD ROAD PLANS

The following Standard Road Plans apply to construction work on this project.		
Number	Date	Title
BA-200	04-20-21	Steel Beam Guardrail Components
BA-201	04-19-22	Steel Beam Guardrail Barrier Transition Section (MASH TL-3)
BA-202	10-20-15	Steel Beam Guardrail Bolted End Anchor
BA-205	10-19-21	Steel Beam Guardrail Tangent End Terminal (MASH TL-3)
BA-221	04-19-22	Steel Beam Guardrail Barrier Transition Section (MASH TL-2)
BA-225	10-19-21	Steel Beam Guardrail Tangent End Terminal (MASH TL-2)
BA-250	04-20-21	Steel Beam Guardrail Installation at Concrete Barrier or Bridge End Post (MASH TL-3)
BA-260	04-20-21	Steel Beam Guardrail Installation at Concrete Barrier or Bridge End Post (MASH TL-2)
DR-101	04-18-17	Pipe Culvert (Bedding and Backfill)
DR-121	10-17-17	Connected Pipe Joints
DR-122	10-18-16	Construction of Type "C" Concrete Adaptors for Pipe Culvert Connections
DR-201	04-21-20	Concrete Aprons
DR-402	04-19-22	Rock Flume for Bridge End Drain
DR-601	04-18-17	Reinforced Concrete Pipe Culvert
DR-621	04-18-17	Pipe Extension
EC-201	04-20-21	Silt Fence
EC-204	10-19-21	Perimeter, Slope and Ditch Check Sediment Control Devices
EC-301	10-18-16	Rock Erosion Control (REC)
EC-502	04-21-15	Seeding in Rural Areas
EW-301	04-20-21	Guardrail Grading
PM-110	04-21-20	Line Types
PM-120	10-21-14	Stop Lines and Islands
PM-420	10-15-19	Two-Lane Roadway with no Turn Lanes (One-Way Stop Condition)
PM-521	10-15-19	Two-Lane Roadway with Right Turn Lanes
PR-103	04-21-20	Full Depth PCC Patch with Dowels
PR-201	10-21-14	Runouts for Resurfacing
PR-202	10-21-14	Notches for Resurfacing (with or without Runout)
PV-3	04-16-19	Safety Edge
PV-12	10-20-20	Milled Shoulder Rumble Strips
PV-13	10-17-17	Milled Centerline Rumble Strips
PV-101	04-19-22	Joints
PV-202	04-21-20	Hot Mix Asphalt Resurfacing
PV-301	04-21-20	Superelevation Details Two Lane Roadway
SI-172	04-19-16	Delineators
SI-173	04-19-16	Object Markers
SI-211	10-18-16	Object Marker and Delineator Placement with Guardrail
TC-1	10-15-19	Work Not Affecting Traffic (Two-Lane or Multi-Lane)
TC-202	10-19-21	Work Within 15 ft of Traveled Way
TC-213	10-15-19	Lane Closure with Flaggers
TC-214	04-21-20	Lane Closure with Flaggers for use with Pilot Car
TC-282	10-15-19	Uneven Lanes

111-25 10-18-11
INDEX OF TABULATIONS

Tabulation	Tabulation Title	Sheet No.
C Sheets		
100-1D	PROJECT DESCRIPTION	C.9
100-1E	UTILITIES	C.21
100-17	TABULATION OF SILT FENCES	C.13
100-18	SILT FENCES FOR DITCH CHECKS	C.13
100-19	PERIMETER, SLOPE AND DITCH CHECK SEDIMENT CONTROL DEVICES	C.14
100-23	ROCK EROSION CONTROL	C.14
100-25	HMA PAVEMENT	C.18
102-5	EXISTING PAVEMENT	C.12
102-6C	FULL-DEPTH PATCHES	C.14
102-16	NOTCHES AND RUNOUTS FOR RESURFACING	C.12
104-8A	SCOUR PROTECTION OR ROCK FLUME FOR BRIDGE END DRAIN	C.19
104-13	FORESLOPE FLATTENING AND DRAINAGE STRUCTURES BY ROAD CONTRACTOR (MAINLINE PIPES)	C.13
105-4	STANDARD ROAD PLANS	C.9
107-23	GRADING FOR GUARDRAIL INSTALLATIONS	C.19
108-8A	STEEL BEAM GUARDRAIL AT CONCRETE BARRIER OR BRIDGE RAIL END SECTION	C.19
108-22	PAVEMENT MARKING LINE TYPES	C.21
110-1	REMOVAL OF PAVEMENT	C.20
110-2	REMOVAL OF EXISTING STRUCTURES	C.14
110-7A	REMOVAL OF STEEL BEAM GUARDRAIL	C.19
110-12	POLLUTION PREVENTION PLAN	C.10 - C.11
110-13	DELIVERY AND STOCKPILING	C.19
110-17	CLEARING AND GRUBBING	C.15
111-25	INDEX OF TABULATIONS	C.9
112-9	SHOULDERS	C.17
112-10	MILLED RUMBLE STRIPS	C.20
190-25	REFERENCE LOCATION SIGNS AND DELINEATORS	C.16

231-2 04-21-20
HERBICIDE
For all herbicide applications, the following provisions shall apply.
1. Follow all laws, rules and regulations related to the handling of pesticides, including but not limited to: <ol style="list-style-type: none"> a. Follow all herbicide label directions, restrictions, and precautions. b. The company responsible for the herbicide applicator must be licensed with Iowa Department of Agriculture and Land Stewardship (IDALS) as a commercial pesticide applicator company. c. The person applying the herbicide must be certified through IDALS as a pesticide applicator in Category 6, Right-of-Way. For herbicide applications that require an aquatic certification, the applicator must also be certified as a pesticide applicator in Category 5, Aquatics. d. Use herbicide and adjuvant products labeled for the application site: <ol style="list-style-type: none"> i. For applications on the primary highway right-of-way, use only products labeled for use on highway rights-of-way or roadsides. ii. For applications to or over water, use only products labeled for corresponding use in aquatic sites, unless intermittent pockets of standing water, such as tire ruts, and the product is labeled for such use. iii. For applications to areas in the water conveyance portion of the ditch that do not contain water at the time of application, use only products labeled for non-irrigation ditch banks or aquatic sites. e. Do not apply any herbicide to or over standing or flowing water unless required coverage is obtained under a National Pollutant Discharge and Elimination System (NPDES) Pesticide Discharge Permit through Iowa DNR. If standing or flowing water is encountered in areas when they need to be sprayed, notify Iowa DOT (Roadside Development) to determine required coverage.
2. Schedule work according to weather conditions and take measures to avoid off-target damage, such as runoff, leaching, drift and volatilization. <ol style="list-style-type: none"> a. Do not spray herbicide 24 hours prior to forecast precipitation that is expected to cause significant runoff conditions. b. For areas with saturated soil, such as ditch bottoms, do not spray herbicide 24 hours prior to forecast precipitation, unless using products labeled for aquatic sites. c. For conventional applications, avoid applications when wind speed exceeds 10 mph. For invert applications, avoid applications when wind speed exceeds 15 mph. d. For conventional foliar applications, use a drift retardant and maintain drift control throughout the application period by adding more to the tank as it breaks down from agitation. e. Avoid spraying volatile products when temperatures are forecast to exceed 85° F within 3 days. f. Check the IDALS Sensitive Crops Directory and do not spray adjacent to a listed operation when wind is blowing towards it.
3. Respond to allegations of any off-target damage attributed to handling and spraying of herbicide.
4. Provide the following documents to the Engineer for approval not less than 2 weeks prior to the application. <ol style="list-style-type: none"> a. A copy of the herbicide and adjuvant labels, including any applicable supplemental labels. b. A copy of the herbicide and adjuvant Material Safety Data Sheets (MSDS.)
5. Have copies of the herbicide and adjuvant labels and MSDSs on-hand and at locations of storage, transport, and application.
6. Schedule work to maximize efficiency of the herbicide application in relation to weather conditions and plant growth stage. Follow any label recommendations given as "for best results." <ol style="list-style-type: none"> a. For weed applications: <ol style="list-style-type: none"> i. To determine if weeds are "actively growing," use as a guideline that there needs to have been at least 1 hour of temperature above 65° F and 1 hour of sun in the day prior to, of, or forecast before a rain the day after the application. ii. For spring applications to thistles, apply after basal leaves of Canada thistles are fully extended, and after rosettes of musk thistle are at least 8 inches diameter, but before flower stage. iii. For fall applications to thistles, apply prior to the second hard freeze of 28° F, unless otherwise listed in the label directions.

231-2 04-21-20
HERBICIDE
<ol style="list-style-type: none"> b. For tree and brush applications: <ol style="list-style-type: none"> i. For foliar applications and cut stump/surface applications with water-soluble products, apply after leaves are fully opened in the spring and prior to leaf discoloration in the fall. ii. For cut stump applications with oil soluble products, do not apply during periods of heavy sap flow. Use as a guideline that heavy sap flow occurs in late winter to early spring when nighttime temperatures below 32° F are followed by daytime temperatures above 32° F with sunny conditions. iii. For cut stump and basal bark applications, add sufficient dye so that treated areas are visible to inspection 7 days after application.
7. Notify the Engineer prior to calibrating, mixing and applying herbicides, including incidental items.
8. Provide copies of daily spray logs to the RCE at the end of each week of spraying (form provided by Iowa DOT).
9. If Contractor does not complete spray item on schedule, the

232-10 04-18-17
EMERALD ASH BORER
Any living, dead, cut or fallen material of the ash (Fraxinus spp.) including trees, nursery stock, logs, firewood, stumps, roots, branches, and composted or uncomposted ash chips can be freely moved within the yellow areas of the most recent Federal EAB Quarantine & Authorized Transit.
https://www.aphis.usda.gov/plant_health/plant_pest_info/emerald_ash_b/downloads/eab_quarantine_map.pdf .
Obtain appropriate Compliance Agreements from USDA APHIS PPQ prior to moving any of the above listed ash articles to areas outside the yellow zone on the map.
For questions, concerns, and general assistance, contact:
USDA APHIS PPQ, Iowa office, 515-414-3295
Or
Iowa Department of Agriculture & Land Stewardship 515-725-1470 Entomology@IowaAgriculture.gov

262-6 10-18-05
UTILITIES (NOT A POINT 25 PROJECT)
This is NOT a POINT 25 project and is not subject to the provisions of IAC 761-115.25.

ARCHAEOLOGICAL SITES
Several archaeological sites are located within the project limits. (13AM604, 13AM581, 13AM528, 13AM82, 13AM603, 13AM510, 13AM337, 13AM588 and 13AM508.) A Vertical Restricted Area with No Access is present from MP 7.54 to MP 9.5. The restriction will prohibit any excavation below the subgrade in the area, except in those areas where culvert work is needed. This project will be monitored by the Iowa DOT archaeologist Brennan Dolan (515-239-1795) as needed and will be in attendance at the preconstruction meeting to discuss the project requirements with the Construction Engineer and the Contractor. The Contractor shall contact him with questions during project construction. Should any new important historical or archaeological material be encountered during construction, project activities shall cease, and the Location and Environment Bureau shall be contacted immediately.

281-1 10-18-16
SECTION 404 PERMIT AND CONDITIONS
Construct this project according to the requirements of U.S. Army Corps of Engineers Nationwide, Permit No. 3. A copy of this permit is available from the Iowa DOT website http://www.envpermits.iowadot.gov/ . The U.S. Army Corps of Engineers reserves the right to visit the site without prior notice.

POLLUTION PREVENTION PLAN

System (NPDES) General Permit No. 2 OR an Iowa Department of Natural Resources (DNR) National Pollutant Discharge Elimination System (NPDES) individual storm water permit. The Contractor shall carry out the terms and conditions of this permit and the Pollution Prevention Plan (PPP).

This Base PPP includes information on Roles and Responsibilities, Project Site Description, Controls, Maintenance Procedures, Inspection Requirements, Non-Storm Water Controls, Potential Sources of Off Right-of-Way Pollution, and Definitions. This plan references other documents rather than repeating the information contained in the documents. A copy of this Base Pollution Prevention Plan, amended as needed during construction, will be readily available for review.

All contractors shall conduct their operations in a manner that controls pollutants, minimizes erosion, and prevents sediments from entering waters of the state and leaving the highway right-of-way. The Contractor shall be responsible for compliance and implementation of the PPP for their entire contract. This responsibility shall be further shared with subcontractors whose work is a source of potential pollution as defined in this PPP.

I. ROLES AND RESPONSIBILITIES

- A. Designer:
 1. Prepares Base PPP included in the project plan.
 2. Prepares Notice of Intent (NOI) submitted to Iowa DNR.
 3. Is signature authority on the Base PPP. If consultant designed, signature from Contracting Authority is also required.
- B. Contractor:
 1. Signs a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP. All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
 2. Designates a Water Pollution Control Manager (WPCM), who has the duties and responsibilities as defined in Section 2602 of the Standard Specifications.
 3. Submits an Erosion Control Implementation Plan (ECIP) and ECIP updates according to Section 2602 of the Standard Specifications.
 4. Installs and maintains appropriate controls. This work may be subcontracted as documented through Subcontractor Request Forms (Form 830231).
 5. Supervises and implements good housekeeping practices according to Paragraph III, C, 2.
 6. Conducts joint required inspections of the site with inspection staff. When Contractor is not mobilized on site, Contractor may delegate this responsibility to a trained or certified subcontractor. Contracting Authority also may waive joint inspection requirement during winter shutdown. In both circumstances, WPCM (or trained or certified delegate from the Contractor) is still responsible to review and sign inspection reports.
 7. Complies with training and certification requirements of Section 2602 of the Standard Specifications.
 8. Submits amended PPP site map according to Section 2602 of the Standard Specifications.
- C. Subcontractors:
 1. Sign a co-permittee certification statement adhering to the requirements of the NPDES permit and this PPP if: responsible for sediment or erosion controls; involved in land disturbing activities; or performing work that is a source of potential pollution as defined in this PPP. Subcontracted work items are identified in Subcontractor Request Forms (Form 830231). All co-permittees are legally required under the Clean Water Act and the Iowa Administrative Code to ensure compliance with the terms and conditions of this PPP.
 2. Implement good housekeeping practices according to Paragraph III, C, 2.
- D. RCE/Project Engineer:
 1. Is Project Storm Water Manager.
 2. On projects where DOT is the Contracting Authority, is current with erosion control training or certification.
 3. Takes actions necessary to ensure compliance with storm water requirements including, where appropriate, issuing stop work orders, and directing additional inspections at construction project sites that are experiencing problems with achieving permit compliance.
 4. Orders the taking of measures to cease, correct, prevent, or minimize the consequences of non-compliance with the storm water requirements of the Applicable Permit.
 5. Supervises all work necessary to meet storm water requirements at the Project, including work performed by contractors and subcontractors.
 6. Requires employees, contractors, and subcontractors to take appropriate responsive action to comply with storm water requirements, including requiring any such person to cease or correct a violation of storm water requirements, and to order or recommend such other actions as necessary to meet storm water requirements.
 7. Is familiar with the Project PPP and storm water site map.
 8. On projects where DOT is Contracting Authority, is responsible for periodically monitoring inspection reports to determine whether deficiencies identified in inspection reports were adequately and timely addressed, and if not, has the authority and responsibility to direct immediate actions to correct the deficiencies.
 9. Is the point of contact for the Project for regulatory officials, Inspector, contractors, and subcontractors regarding storm water requirements.
 10. Is signature authority on Notice of Discontinuation.
 11. Maintains an up-to-date record of contractors, subcontractors, and subcontracted work items through Subcontractor Request Forms (Form 830231).
 12. Makes information to determine permit compliance available to the DNR upon their request.
- E. Inspector:
 1. Updates PPP through fieldbook entries and storm water site inspection reports if there is a change in design, construction, operation, or maintenance which has a significant effect on the discharge of pollutants from the project.
 2. Makes information to determine permit compliance available to the DNR upon their request.
 3. Conducts joint required inspections of the site with the contractor/subcontractor.
 4. Completes an inspection report after each inspection.
 5. Is signature authority on storm water inspection reports.

II. PROJECT SITE DESCRIPTION

- A. This Pollution Prevention Plan (PPP) is for the construction of HMA Resurfacing.
- B. This PPP covers approximately 224 acres with an estimated 41 acres being disturbed. The portion of the PPP covered by this contract has 41 acres disturbed.
- C. The PPP is located in an area of one soil association Downs-Fayette-Nordness. The estimated weighted average runoff coefficient number for this PPP after completion will be 0.35.
- D. Storm Water Site Map is located in the R sheets. Proposed slopes are shown in cross sections, details, or standard road plans. Supplemental information is located in the Tabulations in the C or CE sheets.
- E. The base storm water site map is amended by contract modifications and progress payments (fieldbook entries) of completed erosion control work. Also, due to project phasing, erosion and sediment controls shown on project plans may not be installed until needed, based on site conditions. For example, silt fence ditch checks will typically not be installed until the ditch has been installed. Installed locations may also be modified from tabulation locations by field staff. Installed locations will be

POLLUTION PREVENTION PLAN

documented by fieldbook entries and amended PPP site map.
F. Runoff from this work will flow into Paint Creek and Yellow River.

III. CONTROLS

- A. The Contractor's ECIP specified in Article 2602.03 of the Standard Specifications for accomplishment of storm water controls should clearly describe the intended sequence of major activities, and for each activity define the control measure and the timing during the construction process that the measure will be implemented.
- B. Preserve vegetation in areas not needed for construction.
- C. Sections 2601 and 2602 of the Standard Specifications define requirements to implement erosion and sediment control measures. Actual quantities used and installed locations may vary from the Base PPP and amendment of the plan will be documented via fieldbook entries, amended PPP site map, or by contract modification. Additional erosion and sediment control items may be required as determined by the inspector and/or contractor during storm water site inspections. If the work involved is not applicable to any contract items, the work will be paid for according to Article 1109.03 paragraph B of the Standard Specifications.
 - 1. EROSION AND SEDIMENT CONTROLS
 - a. Stabilization Practices
 - 1) Site plans will ensure that existing vegetation or natural buffers are preserved where attainable and disturbed portions of the site will be stabilized.
 - 2) Initialize stabilization of disturbed areas immediately after clearing, grading, excavating, or other earth disturbing activities have:
 - a) Permanently ceased on any portion of the site, or
 - b) Temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days.
 - 3) Staged permanent and/or temporary stabilizing seeding and mulching shall be completed as the disturbed areas are completed. Incomplete areas shall be stabilized according to paragraph III, C, 1, a, 2, b above.
 - 4) Permanent and Temporary Stabilization practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation (105-4) in the C or R sheets.
 - 5) Preservation of existing vegetation within right-of-way or easements will act as vegetative buffer strips.
 - 6) Preservation of topsoil: Bid items to be used for this project are located in the Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets. Additional information may be found in the Tabulations in the C or T Tabulation sheets, or is referenced in Section 2105 of the Standard Specifications.
 - b. Structural Practices
 - 1) Structural practices will be implemented to divert flows from exposed soils and detain or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Additionally, structural practices may include: silt basins that provide 3600 cubic feet of storage per acre drained or equivalent sediment controls, outlet structures that withdraw water from surface when discharging basins, and controls to direct storm water to vegetated areas.
 - 2) Structural practices to be used for this project are located in the storm water site map, Estimated Project Quantities (100-0A, 100-1A, or 100-1C), and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the devices to be used on this project can be found on the B or R sheets or are referenced in the Standard Road Plans Tabulation (105-4) located in the C or R sheets.
 - c. Storm Water Management

Measures shall be installed during the construction process to control pollutants in storm water discharges that will occur after construction operations have been completed. This may include velocity dissipation devices at discharge locations and along length of outfall channel as necessary to provide a non-erosion velocity flow from structure to water course. If included with this project, these items are located in the storm water site map and Estimated Project Quantities (100-0A, 100-1A, or 100-1C) and Estimate Reference Information (100-4A) located in the C or R sheets, as well as all other item specific Tabulations. Typical drawings detailing construction of the practices to be used on this project are referenced in the Standard Road Plans Tabulation. The installation of these devices may be subject to Section 404 of the Clean Water Act.
 - 2. OTHER CONTROLS

Contractor disposal of unused construction materials and construction material wastes shall comply with applicable state and local waste disposal, sanitary sewer, or septic system regulations. In the event of a conflict with other governmental laws, rules and regulations, the more restrictive laws, rules or regulations shall apply.

 - a. Vehicle Entrances and Exits - Construct and maintain entrances and exits to prevent tracking of sediments onto roadways.
 - b. Material Delivery, Storage and Use - Implement practices to prevent discharge of construction materials during delivery, storage, and use.
 - c. Stockpile Management - Install controls to reduce or eliminate pollution of storm water from stockpiles of soil and paving.
 - d. Waste Disposal - Do not discharge any materials, including building materials, into waters of the state, except as authorized by a Section 404 permit.
 - e. Spill Prevention and Control - Implement chemical spill and leak prevention and response procedures to contain and clean up spills and prevent material discharges to the storm drain system and waters of the state.
 - f. Concrete Residuals and Washout Wastes - Waste shall not be discharged to a surface water and is not allowed to adversely affect a water of the state. Designate temporary concrete washout facilities for rinsing out concrete trucks. Provide directions to truck drivers where designated washout facilities are located. Designated washout areas should be located at least 50 feet away from storm drains, streams or other water bodies. Care should be taken to ensure these facilities do not overflow during storm events.
 - g. Concrete Grooving/Grinding Slurry - Do not discharge slurry to a waterbody or storm drain. Slurry may be applied on foreslopes or removed from the project.
 - h. Vehicle and Equipment Storage and Maintenance Areas - Perform on site fueling and maintenance in accordance with all environment laws such as proper storage of onsite fuels and proper disposal of used engine oil or other fluids on site. Employ washing practices that prevent contamination of surface and ground water from wash water. Wash waters must be treated in a sediment basin or alternative control that provides equivalent or better treatment prior to discharge.
 - i. Litter Management - Ensure employees properly dispose of litter. Minimize exposure of trash if exposure to precipitation or storm water would result in a discharge of pollutants.
 - j. Dewatering - Properly treat water to remove suspended sediment before it re-enters a waterbody or discharges off-site. Measures are also to be taken to prevent scour erosion at dewatering discharge point.
- 3. APPROVED STATE OR LOCAL PLANS

During the course of this construction, it is possible that situations will arise where unknown materials will be encountered. When such situations are encountered, they will be handled according to all federal, state, and local regulations in effect at the time.

IV. MAINTENANCE PROCEDURES

POLLUTION PREVENTION PLAN

The Contractor is required to maintain all temporary erosion and sediment control measures in proper working order, including cleaning, repairing, or replacing them throughout the contract period. This shall begin when the features have lost 50% of their capacity.

V. INSPECTION REQUIREMENTS

- A. Inspections shall be made jointly by the Contractor and the Contracting Authority's inspector at least once every seven calendar days. Storm water site inspections will include:
 1. Date of the inspection.
 2. Summary of the scope of the inspection.
 3. Name and qualifications of the personnel making the inspection.
 5. Review of erosion and sediment control measures within disturbed areas for the effectiveness in preventing impacts to receiving waters.
 6. Major observations related to the implementation of the PPP.
 7. Identification of corrective actions required to maintain or modify erosion and sediment control measures.
- B. Include storm water site inspection reports in the Amended PPP. Incorporate any additional erosion and sediment control measures determined as a result of the inspection. Immediately begin corrective actions on all deficiencies found within 3 calendar days of the inspection and complete within 7 calendar days following the inspection. If it is determined that making the corrections less than 72 hours after the inspection is impracticable, it should be documented why it is impracticable and indicate an estimated date by which the corrections will be made.

VI. NON-STORM WATER DISCHARGES

This includes subsurface drains (i.e. longitudinal and standard subdrains) and slope drains. The velocity of the discharge from these features may be controlled by the use of headwalls or blocks, Class A stone, erosion stone or other appropriate materials. This also includes uncontaminated groundwater from dewatering operations, which will be controlled as discussed in Section III of the PPP.

VII. POTENTIAL SOURCES OF OFF RIGHT-OF-WAY (ROW) POLLUTION


Silts, sediment, and other forms of pollution may be transported onto highway right-of-way (ROW) as a result of a storm event. Potential sources of pollution located outside highway ROW are beyond the control of this PPP. Pollution within highway ROW will be conveyed and controlled per this PPP.

VIII. DEFINITIONS


- A. Base PPP - Initial Pollution Prevention Plan.
- B. Amended PPP - Base PPP amended during construction. May include Plan Revisions or Contract Modifications for new items, storm water site inspection reports, fieldbook entries made by the inspector, amended PPP site map by the Contractor, ECIP, NOI, co-permittee certifications, and Subcontractor Request Forms. Items amending the PPP are stored electronically and are readily available upon request.
- C. Fieldbook Entries - This contains the inspector's daily diary and bid item postings.
- D. Controls - Methods, practices, or measures to minimize or prevent erosion, control sedimentation, control storm water, or minimize contaminants from other types of waste or materials. Also called Best Management Practices (BMPs).
- E. Signature Authority - Representative authorized to sign various storm water documents.

CERTIFICATION STATEMENT

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.



 Signature



 Printed or Typed Name

 Signature

EXISTING PAVEMENT

No.	Location					Year	Type	Project Number	Surface		Base		Subbase		Removal		Coarse Aggregate			Reinforcement	Remarks	
	County	Route	Dir. of Travel	Begin Ref. Loc. Sign	End Ref. Loc. Sign				Type	Depth IN	Type	Depth IN	Type	Depth IN	Type	Depth IN	Source	Type	Durability Class			Type
3	76			7.54	11.32	1937	ACC(4)	FN-347ABC	BSC	1	SAS	4										
				7.54	11.32	1972	ACC(4)	FN-76-2(8)	BAC	4.5												
				7.54	11.32	1991	ACC(4)	FN-76-2(18)--21-03	AAC	2	BAC	2.5			MIL	1	MCCABE QUARRY	C.LST.				
				7.54	11.32	2013	ACC(4)	MP-076-2(707)9--76-03	AAC	2												
3	76			11.32	12.38	1964	ACC(4)	FN-347	BAC	3	ATB	7	SAS	6								
				11.32	12.38	1994	ACC(4)	STP-76-2(19)--2C-03	AAC	2	BAC	2			MIL	1	ROSSVILLE	C.LST.				
				11.32	12.38	2013	ACC(4)	MP-076-2(707)9--76-03	BSC													
3	76			12.38	15.33	1964	ACC(4)	FN-347	BAC	3	ATB	7	SAS	6								
				12.38	15.33	1995	ACC(4)	STPN-76-2(24)--2J-03	BAC	2	AAC	2					BERNHARD QUARRY	C.LST.				
				12.38	15.33	2013	ACC(4)	MP-076-2(707)9--76-03	BSC													
				15.33	16.75	1964	ACC(4)	FN-347	BAC	3	ATB	7	SAS	6								
				15.33	16.75	1994	ACC(4)	STP-76-2(19)--2C-03	ACC	2	BAC	2			MIL	1	ROSSVILLE	C.LST.				
3	76			16.75	19.78	1964	ACC(4)	FN-347	BAC	3	ATB	7	SAS	6								
				16.75	19.78	1995	ACC(4)	STPN-76-2(24)--2J-03	BAC	2	AAC	2					BERNHARD QUARRY	C.LST.				
				16.75	19.78	2013	ACC(4)	MP-076-2(707)9--76-03	BSC													

NOTCHES AND RUNOUTS FOR RESURFACING

Refer to PR-201 and PR-202.

① Bid item. Applies only to Types 'N1' and 'N3' on PR-202. Refer to 100-25 for remaining values.

Location Station	Type of Notch or Runout	(S)	(I)	(DI)	(L)	(M)	Pavement Scarification SY	Remarks
		IN	IN	IN	FT	IN		
202+35.36	Type 'N5'	2.0	1.0		150.0			BOP
220+92.98	Type 'N5'	2.0	1.0		150.0			Bridge approach
226+20.02	Type 'N5'	2.0	1.0		150.0			Bridge approach
239+17.00	Type 'N3'	2.0	1.0		12.0		8.0	Effigy Mounds Entrance
397+03.00					100.0			Equation. See Typical MK-5
819+38.00	Type 'N3'	1.5			37.5		25.0	sideroad X52
546+67.00	Type 'R1'	1.5			37.5			sideroad B25
425+50.00	Type 'R1'	1.5			15.0			PCC Ent. Lt.
376+50.00	Type 'N4'	1.5	1.5		150.0			EOP
							33.0	total

FORESLOPE FLATTENING AND DRAINAGE STRUCTURES BY ROAD CONTRACTOR (MAINLINE PIPES)

Refer to Standard Road Plans DR-121, DR-122, and DR-213.


* Not a bid item

Existing Information		New Information		Length of New Const. LF	Flow Line Elevations		Dimensions				Removal and Reinstallation of Culvert Aprons and Pipes				New Apron No.		Apron Guard* (DR-213) NO.	Type 'C' Connections (DR-122) TYPE NO.		Connected Pipe Joint* (DR-121) TYPE	Embank.- In-Place CY	Class 20 CY	Remarks
Location	Size and Type of Culvert	Size IN	Type of Culvert		LEFT	RIGHT	Total (LF)		Extensions (LF)		Aprons		Culvert Sections		IN	OUT		NO.	TYPE				
				LEFT			RIGHT	LEFT	RIGHT	LEFT	RIGHT	NO.*	FT	NO.*			FT						
Section A	Mainline																						
239+75	24"RCP																						
276+00	5'x5' RCB																						
284+55	4'x4'x47' RCB																						
287+20	5'x4'x47' RCB																						
329+50	2'X2' RCB																						
340+24	24"RCP			12																			
344+35	2'x2' RCB																						
367+00	24"RCP	24	RCB	6																			
378+00	24"RCP	24	liner pipe	66																			
Section A	Sideroad																						
363+05, 30' Lt.	18"x60' HDPE		Unclassified																				
Section B	Mainline																						
804+46	2'x2' RCB																						
774+88	6'X6'x243.6' RCB	66"	Liner Pipe	244																			
795+31	2'x2' RCB																						
652+11	24" RCP																						
602+79	2'x2'RCB 24" extension																						
516+78	24" RCP																						
508+79	4'X5' RCB																						
467+44	4'x7' RCB																						
436+10	2'x2'RCB 30" extension																						
410+29	2'x2'70' RCB 30" ext.																						
389+51	2'x2'RCB																						
384+90	24" RCP	24	Liner Pipe	70																			

- A: Replacing one section Lt. and replace one section Rt.
- B: Replacing one section Rt. See Tabs. 110-2 & 110-18.
- C: See Cleanout Pipe Culvert. See Typical MK-7.
- D: Type 'C' is for RCB joint repair. 23' Lt. See Tabs 102-6C, 110-17, & 100-19.
- E: Type 'C' is for 3 RCB joint repairs. 13' Lt., 5' Rt., & 19' Rt. See Tab 100-19.
- F: Type 'C' is for RCB joint repair. 23' Rt.
- G: Type 'C' is for RCB joint repair. 30' Rt., See Tab. 100-19.
- H: Type 'C' is for RCB joint repair. 18' Lt.
- I: Type 'C' is for RCB joint repair. 29' Rt.
- J: Type 'C' is for 2 RCB joint repairs. 9' Lt. & 9' Rt.
- K: Type 'C' is for RCB joint repair. 12' Rt. See Tabs. 100-23 & 100-17.
- L: See Tab.100-19
- M: Type 'C' is for RCB to flume joint repair. See Tab. 110-17
- N: Type 'C' is for RCB joint repair. 18' Lt. & 34' Rt. See Tabs 100-23 & 102-6C.

SILT FENCES FOR DITCH CHECKS

Possible Standard: EC-201



* The functional height used in the volume equation is 85% of effective height. Effective height is 1.58 feet as shown on EC-201.
 * Volume equation: $[0.5 * Spacing * (0.5 * H^2 * FS + DW * H + 0.5 * H^2 * BS)]$

Basin No.	Type	Location Station	Side	Bid Items			Stormwater Storage Volume Summary				Remarks
				Installation LF	Maintenance LF	Removal LF	Foreslope FS:1	Backslope BS:1	Ditch Width FT	Avg.% Slope Ditch Grade	
	1	329+63.0	rt	24.0	24.0	24.0	3.0	4.0	10.0	7.2%	A
	1	367+00.0	rt	24.0	24.0	24.0	3.0	4.0	10.0	5.9%	

A: See Tabulation 104-13.

TABULATION OF SILT FENCES

Refer to EC-201

Location			Length LF	Remarks
Begin Station	End Station	Side		
328+88.00	330+38.00	Rt	150.0	RCB 329+63 tab. 104-13
344+30.00	344+80.00	Lt	150.0	RCB 344+33 tab. 104-13
			300.0	total

FULL-DEPTH PATCHES

Possible Standards: PR-101, PR-102, PR-103, PR-104, PR-105, and PR-140.

Count	Location			Dimension			PCC Patches				HMA Patches	Composite HMA	Subbase Patches	Subbase Patch w/ 'EF' Joint	Patch Subdrain	'CD' Joints	'CT' Joints	'EF' Joints	Anchor Lugs Removal	Remarks		
	Station	Reference Location Sign	Lane	Length	Width	Patch Thickness	With Dowels	Without Dowels	C R C	Ramp with Dowels												
							PR-103	PR-102	PR-104	PR-105												
			L, R, or B	FT	FT	IN	SY	SY	SY	SY	SY	TON	SY	SY	PR-101 or PR-140	No.	No.	No.	No.	No.		
	Section A																					
1	329+50.00			R	14.0	7.0	9.0													See Tab. 104-13		
1	340+24.00			R	24.0	12.0	9.0													See Tab. 104-13		
1	344+35.00			L	12.0	8.0	9.0													See Tab. 104-13		
1	A	MP8			20.0	12.0	9.0	26.7												Yellow River Bridge S Approach		
1	A	MP8			20.0	12.0	9.0	26.7												Yellow River Bridge S Approach		
	Section B																					
2	467+44.00			B	34.0	27.0	13.0													See Tab. 104-13		
1	602+79.00			L	36.0	9.0	14.0													See Tab. 104-13		
8								53.4														totals
A: See sheet U.1 for location																						

PERIMETER, SLOPE AND DITCH CHECK SEDIMENT CONTROL DEVICES

Possible Standards: EC-204

Location			Perimeter and Slope			Ditch Check		Remarks
Begin Station	End Station	Side	Length of Installation			Length of Installation		
			9 inch Dia	12 inch Dia	20 inch Dia	12 inch Dia	20 inch Dia	
			LF	LF	LF	LF	LF	
		R		160				A, Guardrail
		L		160				A, Guardrail
		R		200				A, Guardrail
		L		240				A, Guardrail
239+82.00	239+82	Lt		120				See Tabulation 104-13 and Road Design Detail 570-11
284+33.00	284+33	Both		240				See Tabulation 104-13 and Road Design Detail 570-11
287+20.00	287+20	Both		240				See Tabulation 104-13 and Road Design Detail 570-11
340+25.00	340+25	Both		240				See Tabulation 104-13 and Road Design Detail 570-11
362+85.00	363+25.00	Lt				120.0		See Tabulation 104-13
378+00.00		Both		240				See Tabulation 104-13 and Road Design Detail 570-11
384+90.00		Both		240				See Tabulation 104-13 and Road Design Detail 570-11
389+51.00		Both		240				See Tabulation 104-13
410+29.00		rt		120				See Tabulation 104-13
436+10.00		Lt		120				See Tabulation 104-13
467+44.00		Both		240				See Tabulation 104-13 and Road Design Detail 570-11
508+79.00		Lt		120				See Tabulation 104-13 and Road Design Detail 570-11
516+78.00		Both		240				See Tabulation 104-13 and Road Design Detail 570-11
652+11.00		Lt		120				See Tabulation 104-13
774+88.00		Both		240				See Tabulation 104-13
795+27.00	795+67.00	Rt.		120				See Tabulation 104-13 and Road Design Detail 570-11
804+40.00		Lt		120				See Tabulation 104-13 and Road Design Detail 570-11
				3520		120.0		total
A: See sheet U.1 for additional information. To be placed at toe of foreslope.								

ROCK EROSION CONTROL

Refer to EC-301 and Detail 570-8

Location				L	W	Rock Erosion Control (REC)					Material Bid Quantities			Remarks
Road Identification	Begin Station	End Station	Side			Type 1	Type 2	Type 3	Type 4	Type 5	Eng. Fabric	Class E Revetment	Erosion Stone	
						Rock Ditch Check	Rock Ditch	Rock Flume	Rock Splash Basin	Rock Slope Protection				
IA 76 Section A	239+82.00		Lt.	8	30					27.0	25.2		See Tab. 104-13	
	276+00.00		Lt.	12	30			x		71.0	50.4		5x5 RCB	
	329+63.00		Rt.	10	24				x	24.0	12.6		See Tab. 104-13	
	602+62.00		Rt.	10	8				x	8.0	4.2		See Tab. 104-23	
	652+16.00		Rt.	5	40			x		40.0	21.0		See Tab. 104-23	
										170.0	113.4		totals	

REMOVAL OF EXISTING STRUCTURES

Location	Description	Remarks
Section A		
239+75, Lt.	two 30" flume sections	replacing flume with class E Rip Rap
340+24	24" RCP	replace one pipe section each side.
367+00	24" RCP	replace one pipe section Lt. side.
Section B		
602+79	24" RCP extension apron	replace apron

CLEARING AND GRUBBING

Location		Work and Material Type	Trees, Stumps, and Logs and Down Timber Material Diameters													All Other Materials		Estimated Quantities			Remarks
Station to Station or Ref. Loc. Sign to Ref. Loc. Sign or Description	Direction of Travel		3"-6"	>6"-9"	>9"-12"	>12"-15"	>15"-18"	>18"-24"	>24"-30"	>30"-36"	>36"-42"	>42"-48"	>48"-60"	>60"-72"	>72"	Length	Width	Units	Area	Herbicide Application	
			FT	FT	Units	Acres	Each	FT	FT	Units	Acres	Each									
202+35.6 to 220+00.0 Lt. Side	SB	Trees - Clearing														1764.4	15.0		0.6		A
243+00.0 to 253+81.3 Rt. Side	NB	Trees - Clearing														1081.3	15.0		0.4		A, Equation
253+67.2 to 273+25.0 Rt. Side	NB	Trees - Clearing														1957.8	15.0		0.7		A, Equation
291+00.0 to 326+85.2 Lt. Side	SB	Trees - Clearing														3585.2	15.0		1.2		A, Equation
326+99.0 to 329+28.0 Lt. Side	SB	Trees - Clearing														229.0	15.0		0.1		A, Equation
292+00.0 to 329+28.0 Rt. Side	NB	Trees - Clearing														3728.0	15.0		1.3		A
602+62 RCB Rt. Outlet	SB	Trees - Clearing and Grubbing			1		1											20.2			
795+47 RCB Flume Outlet Lt.	NB	Trees - Clearing		2		3			1									22.0		6	B
																		42.2	4.3		totals

A: Clearing will be defined as a 15 foot wide path measured 25 feet to 40 feet from centerline of roadway. Do not clear beyond existing right of way. Clearing to be discussed with Area Maintenance Supervisor at Precon meeting. All clearing measured by area to be included in the lump sum herbicide application bid item.

B: Protect RCB flume.



SHOULDERS

- ① Lane(s) to which the shoulder is adjacent.
- ② See Typ. 7156, 7157, or 7158.
- ③ Bid Item.
- ④ Applies only for Paved Shoulders constructed on project with existing granular shoulders.
- ⑤ Bid Item. Typ. 7156, 7157, or 7158.
- ⑥ Does not include shrink.

Calculations assume a HMA unit weight (lbs/cf) of 145, a Special Backfill unit weight (lbs/cf) of 140, and a Granular Shoulder unit weight (lbs/cf) of 140.

Road Identification	Direction Of Traffic	Location		Side	P Width FT	P _{SG} Width FT ②	G Width FT	L Length FT	Class 13 Excavation CY ③	Hot Mix Asphalt		Binder TONS ③	Paved Shoulder SY	9" Paved Shoulder at Guardrail SY ⑤	Reinforced Paved Shoulder SY ③	Special Backfill				Subbase CY ③	Granular Shoulder		Earth Shoulder Construction Alternates			Remarks						
		Station to Station	Station to Station							HMA Alternate						PCC Alternate		TON ③	TON/STA		TON ③	TON/STA	CY ③	TON ③	TON/STA		STA ③	HMA CY ⑥	PCC CY ⑥			
										TON ③	TON/STA					TON ③	TON/STA															
Section A																																
IA 76	SB	202+35.36	220+72.90	Lt	2.0			1837.5	68.1	110.6	6.0	6.6	408.3																B			
	NB	202+35.36	220+61.80	Rt	2.0			1826.4	67.6	109.9	6.0	6.6	405.9																			
	SB	227+22.90	233+93.00	Lt.	2.0			670.1	24.8	40.3	6.0	2.4	148.9																			
	NB	226+62.00	233+93.00	Rt	2.0			731.0	27.1	44.0	6.0	2.6	162.4																			
	NB	239+60.00	244+50.00	Rt	2.0			490.0	18.1	29.5	6.0	1.8	108.9																			
	Both	244+50.00	253+81.30	Both	2.0			8235.2	610.0	991.1	12.0	59.5	1830.0																			
	Both	253+67.20	326+85.20	Both	2.0			7318.0	542.1	880.7	12.0	52.8	1626.2																			
	Both	326+99.00	346+73.50	Both	2.0			1974.5	146.3	237.6	12.0	14.3	438.8																			
	Both	348+36.90	387+64.60	Both	2.0			3927.7	290.9	472.7	12.0	28.4	872.8																			
	Both	388+31.70	397+03.00	Both	2.0			871.3	64.5	104.9	12.0	6.3	193.6																			
								sub-total (63)	1859.6	3021.3		181.3																				
Section B																																
IA 76	NB	835+00.00	823+43.00	Lt	4.0			18934.4	1634.0	3198.5	16.9	191.9	8415.3																	A		
	NB	818+28.00	699+72.76	Lt	4.0			11855.2	1023.1	2002.6	16.9	120.2	5269.0																			
	NB	699+68.38	605+01.60	Lt	4.0			9466.8	816.9	1599.2	16.9	96.0	4207.5																			
	NB	604+37.07	547+52.00	Lt	4.0			5685.1	490.6	960.4	16.9	57.6	2526.7																	B25		
	NB	545+77.00	456+14.61	Lt	4.0			8962.4	773.4	1514.0	16.9	90.8	3983.3																			
	NB	456+22.53	376+50.00	Lt	4.0			7972.5	688.0	1346.8	16.9	80.8	3543.3																			
	SB	835+00.00	699+72.76	Rt	4.0			13527.2	1167.4	2285.1	16.9	137.1	6012.1																			
	SB	699+68.38	605+01.60	Rt	4.0			9466.8	816.9	1599.2	16.9	96.0	4207.5																			
	SB	604+37.07	456+14.61	Rt	4.0			14822.5	1279.1	2503.9	16.9	150.2	6587.8																			
	SB	456+22.53	376+50.00	Rt	4.0			7972.5	688.0	1346.8	16.9	80.8	3543.3																			
								sub-total (64)	9377.4	18356.3		1101.4																				
	IA 76	NB	220+61.80	221+57.80	Rt			96.0	26.2				104.6																	C		
	9" guardrail	SB	220+72.90	221+66.70	Lt			93.8	25.6				102.3																	C		
	pavement	NB	225+89.30	226+62.00	Rt			72.7	21.2				84.7																	C		
		SB	225+99.80	227+22.90	Lt			123.1	42.8				171.4																	C		
								sub-total (63)																								
								385.6	115.8	0.0		0.0	463.0																			
	A: Turn Lane								11352.8	21377.6		1282.7																				
	B: Bridge																															
	C: Excavated material from shoulder construction may be used for embankment.																															

HMA PAVEMENT



- ① Does not include raised island area or curb. Refer to tabulation 112-4 for quantities.
- ② Refer to PV-410, PV-411, PV-412, and PV-414.
- ③ Quantity includes Pavement Header.

Calculations assume a surface course unit weight (lbs/cf) of 147, an intermediate course unit weight (lbs/cf) of 147, a base course unit weight (lbs/cf) of 150, and a special backfill unit weight (lbs/cf) of 140.

Location			Mainline			Area ③								Hot Mix Asphalt Pavement										Bid Items	Pavement Scarification	Remarks	
Road Identification	Direction of Travel	Station to Station	Width	Length	Area	Area ③								Surface				Intermediate		Interlayer\CIPR		Binder					Special Backfill
						A ①	B	C	D	E	F ②	G	H	Surface	Intermediate	Interlayer\CIPR	Surface	Intermediate	Interlayer								
			FT	FT	SY	SY	SY	SY	SY	SY	SY	SY	SY	TONS	SY	TONS	SY	TONS	SY	TONS	TONS	TONS	CY	SY	SY		
Section A	both	202+35.36 - 220+92.98	28.0	1857.6	5779.3									637.2	5779.3			325.1		38.2					26.0		4953.7
	both	226+20.02 - 233+40.00	28.0	720.0	2239.9									247.0	2239.9			126.0		14.8					10.1		1919.9
	nb	233+40.00 - 239+60.00		620.0										70.6	640.0			36.0		4.2					2.9		1653.3
	sb	233+40.00 - 245+00.00		1160.0				640.0						158.1	1434.0			80.7		9.5					6.5		3093.3
	both	233+40.00 - 239+60.00	24.0	620.0	1653.3									182.3	1653.3			93.0		10.9					7.4		1653.3
	both	239+60.00 - 245+00.00	26.0	540.0	1560.0									172.0	1560.0			87.8		10.3					7.0		1440.0
	both	245+00.00 - 253+81.30	28.0	881.3	2741.8									302.3	2741.8			154.2		18.1					12.3		2350.1
	both	253+67.20 - 326+85.20	28.0	7318.0	22767.1									2510.1	22767.1			1280.7		150.6					102.5		19514.7
	both	326+99.00 - 346+73.50	28.0	1974.5	6142.9									677.3	6142.9			345.5		40.6					27.6		5265.3
	both	348+36.90 - 387+64.60	28.0	3927.7	12219.5									1347.2	12219.5			687.3		80.8					55.0		10473.9
	both	388+31.70 - 397+03.00	28.0	871.3	2710.7									298.9	2710.7			152.5		17.9					12.2		2323.5
Subtotal (63)														6602.7				3368.7		396.2					269.5		54641.1
Section B	both	835+00.00 - 823+76.00	32.0	1124.0	3996.4									330.5	3996.4	330.5	3996.4		3996.4		19.8				19.8		
	lt	823+76.00 - 822+76.00		100.0										5.5	66.7	5.5	66.7			0.3					0.3		
	lt	822+76.00 - 815+70.00		806.0				66.7						77.9	941.5	77.9	941.5		941.5	4.7					4.7		
	both	823+76.00 - 699+72.76	32.0	12403.2	44100.4									3646.6	44100.4	3646.6	44100.4		44100.4	218.8					218.8		
	both	699+68.38 - 605+01.60	32.0	9466.8	33659.7									2783.2	33659.7	2783.2	33659.7		33659.7	167.0					167.0		
	both	604+37.07 - 456+14.61	32.0	14822.5	52702.1									4357.8	52702.1	4357.8	52702.1		52702.1	261.5					261.5		
	both	456+22.53 - 376+50.00	32.0	7972.5	28346.8									2343.9	28346.8	2343.9	28346.8		28346.8	140.6					140.6		
Subtotal=75% (63)														10159.0		10159.0		122810.2		609.5					609.5		
Subtotal=25% (64)														3386.3		3386.3		71639.3		203.2					203.2		
Total (63)														16761.7		10159.0		3368.7		122810.2		1005.7			609.5		109282.1
Total (64)														3386.3		3386.3		71639.3		203.2					203.2		
Totals														20148.1		13545.3		3368.7		194449.4		1208.9			812.7		269.5

1/13/2022 4:37:13 PM dn1e c:\pw_work\pmain\dn1e\d1191228\03076063C_.xls

STEEL BEAM GUARDRAIL AT CONCRETE BARRIER OR BRIDGE RAIL END SECTION

Possible Standards: BA-200, BA-201, BA-202, BA-205, BA-206, BA-210, BA-211, BA-221, BA-225, BA-250, BA-260, LS-625, LS-626, LS-630, LS-635, SI-172, SI-173 and SI-211.

- ① Lane(s) to which the obstacle is adjacent.
- ② Not a bid item. Incidental to guardrail installation.

No.	Direction of Traffic	Location			Layout Lengths				Long-Span System		Delineators and Object Markers ②				Bid Items										Remarks						
		Side O = Outside M = Median	Station	Offset	BA-250, BA-260, LS-630, or LS-635				STATION	TYPE	SI-211	Delineator SI-172	Object Marker SI-173			Bolted End Anchor *	Post Adapter	Steel Beam Guardrail	Barrier Transition Section	BA-250 or LS-630				BA-260 or LS-635							
					VT1	VF	VT2	ET					Type 1	Type 2	Type 3					End Terminal				Barrier Transition Section		End Terminal					
					BA-211								White	OM2-2	OM3-L					OM3-R	BA-202	BA-210	BA-200	BA-201		Tangent	Flared	Tangent	Flared	BA-221	BA-225
					FT	LF	LF	LF					LF	EACH	EACH					EACH	EACH	TYPE	EACH	EACH		EACH	EACH	EACH	EACH	EACH	EACH
SB	O	221+57.00	10.5	28.125					3			1	1	A	1	6.25							1	1							
NB	O	221+45.90	10.5	28.125					3			1	1	A	1	6.25							1	1							
SB	O	225+67.10	10.5	53.125					3			1	1	A	1	12.50		1	1												
NB	O	225+56.00	10.5	37.500					3			1	1	A	1			1	1												
														4		25.00		2	2					2	2	totals					

* Contractor will need to drill new bolt holes for new bolt pattern for BA-202.

SCOUR PROTECTION OR ROCK FLUME FOR BRIDGE END DRAIN

Refer to Standard Road Plan DR-401 and DR-402

Location		Bid Items			PCC Paved Shoulder			Scour Protection (DR-401)			Rock Flume (DR-402)			Remarks
Bridge Station	Bridge Corner	Distance DI-1 or DI-2	PCC Paved Shoulder	Bridge End Drain	Panel Required	Polymer Grid	Modified Subbase	Special Ditch Control, Wood Excelsior Mat	Turf Reinforced Mat (TRM), Type 2	Transition Mat	Macadam Stone Base	Engineering Fabric	Erosion Stone	
FT	SY	TYPE	A B C or D	SY	TONS	EC-101	EC-104	EC-105	TONS	SY	TONS	SY	TONS	
223+56.50	NE	32.3	43.3	DR-402	A,D						1.100	34.3	24.800	
223+56.50	NW	32.3	44.8	DR-402	B,C,F						1.100	21.1	10.800	
											2.200	55.4	35.600	Totals

REMOVAL OF STEEL BEAM GUARDRAIL

- ① Lane(s) to which the installation is adjacent.
- ② Includes length of End Terminals and End Anchors.

Location				Removal of Guardrail	
No.	Direction of Traffic	Station to Station	Side		
SB		221+12.34	221+68.34	Lt	56.0
NB		221+01.62	221+57.62	Rt	56.0
SB		225+55.38	226+18.38	Lt	63.0
NB		225+44.66	226+07.66	Rt	63.0
					238.0

GRADING FOR GUARDRAIL INSTALLATIONS

Refer to EW-301

Location				Foreslope at Guardrail	Dimensions (Feet)							Earthwork		Remarks				
No.	Direction of Traffic	Station	Side		X1	Y1	X2	Y2	X3	Y3	X4	Y4	Z		Excavation Class 10	Embankment In Place		
1	SB	221+57.00	Lt	UAC	25.7	5.0								63.8	15.0	76.0	9.0	A,B
2	NB	221+45.90	Rt	UAC	25.7	5.0								63.8	15.0	76.0	14.0	A,B
3	SB	225+67.10	Lt	UAC	50.5	5.0	84.7	16.7						135.5	19.0	91.0	65.0	A,B
4	NB	225+56.00	Rt	UAC	35.0	5.0								85.9	16.0	80.0	132.0	A,B
														220.0		totals		

A: Material excavated for paved shoulders may be used for embankment.
B: All location stations measured from bridge sta. 223+56.5. See sheets U.1 & U.2 for additional information.

DELIVERY AND STOCKPILING

Item Description	Quantity	Units	Delivery Location	Contact Name & Number	Remarks
W-beam guardrail	56		A	Joel Monroe	A
	56			Area Supervisor	
	63			563-880-0084	
	63				
	238				total lineal feet

A: Salvage guardrail less posts, impact heads, and hardware. Deliver to Iowa DOT Maintenance yard Waukon, Iowa

MILLED RUMBLE STRIPS

See PV-12 and PV-13

* Calculated at 18" width for Shoulder.

Road Identification	Station to Station	Location		Installation Length	Fog Seal* (Milled Rumble Strip) Shoulder GAL	Effective Shoulder Width			Remarks	
		Shoulder Pavement Type	Rumble Strip Type (Centerline, Rt or Lt Shoulder)			L	PCC Paved	HMA Paved		Granular\ Earth
							FT	FT		FT
Proj. (63)	202+35.36	397+03.00	HMA	Left Shoulder	8"		189.34		205.2	
Proj. (64)	835+00.00	376+50.00	HMA	Left Shoulder	12"		459.10		497.4	
Proj. (63)	202+35.36	397+03.00	HMA	Right Shoulder	8"		189.34		205.2	
Proj. (64)	835+00.00	376+50.00	HMA	Right Shoulder	12"		459.10		497.4	
Proj. (63)	202+35.36	397+03.00	HMA	Centerline			189.34		0.0	
Proj. (64)	835+00.00	376+50.00	HMA	Centerline			459.10		0.0	
Lengths are adjusted for station equations										
Totals										
HMA Shoulders							PCC	HMA	Fog Seal	
PCC Shoulders							0.00	1296.89	1405.2	
PCC or HMA Shoulders							0.00	0.00	0.0	
HMA Centerlines								648.44		
PCC Centerlines							0.00			
PCC or HMA Centerlines							0.00	0.00		

REMOVAL OF PAVEMENT

Refer to Tabulation 102-5

* Not a Bid Item

Begin Station	End Station	Side	Pavement Type	Area		Saw Cut*	Remarks
				SY	LF		
221+48.30	221+68.30	Lt	PCC	17.8		20.0	Ex. pave. Shoulder at Guardrail
221+34.60	221+57.60	Rt	PCC	20.4		23.0	Ex. pave. Shoulder at Guardrail
225+55.40	225+78.40	Lt	PCC	20.4		23.0	Ex. pave. Shoulder at Guardrail
225+44.70	225+65.70	Rt	PCC	18.7		21.0	Ex. pave. Shoulder at Guardrail
243+30.00	245+30.00	Rt	HMA	44.4			Ex. pave. Shoulder. Incidental to Class 13
277+07.00	287+10.00	Lt	HMA	222.9			Ex. pave. Shoulder. Incidental to Class 13
289+70.00	375+00.00	Rt	HMA	1895.6			Ex. pave. Shoulder. Incidental to Class 13
315+10.00	321+50.00	Lt	HMA	142.2			Ex. pave. Shoulder. Incidental to Class 13
359+40.00	388+82.00	Lt	HMA	653.8			Ex. pave. Shoulder. Incidental to Class 13
831+60.00	815+70.00	Rt	HMA	530.0			Ex. pave. Shoulder. Incidental to Class 13
831+60.00	804+90.00	Lt	HMA	890.0			Ex. pave. Shoulder. Incidental to Class 13
808+88.00	801+50.00	Rt	HMA	164.0			Ex. pave. Shoulder. Incidental to Class 13
787+50.00	774+70.00	Rt	HMA	284.4			Ex. pave. Shoulder. Incidental to Class 13
878+50.00	762+18.00	Lt	HMA	2584.9			Ex. pave. Shoulder. Incidental to Class 13
762+18.00	743+75.00	Rt	HMA	409.6			Ex. pave. Shoulder. Incidental to Class 13
739+09.00	724+00.00	Lt	HMA	503.0			Ex. pave. Shoulder. Incidental to Class 13
708+44.00	698+42.00	Lt	HMA	1113.3			Ex. pave. Shoulder. Incidental to Class 13
699+89.00	671+37.00	Rt	HMA	3168.9			Ex. pave. Shoulder. Incidental to Class 13
669+32.00	653+00.00	Lt	HMA	544.0			Ex. pave. Shoulder. Incidental to Class 13
625+11.00	586+00.00	Lt	HMA	869.1			Ex. pave. Shoulder. Incidental to Class 13
625+11.00	586+00.00	Rt	HMA	869.1			Ex. pave. Shoulder. Incidental to Class 13
576+00.00	558+87.00	Rt	HMA	571.0			Ex. pave. Shoulder. Incidental to Class 13
547+70.00	532+75.00	Lt	HMA	498.3			Ex. pave. Shoulder. Incidental to Class 13
522+28.00	507+79.00	Rt	HMA	483.0			Ex. pave. Shoulder. Incidental to Class 13
497+00.00	461+60.00	Lt	HMA	1180.0			Ex. pave. Shoulder. Incidental to Class 13
456+20.00	446+00.00	Rt	HMA	340.0			Ex. pave. Shoulder. Incidental to Class 13
432+25.00	414+45.00	Lt	HMA	593.3			Ex. pave. Shoulder. Incidental to Class 13
414+45.00	377+50.00	Rt	HMA	1231.7			Ex. pave. Shoulder. Incidental to Class 13

PAVEMENT MARKING LINE TYPES

See PM-110

***MNY4 - Factor of 1.00 as value includes number of 4-inch passes to cover median nose area.

*BCY4 - Place on the same side of the roadway to match existing markings near the project.

**NPY4 - For estimating purposes only. No Passing Zone Lines will be located in the field.

BCY4: Broken Centerline (Yellow) @ 0.25

DCY4: Double Centerline (Yellow) @ 2.00

NPY4: No Passing Zone Line (Yellow) @ 1.25

SLW4: Solid Lane Line (White) @ 1.00

SLW2: Stop Line (White) @ 6.00

ELY4: Edge Line Left (Yellow) @ 1.00

Road ID	Station to Station	Dir. of Travel	Location			Length by Line Type (Unfactored)												Remarks			
			Marking Type	Side			BCY4*	DCY4	NPY4**	SLW4	SLW2	ELY4									
				L	C	R															
			Factored Total: Waterborne/Solvent Paint			37.86	818.46	406.04	15.65											Milling/CIPR	
			Bid Quantity: Painted Pavement Markings, Waterborne or Solvent-Based						1278.01												
			Factored Total: Waterborne/Solvent Paint			37.86	818.46	406.04	15.65											1st Lift	
			Bid Quantity: Painted Pavement Markings, Waterborne or Solvent-Based						1278.01												
			Factored Total: Waterborne/Solvent Paint			37.86	818.46	406.04	15.65											2nd Lift	
			Bid Quantity: Painted Pavement Markings, Waterborne or Solvent-Based						1278.01												
			Factored Total: Waterborne/Solvent Paint			37.86	818.46	406.04	15.65											Surface Lift	
			Bid Quantity: Painted Pavement Markings, Waterborne or Solvent-Based						1278.01												
			Bid Quantity: Grooves Cut for Pavement Markings						1278.01												
			Bid Quantity: Painted Pavement Markings, Waterborne or Solvent-Based						5112.00	3.00										Totals	
			Bid Quantity: Grooves Cut for Pavement Markings						1278.01												

UTILITIES

100-1D
10-18-05

Engineering Supervisor
Acentek (Telephone, & Fiber Distribution)
207 East Cedar St.
Houston, MN 55943-0360
(507) 896-6231 Cell: (507) 429-1020
bjerviss@acentek.net

Paul Foxwell
General Manager
Allamakee-Clayton Electric Cooperative, Inc. (Electric Transmission)
229 Hwy 51
Postville, IA 52162-0715
(563) 864-7611
pfoxwell@acrec.coop

Jacqueline Michaca
Field Engineering Process Specialist
Alliant Energy (Electric & Gas Distribution, Gas Transmission)
200 First Street SE
Cedar Rapids, IA 52401
(319) 786-4208
JacquelineMichaca@alliantenergy.com

Mary Montgomery
Real Estate and Right of Way Representative II
Alliant Energy (Gas & Fiber Transmission, Gas & Electric Distribution)
PO Box 351
Cedar Rapids, IA 52406-9874
(319) 786-4768
MaryMontgomery@alliantenergy.com

Chad Ruegnitz
Plant Manager
Alpine Communications (Cable TV & Telephone)
923 Humphrey Street PO Box 1008
Elkader, IA 52043
(563) 245-4000
cruegnitz@alpine-communications.com

Steve Parker
Manager of Engineering & Construction
Lumen Centurylink (Telephone, Fiber Transmission & Distribution)
2103 E. University Ave.
Des Moines, IA 50317
(515) 265-0968 Cell: (507) 358-1978
Steven.Parker4@lumen.com

UTILITIES

100-1D
10-18-05

Brent Geise
Engineer II
Lumen Centurylink (Telephone)
3565 Utica Ridge Rd
Bettendorf, IA 52722
(563) 355-2592 Cell: (563) 650-0147
Brent.Giese@CenturyLink.com

Craig Eggert
Construction Specialist
Mediacom Communications Corporation (Cable TV, Fiber Transmission & Distribution)
1240 Hwy 52 South
Chatfield, MN 55923
(563) 419-5160
Ceggert@mediacomcc.com

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	IOWA	347		8	179

LEGEND



- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage

**STA. 202+35.36
BEGIN PROJECT
BEGIN SECTION A (NB Stations)
Clayton/Allamakee County line
RP. 7.54**

**EQUATION:
STA. 223+96.40 Bk=
STA. 221+72.00 Ah**

**BRIDGE
FWHA: 13611
MAINT.: 0307.9S076**

DATE	BY	REVISION
		APPROVED FOR CONSTRUCTION
		NOTED FOR CONSTRUCTION




AS-BUILT PLANS, FOR INFORMATION ONLY
Clayton - Allamakee Co. IOWA, F.H. 24/3/1987

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	Iowa	377		2	170

ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.

FAIRVIEW TWP.
T. 96 N. R. 3 W
SEC. 34

STA. 231 + 45
END OF SEC. B
BEG. OF SEC. C



LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- - - Earth Shoulder Construction
- ← Drainage




AS-BUILT PLANS, FOR INFORMATION ONLY

ESTABLISHED WIDTH OF RIGHT OF WAY — FT.


FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	Iowa	347		10	172

EQUATION:
STA. 253+81.3 Bk=
STA. 253+67.20 Ah



LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage



R.C.	0	0	35	110	205	100	2710	1750	00	545	302	12	202	265	270	170	352	200	0	130	0	24	200	301	120	057	137.3	1702	159.9
E.C.	24	7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
F.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
B.F.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0


AS-BUILT PLANS, FOR INFORMATION ONLY
 Hillamakee COUNTY, PROJ. NO. FA 347 SHEET NO. 10

ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.


FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	Iowa	347		11	179

LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device
See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage



BENCH MARKS:
 #20 Sta. 275+34 R/R Spike in 24" Butternut tree So. of schoolhouse 86' Rt. ----- El. 629.53
 #21 Sta. 293+58 Spike in 36" Elm. So. of House 75' Lt. ----- El. 628.32



AS-BUILT PLANS, FOR INFORMATION ONLY



ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.

LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	Iowa	327		12	179


EQUATION:
STA. 326+85.2 Bk=
STA. 326+99.0 Ah



BENCH MARKS:
 No. 22. Sta. 305+85. R.R Spike in West side of 12" Basswood 25' Lt. --- El. 734.52
 No. 23. Sta. 311+72. R.R Spike in West side of 12" Oak 18' Rt. --- El. 754.01
 No. 24. Sta. 320+40. R.R Spike in West side of 15" Poplar 18' Rt. --- El. 831.30

AS-BUILT PLANS, FOR INFORMATION ONLY


ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.



FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS


LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage



EQUATION:
STA. 346+73.5 Bk=
STA. 348+36.9 Ah

Bench Marks:-
 #25 Sta. 333+12 R.R. Spk. in West Side of Lone 15" Oak on Fence Line.....200Lt.....El. 935.89
 #26 Sta. 352+94 R.R. Spk. in Croch of Twin 18" Oak.....93Lt.....El. 1001.92



AS-BUILT PLANS, FOR INFORMATION ONLY
 ALLAMAKEE COUNTY, PROJ. NO. FA 347 SHEET NO. 13

ESTABLISHED WIDTH OF
RIGHT OF WAY _____ FT.

FEDERAL LAND BANK OF OMAHA

CULTIVATED

$\Delta = 41^{\circ}23'Lt$
 $D = 3'$
 $T = 7214$
 $L = 13794$
 $E = 1317$
 $R = 13100$


CULTIVATED

FEDERAL LAND BANK
OF OMAHA


Thomas Road
Sta. 363+05

Fairview Hts. Ln.
Sta. 362+45

Ref to POST 893' Back of PT




Ref to PI Sta 378+270



FAIRVIEW TWP
T.96N.R.3W

SEC. 21

Ref to PT Sta 387+646



FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	Iowa	347		14	179

LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage

MEADOW

MARGARET BAKER


Superelevate Curve

$\Delta = 35^{\circ}56'Lt$
 $D = 2'$
 $T = 9291$
 $L = 17967$
 $E = 1468$
 $R = 28650$

Sta 367+00
D.A. = 2 1/2 Ac. P.
Place 24"x60"
Conc. Pipe
Rd. Contr. to
Build dyke at
Inlet.

Sta 377+63
D.A. = 2 1/2 Ac. P.
Place 24"x48"
Conc. Pipe
at Sta 378+00
Rd. contr. to
leave dyke
of inlet.



BENCH MARKS:
No 27 Sta 363+45 RR Spike in East Side of 18" Maple in Fence Cor. 90' Lt. --- El. 11006.22
No 28 Sta 378+42 Spike in 24" Oak Third Tree in Row 84' Rt. --- El. 11366.69
No 29 Sta 387+10 Spike in 18" Lone Hickory 12' Lt. --- El. 10999.03



AS-BUILT PLANS, FOR INFORMATION ONLY
Allamakee COUNTY, PROJ. NO. 07-24 SHEET NO. 14

ESTABLISHED WIDTH OF RIGHT OF WAY _____ FT.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	Iowa	347		15	179





LEGEND


- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage

AS-BUILT PLANS, FOR INFORMATION ONLY


TYPICAL CROSS SECTIONS



DETAILS OF P.C. CONC. CURB & GUTTER



NOTE: See Paving Cross Section - Sheet No. 2.



TABULATION OF SHOULDER MATERIAL AVAILABILITY AREAS

LOCATION STATION TO STATION	SIDE	ESTIMATED QUANTITY AVAILABLE CU. YDS.
78 to 85	Left	3,000 C. Y.
127 to 136	Left	18,000 C. Y.
143 to 146	Right	7,000 C. Y.
147 to 150	Right	2,000 C. Y.
192 to 195	Left	2,000 C. Y.
276 to 281	Left	2,000 C. Y.
295 to 305	Left	4,500 C. Y.
328 to 335	Left	9,000 C. Y.
465 to 473	Left	6,000 C. Y.
581 to 587	Left	45,000 C. Y.
593 to 596	Right	2,500 C. Y.
575 to 577	Left	1,000 C. Y.
615 to 619	Left	2,000 C. Y.
627 to 635	Right	2,500 C. Y.
691 to 697	Right	10,000 C. Y.

TABULATION OF SUPERELEVATED CURVES

P.I. STA.	Δ	D	e	l
1786+68.5	19°-17' Rt	5°	0.040	Spiral
1+59.5	9°-33' Lt	3°	0.066	180'
17+13.2	16°-58 1/2' Lt	2°	0.047	Spiral
28+01.3	20°-12 1/2' Rt	3°	0.066	Spiral
44+76.9	9°-57' Rt	3°-30'	0.072	Spiral
53+64.3	38°-00' Lt	4°	0.076	Spiral
71+76.7	2°-53' Rt	0°-30'	R.C.	175'
147+91.4	36°-09 1/2' Rt	3°	0.066	Spiral
192+38.8	44°-40 1/2' Rt	4°	0.076	Spiral
211+04.7	46°-10' Lt	5°	0.080	Spiral
230+34.1	31°-51' Rt	2°-30'	0.057	Spiral
273+66.4	27°-14' Rt	4°	0.076	Spiral
294+90.6	38°-06' Lt	3°-45'	0.074	Spiral
348+36.7	19°-37' Rt	2°	0.047	Spiral
366+09.4	3°-06' Rt	0°-30'	R.C.	175'
384+22.2	17°-04' Lt	3°	0.066	175'
419+75.6	37°-31' Rt	2°	0.047	Spiral
451+29.5	24°-01' Lt	3°	0.066	Spiral
473+42.9	34°-27' Rt	4°	0.076	Spiral
514+97.4	34°-59' Lt	4°	0.076	Spiral
540+06.4	38°-47' Rt	4°	0.076	Spiral
564+98.6	42°-24' Lt	5°	0.080	Spiral
599+25.5	16°-35' Lt	2°	0.047	Spiral
616+48.1	27°-29 1/2' Rt	3°	0.066	Spiral
645+04.3	10°-06' Rt	2°	0.047	Spiral
661+36.0	50°-06' Rt	4°	0.076	Spiral
690+65.3	102°-06 1/2' Lt	4°	0.076	Spiral
703+74.6	20°-08' Rt	3°-30'	0.072	Spiral
732+03.0	51°-47' Rt	5°	0.080	Spiral
753+62.8	63°-12' Lt	5°	0.080	Spiral
768+94.1	27°-51 1/2' Rt	3°	0.066	Spiral
782+50.0	3°-53' Rt	0°-30'	R.C.	175'
800+22.6	3°-27' Lt	0°-30'	R.C.	175'
815+96.4	33°-29' Rt	3°	0.066	Spiral
826+06.5	19°-26' Lt	4°	0.076	Spiral

e = Rate of superlevation in ft. per ft. of width.

l = Length of transition from normal section to full superlevation.

AS-BUILT PLANS, FOR INFORMATION ONLY

FAIRVIEW TWP
T. 96. N. R. 3 W.

LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage


PURCHASED FROM Helen McCormick, P.O. Acres
 Helen McCormick, P.O. Acres
 McCormick & Emmert J. McCormick
 ACQUIRED September 28, 1962
 CONSIDERATION \$ 725.00
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 520-521
 COUNTY RECORDED Allamakee

ACCESS CONTROL ACQUIRED
 STA. 814+38 ON NORTH SIDE
 TO STA. 824+38 ON NORTH SIDE
 STA. 0+01.9 ON RT. & LT. SIDES
 TO STA. 5+01.9 ON RT. & LT. SIDES


EQUATION: (Section line)
END SECTION A 397+03.0 (NB Stations)
BEGIN SECTION B 835+00.0 (SB Stations)
R.P. 11.32

1.83 Acres
 PURCHASED FROM Mabel E. Whorton
 ACQUIRED August 2, 1962
 CONSIDERATION \$ 1,619.70
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 539-540
 COUNTY RECORDED Allamakee

ACCESS CONTROL ACQUIRED
 STA. 816+88 I.P.L. SOUTH SIDE
 TO STA. 826+00 ON SOUTH SIDE




SW-SW
 A = 19° 26' LT
 D = 4° 00' V
 L = 200' V
 T = 345.44
 E = 22.05 V
 G = 4° 00' V
 P = 1.16 V
 K = 99.98 V
 X = 199.90 V
 Y = 4.65 V
 LT = 133.37 V
 ST = 66.70 V
 LC = 199.96 V




Revised Dec 11, 1963

AS-BUILT PLANS, FOR INFORMATION ONLY

ED NO.	STAT.	PRJ. NO.	YEAR	SHEET NO.	TOTAL SHEETS
1	1	F-347(4)		31	55



PURCHASED FROM Emmett J. McCormick & Dorothy McCormick
 ACQUIRED October 4, 1962
 CONSIDERATION \$ 2,709.00
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 497-498
 COUNTY RECORDED Allamakee




LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage

Revised Dec. 11, 1963


AS-BUILT PLANS, FOR INFORMATION ONLY



PURCHASED FROM Ralph L. Brown & Catherine A. Brown
 ACQUIRED September 27, 1962
 CONSIDERATION \$ 1,969.75
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 517-518
 COUNTY RECORDED Allamakee

BENCH MARKS

No. 55 Sta. 766+70 2 NAILS IN JAIL POLE
 No. 56 Sta. 777+30 2 NAILS IN POWER POLE
 No. 57 Sta. 791+60 2 NAILS IN JAIL POLE
 No. 58 Sta. 795+31.5 T.H.C. BM IN R.Y.R. R.C.B. 4" WIDE 14" HIGH
 No. 59 Sta. 795+00 2" X 2" R.C. BOX 5' V. 150'




LEGEND


- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage

Revised Dec. 11, 1963

AS-BUILT PLANS, FOR INFORMATION ONLY





2.9 Aves
 PURCHASED FROM W.H. JOHANNMEIER & CATHERINE A. BROWN
 ACQUIRED August 7, 1962
 CONSIDERATION \$ 1,140
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 123
 COUNTY RECORDED Allamakee Co.



FED. ROAD DIST. NO.	STATE	PROJ. NO.	SECTION	SHEET NO.	TOTAL SHEETS
5	IOWA	F-347(4)		28	40

54 7.1 Acres
 PURCHASED FROM Cleophus A. Nicholson & Catharine Nicholson
 ACQUIRED October 18, 1962
 CONSIDERATION \$2,296.00
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 445-446
 COUNTY RECORDED Allamakee

FAIRVIEW TWP
 T96N E3W
 SEC. 7.




LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage

AS-BUILT PLANS, FOR INFORMATION ONLY

FED. ROAD DIST.	STATE	PR. NO.	F. A. PLAN	HEET	TOTAL
5	IWA	F-347(4)		27	210



52
 127 Acres
 PURCHASED FROM Frank Basteel
 ACQUIRED October 8, 1962
 CONSIDERATION \$ 989.50
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE A94
 COUNTY RECORDED Allamakee

Note: See Sheet 40 For Sideroad Details


51
 10.26 acres
 PURCHASED FROM John F. Kelly & Clara Kelly
 ACQUIRED September 6, 1962
 CONSIDERATION \$ 4,699.60
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 501 & 502
 COUNTY RECORDED Allamakee

Note: See Sheet 41 For Sideroad Details

Sta. 706+99.1
 5'x6'x40.2 R.C.B. Cattleway
 Cult. cont. to extend across structure 7.37'
 Lt and 18.20 Rt with 5'x6' R.C.B. cattleway
 Compaction of backfill by road contractor
 CLEOPHUS A. & CATHARINE NICHOLSON
 NW-NW
 Warranty Deed

53
 LAWRENCE & MARY WAGNER
 No 49A Sta 685+76 RESPIRATOR
 No 50 Sta 694+48 Split Pole Farm Yard

54
 Sta 698+34.2-175.2 South SW Corner of Section 7
 Pole Farm Yard
 90' Lt. Elev 1087.94
 1087.94




$\Delta = 10^{\circ} 06' R$
 $D = 2^{\circ} 00'$
 $L = 200'$
 $T = 353.20'$
 $E = 117'$
 $\Delta = 2^{\circ} 00'$
 $P = 0.58'$
 $K = 10000'$
 $X = 199.98'$
 $Y = 2.33'$
 $L = 133.34'$
 $S = 66.67'$
 $L = 199.99'$
 $\Delta = 6^{\circ} 06' R$
 $D = 2^{\circ} 00'$
 $T = 152.45'$
 $L = 305.00'$
 $E = 404'$
 $R = 28650'$

Sta 650+33
 Prop Field Ent Rt
 Purchased from John F. Kelly & Clara Kelly
 Acquired September 6, 1962
 Consideration \$4,699.60
 Title by Warranty Deed
 Recorded in Book 87 Page 501+502
 County Recorded Allamakee

$\Delta = 50^{\circ} 06' R$
 $D = 4^{\circ} 00'$
 $T = 820.63'$
 $L = 300'$
 $E = 151.65'$
 $\Delta = 6^{\circ} 00'$
 $P = 2.62'$
 $K = 149.95'$
 $X = 299.67'$
 $Y = 10.46'$
 $L = 200.11'$
 $S = 100.10'$
 $L = 299.85'$
 $\Delta = 38^{\circ} 06' R$
 $D = 4^{\circ} 00'$
 $T = 494.64'$
 $L = 952.50'$
 $E = 83.00'$
 $R = 1432.5'$

Purchased from Frank Bastel
 Acquired October 8, 1962
 Consideration \$989.50
 Title by Warranty Deed
 Recorded in Book 87 Page 494
 County Recorded Allamakee

BENCH MARKS:
 No 47B Sta 654+00 176 BM in E.R. ROW of dist. ECB 50' L. ELEV. 1133.07
 No 48 Sta 654+33 176 BM in E.R. ROW of dist. ECB 50' L. ELEV. 1133.07






LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage

Revised Dec. 11 1963

(A6) 10.7 ACRES
 PURCHASED FROM John J. Lloyd
 ACQUIRED _____
 CONSIDERATION _____
 TITLE BY Condemnation
 RECORDED IN BOOK _____ PAGE _____
 COUNTY RECORDED _____

(A8) 2.26 ACRES
 PURCHASED FROM Mary Egan
 ACQUIRED August 22, 1962
 CONSIDERATION 870.60
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 506
 COUNTY RECORDED Allamakee





DATE	NO	YEAR	TOTAL SHEETS
1963	347(4)	24	55

EQUATION:
STA. 604+37.07 Bk=
STA. 605+01.60 Ah

$\Delta = 16^\circ 35'$
 $D = 2^\circ 00'$
 $L_s = 200'$
 $T_s = 517.55'$
 $E_s = 30.90'$
 $B_s = 2'00"$
 $P = 0.58'$
 $K = 100.00'$
 $X_c = 199.98'$
 $Y_c = 2.33'$
 $LT = 133.34'$
 $ST = 66.67'$
 $LC = 199.99'$

$\Delta = 27^\circ 29' R$
 $D = 3^\circ 00'$
 $L_s = 867.41'$
 $E_s = 57.3'$
 $B_s = 3000'$
 $P = 0.87'$
 $K = 9999'$
 $X_c = 199.95'$
 $Y_c = 3.49'$
 $LT = 193.35'$
 $ST = 66.68'$
 $LC = 199.98'$



LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage

Revised Dec. 11, 1963



ALLAMAKEE COUNTY AS-BUILT PLANS, FOR INFORMATION ONLY

PROJECT NO.	FILE NO.	SHEET	TOTAL SHEETS
F-347(1)		25	55

LINTON TWP
T 96 N. R 4 W

1.24 Acres
PURCHASED FROM Lee Wilkins & Mildred Wilkins
ACQUIRED October 11, 1962
CONSIDERATION \$1,891.10
TITLE BY Warranty Deed
RECORDED IN BOOK 87 PAGE 570
COUNTY RECORDED Allamakee

10.26 Acres
PURCHASED FROM John F. Kelly & Clara Kelly
ACQUIRED September 6, 1962
CONSIDERATION \$4,679.60
TITLE BY Warranty Deed
RECORDED IN BOOK 87 PAGE 501+502
COUNTY RECORDED Allamakee




LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage

AS-BUILT PLANS, FOR INFORMATION ONLY
ALLAMAKEE COUNTY PROJECT No. F-347(1) SHEET No. 25 OF 55

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	IOWA	F-347(1)		23	55



LEGEND


- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage

1160	1150	1140	1130	1120	1110	1100	1090	1080	1070	1060	1050	1040	1030	1020	1010	1000	990	980	970	960	950	940	930	920	910	900	890	880	870	860	850	840	830	820	810	800	790	780	770	760	750	740	730	720	710	700	690	680	670	660	650	640	630	620	610	600	590	580	570	560	550	540	530	520	510	500	490	480	470	460	450	440	430	420	410	400	390	380	370	360	350	340	330	320	310	300	290	280	270	260	250	240	230	220	210	200	190	180	170	160	150	140	130	120	110	100	90	80	70	60	50	40	30	20	10	0
------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	----	----	----	----	----	----	----	----	----	---

ALLAMAKEE COUNTY AS-BUILT PLANS, FOR INFORMATION ONLY OF 210 55


LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device
See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage




$\Delta = 38^\circ - 47' \text{ Rt.}$
 $D = 4^\circ - 00'$
 $L_s = 300'$
 $T_s = 655.07'$
 $E_s = 89.0'$
 $D_s = 6^\circ - 00'$
 $P = 2.62'$
 $K = 149.95'$
 $X = 299.67'$
 $Y = 10.40'$
 $L.T. = 200.12'$
 $S.T. = 100.10'$
 $L.C. = 299.85'$
 $R = 1432.5'$

BENCH MARKS:
 No 38 Sta 537+14 2 Nails in Power Pole 51' Lt Elev. 1150.84'
 No 39 Sta 546+60 "x" ON First step of House 80' Rt Elev. 1154.07'



Revised Dec 11, 1963

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FIN. YEAR	SHEET NO.	TOTAL SHEETS
	IOWA	F-347(4)		21	55




5.1 Acres
 PURCHASED FROM Fred L. Snitker & Ruby R. Snitker
 ACQUIRED October 1, 1962
 CONSIDERATION \$ 3097.00
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 541 & 542
 COUNTY RECORDED Allamakee

244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------

LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage





AS-BUILT PLANS, FOR INFORMATION ONLY

PAINT CREEK TWP
T 37 N - R 4 W



LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device
See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- Drainage



Revised Dec 11, 1963

AS-BUILT PLANS, FOR INFORMATION ONLY




435	440	445	450	455	460	465
67.123	67.020	66.865	66.760	66.523	66.470	66.257
66.167	66.057	65.857	65.727	65.527	65.327	65.127
64.927	64.727	64.527	64.327	64.127	63.927	63.727
63.527	63.327	63.127	62.927	62.727	62.527	62.327
62.127	61.927	61.727	61.527	61.327	61.127	60.927
60.727	60.527	60.327	60.127	59.927	59.727	59.527
59.327	59.127	58.927	58.727	58.527	58.327	58.127
57.927	57.727	57.527	57.327	57.127	56.927	56.727
56.527	56.327	56.127	55.927	55.727	55.527	55.327
55.127	54.927	54.727	54.527	54.327	54.127	53.927
53.727	53.527	53.327	53.127	52.927	52.727	52.527
52.327	52.127	51.927	51.727	51.527	51.327	51.127
50.927	50.727	50.527	50.327	50.127	49.927	49.727
49.527	49.327	49.127	48.927	48.727	48.527	48.327
48.127	47.927	47.727	47.527	47.327	47.127	46.927
46.727	46.527	46.327	46.127	45.927	45.727	45.527
45.327	45.127	44.927	44.727	44.527	44.327	44.127
43.927	43.727	43.527	43.327	43.127	42.927	42.727
42.527	42.327	42.127	41.927	41.727	41.527	41.327
41.127	40.927	40.727	40.527	40.327	40.127	39.927
39.727	39.527	39.327	39.127	38.927	38.727	38.527
38.327	38.127	37.927	37.727	37.527	37.327	37.127
36.927	36.727	36.527	36.327	36.127	35.927	35.727
35.527	35.327	35.127	34.927	34.727	34.527	34.327
34.127	33.927	33.727	33.527	33.327	33.127	32.927
32.727	32.527	32.327	32.127	31.927	31.727	31.527
31.327	31.127	30.927	30.727	30.527	30.327	30.127
29.927	29.727	29.527	29.327	29.127	28.927	28.727
28.527	28.327	28.127	27.927	27.727	27.527	27.327
27.127	26.927	26.727	26.527	26.327	26.127	25.927
25.727	25.527	25.327	25.127	24.927	24.727	24.527
24.327	24.127	23.927	23.727	23.527	23.327	23.127
22.927	22.727	22.527	22.327	22.127	21.927	21.727
21.527	21.327	21.127	20.927	20.727	20.527	20.327
20.127	19.927	19.727	19.527	19.327	19.127	18.927
18.727	18.527	18.327	18.127	17.927	17.727	17.527
17.327	17.127	16.927	16.727	16.527	16.327	16.127
15.927	15.727	15.527	15.327	15.127	14.927	14.727
14.527	14.327	14.127	13.927	13.727	13.527	13.327
13.127	12.927	12.727	12.527	12.327	12.127	11.927
11.727	11.527	11.327	11.127	10.927	10.727	10.527
10.327	10.127	9.927	9.727	9.527	9.327	9.127
8.927	8.727	8.527	8.327	8.127	7.927	7.727
7.527	7.327	7.127	6.927	6.727	6.527	6.327
6.127	5.927	5.727	5.527	5.327	5.127	4.927
4.727	4.527	4.327	4.127	3.927	3.727	3.527
3.327	3.127	2.927	2.727	2.527	2.327	2.127
1.927	1.727	1.527	1.327	1.127	0.927	0.727
0.527	0.327	0.127	0.000	0.000	0.000	0.000

LEGEND
 NOTE BOOK ALIGNMENT CHECKED
 NO. OF WY CHECKED
 NO.

LEGEND

- Silt Fence or Perimeter and Slope Sediment Control Device See Tabulations 100-17, 100-18, & 100-19.
- 570-11 or 570-12. See sheets U3, U4, & U5
- Rock Erosion Control. See Tabulation 100-23.
- Earth Shoulder Construction
- ← Drainage




39
 PURCHASED FROM Willis E. Mason
 ACQUIRED October 9 1962
 CONSIDERATION \$2,790.60
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 489-493 17C.
 COUNTY RECORDED Allamakee

39
 WILLIS E. MASON
 Warranty Deed
 SE-SE
 ACCESS CONTROL ACQUIRED

STA. 376+50.0
END PROJECT
END SECTION B
 R.P. 19.78

35
 PURCHASED FROM Marlyn Bente
 ACQUIRED August 23, 1962
 CONSIDERATION \$883.00
 TITLE BY Warranty Deed
 RECORDED IN BOOK 87 PAGE 511 & 512
 COUNTY RECORDED Allamakee

BENCH MARKS:
 No. 27 Sta. 389+51.5 14CBM in Pt. Hwy of exl. RCB 17.24 Elev. 1197.74
 No. 28 Sta. 389+51.5 14CBM in Pt. Hwy of exl. RCB 4.17 Elev. 1197.74



Revised Dec. 11, 1963

AS-BUILT PLANS, FOR INFORMATION ONLY

511 TRAVEL RESTRICTIONS

Route	Direction	County	Location Description	Feature Crossed	Object Type	Maint. Bridge No., Structure ID, or FHWA No.	Type of Restriction	Existing Measurement	Construction Measurement	Construction Measurement as Signed	Projected As Built Measurement	Remarks
			none									

111-01
04-17-12

COORDINATED OPERATIONS


Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
RCB Culvert Replacement, FY2022	0.6 mi W of E Jct of US 52
Mississippi River in Marquette	Bridge Cleaning , FY 2025


108-23A
08-01-08

TRAFFIC CONTROL PLAN

Through traffic shall be maintained at all times.



SOUTH END GRADING & INSTALLATION




NORTH END GRADING & INSTALLATION

**SPECIAL DETAIL SHEET
PROPOSED GUARDRAIL & PAVED SHOULDER**

FILE NO.	ENGLISH	DESIGN TEAM Kelly\Nie\Suntken	COUNTY	PROJECT NUMBER	SHEET NUMBER U.1
SYSTEMTIME	SYSTEMDATE	USERNAME	DGNSPEC		

FAIRVIEW TWP.
T 96 N R 3 W
SEC. 34

Survey
 $\Delta = 61^{\circ} 48' 57''$
 $D = 5^{\circ} 00' 00''$
 $T = 686.03'$
 $L = 1236.32'$
 $E = 189.66'$
 $R = 1145.92'$
 $\theta = 2$ U.A.C.
 $S = 5$



STA. 221+00.00
 BEGIN PROJECT
 (RECONSTRUCTION) YELLOW


Sta. 222+99.2
 149.6' x 20' High Truss Bridge
 D.A. = 241 Sq. Mi. H. Mts.
 Bridge Contr. Move 37' Lt.
 Build 381' x 40' P.C. Bm. Bridge
 SKEW = 15°00'
 At STA. 223+56.50
 Design No. 479

LEGEND
 ■ Allamakee Clayton Elec. Co-op
 ● N.W. Bell Tel. Co.

C: 640
 Fr. M.L. Sta. 234+59.65 = 988

1979 AS-BUILT - FOR INFORMATION ONLY


See Standard Road Plans , , and for installation details.



① Silt Fence for Ditch Check may be substituted at no additional cost to the Contracting Authority.

Possible Contract Items:
 Perimeter and Slope Sediment Control Device
 Erosion Stone
 Class E Revetment
 Engineering Fabric

Possible Tabulations:
 100-19
 100-23
 100-34




REVISION	
1	10-19-21
570-11	
SHEET 1 of 1	

REVISIONS: Added cross section for staking details.


**TEMPORARY SEDIMENT CONTROL
 FOR CULVERT EXTENSION WITH
 EXPOSED SOIL**

See Standard Road Plans and for installation details.

① Silt Fence for Ditch Check may be substituted at no additional cost to the Contracting Authority.



NON-CONTINUOUS FLOW CULVERT




Possible Contract Items:
Perimeter and Slope Sediment Control Device

Possible Tabulations:
100-19
100-34

ROAD DESIGN DETAIL	REVISION	
	1	10-19-21
	570-12	
SHEET 1 of 2		


REVISIONS: Added cross section for staking details.

**TEMPORARY SEDIMENT CONTROL
FOR SHOULDER WIDENING WITH
EXPOSED SOIL**



① Silt Fence for Ditch Check may be substituted at no additional cost to the Contracting Authority.

CONTINUOUS FLOW CULVERT



ROAD DESIGN DETAIL	REVISION	
	1	10-19-21
	570-12	
SHEET 2 of 2		

REVISIONS: Added cross section for staking details.

**TEMPORARY SEDIMENT CONTROL
FOR SHOULDER WIDENING WITH
EXPOSED SOIL**