

### TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

Station	Cut				Fill						Checks (EW-102)		Topsoil										
	[1]	[2]	[3]	[4]	[5]	[6]	[7]	[8]	[9]	[10]	[11]	[12]	[13]	[14]	[15]	[16]	[17]	[18]	[19]	[20]	[21]	[22]	
	Total Cut Unadjusted Volume	Total Class 10 Unadjusted Volume	Topsoil Cut Volume	Manually Calculated Cut Adjustments (+/- Cut)	Total Cut Adjusted	Total Fill Unadjusted Volume	Existing Topsoil Stripping Undercut (+ Fill)	Manual Calculated Fill Adjustments (+/- Fill)	Total Fill Adjusted	Total Fill Adjusted w/ Weighted Average 1.3 Shrink Factor	Total Cut Adjusted Minus Fill w/ Shrink	Approx. Fill Vol. Below 5' & Above 20' w/ Shrink	Approx. Fill Volume Below 3' w/ Shrink	Topsoil Stripping Undercut Volume	Topsoil Placement Undercut Volume	Topsoil Placement With 1.4 Shrink Factor	Topsoil Stripping Minus Topsoil Placement w/Shrink						
CL393+13.9																							
388+24.18	15	6	9		6	20	9		29	38	-32	0	0	9	14	20	-11						
388+55.37	28	14	14		14	36	14		50	65	-51	0	0	14	24	34	-20						
388+90.34	24	15	9		15	71	9		80	104	-89	0	0	9	17	24	-15						
389+13.21	24	15	9		15	67	9		76	99	-84	0	0	9	16	22	-13						
389+35.92	23	11	12		11	25	12		37	48	-37	0	0	12	20	28	-16						
389+67.09	18	7	11		7	21	11		32	42	-35	0	0	11	17	24	-13						
390+09.79																							
CL393+13.9																							
Totals:	132	68	64	0	68	240	64	0	304	396	-328	0	0	64	108	152	-88						
<b>Excavation, Class 10, Roadway &amp; Borrow</b>					68	CY																	
<b>Embankment-In-Place</b>					253	CY																	
<b>Topsoil, Strip, Salvage &amp; Spread</b>					64	CY																	
<b>Topsoil, Furnish and Spread</b>					63	CY																	