

TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

| Station | Cut | | | | Fill | | | | | | Checks (EW-102) | | Topsoil | | | | [18] | [19] | [20] | [21] | [22] | | | | |
|--|-----------------------------|----------------------------------|--------------------|---|--------------------|------------------------------|--|---|---------------------|---|---|--|--|-----------------------------------|-----------------------------------|--|--|------|------|------|------|--|--|--|--|
| | [1] | [2] | [3] | [4] | [5] | [6] | [7] | [8] | [9] | [10] | [11] | [12] | [13] | [14] | [15] | [16] | [17] | | | | | | | | |
| | Total Cut Unadjusted Volume | Total Class 10 Unadjusted Volume | Topsoil Cut Volume | Manually Calculated Cut Adjustments (+/- Cut) | Total Cut Adjusted | Total Fill Unadjusted Volume | Existing Topsoil Stripping Undercut (+ Fill) | Manual Calculated Fill Adjustments (+/- Fill) | Total Fill Adjusted | Total Fill Adjusted w/ Weighted Average 1.3 Shrink Factor | Total Cut Adjusted Minus Fill w/ Shrink | Approx. Fill Vol. Below 5' & Above 20' w/ Shrink | Approx. Fill Volume Below 3' w/ Shrink | Topsoil Stripping Undercut Volume | Topsoil Placement Undercut Volume | Topsoil Placement With 1.4 Shrink Factor | Topsoil Stripping Minus Topsoil Placement w/Shrink | | | | | | | | |
| CL720+90.7 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 728+76.05 | 0 | 0 | 0 | | 0 | 0 | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | | | | | | |
| 728+87.09 | 8 | 5 | 3 | | 5 | 0 | | | 3 | 4 | 1 | 0 | 0 | 3 | 5 | 7 | -4 | | | | | | | | |
| 728+98.38 | 13 | 8 | 5 | | 8 | 1 | | | 5 | 6 | 0 | 0 | 5 | 8 | 11 | -6 | | | | | | | | | |
| 729+12.09 | 29 | 18 | 11 | | 18 | 9 | | | 11 | 20 | -8 | 0 | 11 | 20 | 28 | -17 | | | | | | | | | |
| 729+35.90 | 35 | 23 | 12 | | 23 | 8 | | | 12 | 20 | -3 | 0 | 12 | 15 | 21 | -9 | | | | | | | | | |
| 729+58.60 | 27 | 17 | 10 | | 17 | 3 | | | 10 | 13 | 0 | 0 | 10 | 11 | 15 | -5 | | | | | | | | | |
| 729+81.40 | 14 | 7 | 7 | | 7 | 3 | | | 7 | 10 | -6 | 0 | 7 | 9 | 13 | -6 | | | | | | | | | |
| 729+99.17 | 13 | 7 | 6 | | 7 | 2 | | | 6 | 8 | 0 | 0 | 6 | 8 | 11 | -5 | | | | | | | | | |
| 730+18.94 | 3 | 2 | 1 | | 2 | 0 | | | 1 | 1 | 1 | 0 | 1 | 2 | 3 | -2 | | | | | | | | | |
| 730+24.17 | 0 | 0 | 0 | | 0 | 0 | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | | | | | | | |
| 730+43.94 | | | | | | | | | | | | | | | | | | | | | | | | | |
| CL720+90.7 | | | | | | | | | | | | | | | | | | | | | | | | | |
| Totals: | 142 | 87 | 55 | 0 | 87 | 26 | 55 | 0 | 81 | 106 | -19 | 0 | 0 | 55 | 78 | 110 | -55 | | | | | | | | |
| Excavation, Class 10, Roadway & Borrow | | | | 87 | CY | | | | | | | | | | | | | | | | | | | | |
| Embankment-In-Place | | | | 15 | CY | | | | | | | | | | | | | | | | | | | | |
| Topsoil, Strip, Salvage & Spread | | | | 55 | CY | | | | | | | | | | | | | | | | | | | | |
| Topsoil, Furnish and Spread | | | | 40 | CY | | | | | | | | | | | | | | | | | | | | |