

### TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

Station	Cut				Fill						Checks (EW-102)		Topsoil				[18]	[19]	[20]	[21]	[22]			
	[1]	[2]	[3]	[4]	[5]	[6]	[7]	[8]	[9]	[10]	[11]	[12]	[13]	[14]	[15]	[16]	[17]							
	Total Cut Unadjusted Volume	Total Class 10 Unadjusted Volume	Topsoil Cut Volume	Manually Calculated Cut Adjustments (+/- Cut)	Total Cut Adjusted	Total Fill Unadjusted Volume	Existing Topsoil Stripping Undercut (+ Fill)	Manually Calculated Fill Adjustments (+/- Fill)	Total Fill Adjusted	Total Fill Adjusted w/ Weighted Average 1.3 Shrink Factor	Total Cut Adjusted Minus Fill w/ Shrink	Approx. Fill Vol. Below 5' & Above 20' w/ Shrink	Approx. Fill Volume Below 3' w/ Shrink	Topsoil Stripping Undercut Volume	Topsoil Placement Undercut Volume	Topsoil Placement With 1.4 Shrink Factor	Topsoil Stripping Minus Topsoil Placement w/Shrink							
721-H0872101																								
760+32.16	0	0	0		0	0			0	0	0	0	0	0	0	0	0							
760+50.00	16	11	5		11	0	5		5	7	5	0	5	10	14	14	-9							
760+75.00	17	11	6		11	0	6		6	8	3	0	6	10	14	14	-8							
761+00.00	0	0	0		0	0			0	0	0	0	0	0	0	0	0							
761+26.14																								
721-H0872101																								
Totals:	33	22	11	0	22	0	11	0	11	15	8	0	0	11	20	28	-17							
<b>Excavation, Class 10, Roadway &amp; Borrow</b>				15	CY																			
<b>Excavation, Class 10, Waste</b>				8	CY																			
<b>Topsoil, Strip, Salvage &amp; Spread</b>				11	CY																			
<b>Topsoil, Furnish and Spread</b>				13	CY																			