

TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

Station	Cut					Fill						Checks (EW-102)		Topsoil				[18]	[19]	[20]	[21]	[22]	
	[1]	[2]	[3]	[4]	[5]	[6]	[7]	[8]	[9]	[10]	[11]	[12]	[13]	[14]	[15]	[16]	[17]	[18]	[19]	[20]	[21]	[22]	
	Total Cut Unadjusted Volume	Total Class 10 Unadjusted Volume	Topsoil Cut Volume	Manually Calculated Cut Adjustments (+/- Cut)	Total Cut Adjusted	Total Fill Unadjusted Volume	Existing Topsoil Stripping Undercut (+ Fill)	Manual Calculated Fill Adjustments (+/- Fill)	Total Fill Adjusted	Total Fill Adjusted w/ Weighted Average 1.3 Shrink Factor	Total Cut Adjusted Minus Fill w/ Shrink	Approx. Fill Vol. Below 5' & Above 20' w/ Shrink	Approx. Fill Volume Below 3' w/ Shrink	Topsoil Stripping Undercut Volume	Topsoil Placement Undercut Volume	Topsoil Placement With 1.4 Shrink Factor	Topsoil Stripping Minus Topsoil Placement w/Shrink						
Summary:																							
CL393+13.9	132	68	64	0	68	240	64	0	304	396	-328	0	0	64	108	152	-88						
CL401+00	179	133	46	0	133	123	46	0	169	220	-87	0	0	46	73	103	-57						
CL720+90.7	142	87	55	0	87	26	55	0	81	106	-19	0	0	55	78	110	-55						
721-H0872101	33	22	11	0	22	0	11	0	11	15	8	0	0	11	20	28	-17						
CL973+45	550	371	179	65	436	1,011	179	60	1,250	1,625	-1,189	0	0	179	287	402	-223						
CL1053+74.6	163	109	54	88	197	157	54	13	224	292	-95	0	0	54	85	119	-65						
Project Totals:	1,199	790	409	153	943	1,557	409	73	2,039	2,654	-1,710	0	0	409	651	914	-505						
Excavation, Class 10, Roadway & Borrow				936	CY																		
Embankment-In-Place				1,324	CY																		
Excavation, Class 10, Waste				8	CY																		
Topsoil, Strip, Salvage, & Spread				409	CY																		
Topsoil, Furnish & Spread				364	CY																		